


WEAVER'S LANDING POOLHOUSE


SECTION 35, TOWNSHIP 17N, RANGE 5E,
VERNON TOWNSHIP, HANCOCK COUNTY, CR 700W & CR 650N
PROJECT LOCATION: 39° 52'47.3" N 85° 56'14.7" W
ZONED: PUD (ORDINANCE NO. 091118A)
CONSTRUCTION PLANS

PLANS PREPARED FOR:
D.R. HORTON - INDIANA, LLC d/b/a WESTPORT HOMES
9210 NORTH MERIDIAN STREET
INDIANAPOLIS, INDIANA 46260
PHONE: (317) 844-0433
FAX: (317) 844-0622
CONTACT: CHRIS MCKINNEY


PROJECT
LOCATION



AREA MAP
NO SCALE



SITE MAP
1"=200'



LOCATION MAP
NO SCALE

OPERATING AUTHORITIES & AREA UTILITIES

GAS VECTREN (GREENFIELD) 2345 E. Main St. Danville, IN 46122 317-718-3639 Holly Columbia	SANITARY & STORM MCCORDSVILLE PUBLIC WORKS 6280 W. CR 800 North McCordsville, IN 46055 317-335-3493 Ron Order	WATER CITIZENS ENERGY GROUP - WATER CWA Authority, Inc. 2150 Dr. Martin Luther King, Jr. Street Indianapolis, IN 46202 317-927-4351 Attn.: Brad Hostetter
ELECTRIC NINE STAR CONNECT (FORMERLY HANCOCK TELECOM) 2243 E. Main St. Greenfield, IN 46140 317-323-2090	TELEPHONE AT&T - DISTRIBUTION 240 N. Meridian St., Room 1791 Indianapolis, IN 46204 317-265-3050 Matt Spindler	CABLE TELEVISION BRIGHT HOUSE NETWORKS 3030 Roosevelt Ave Indianapolis, IN 46218 317-632-9077 Jason Kirkman
SCHOOL DISTRICT Mt. Vernon Community School Corp. 1806 West State Road 234 Fortville, IN 46040 Dr. Shane Robbins	TELEPHONE NINE STAR CONNECT (FORMERLY HANCOCK TELECOM) 2243 E. Main St. Greenfield, IN 46140 317-323-2090 Jennifer McMillan	CABLE TELEVISION COMCAST CABLEVISION 5330 East 65th Street Indianapolis, IN 46220 317-594-6509
FIRE DEPARTMENT McCordsville Fire Station 7580 Form Street McCordsville, IN 46055 317-335-2268 Attn.: Tom Alexander	POLICE MCCORDSVILLE POLICE DEPT. 6280 West CR 800 North McCordsville, IN 46055 317-335-2812	



REVISIONS		
NUMBER	DESCRIPTION	DATE

SHEET INDEX	
SHEET NO	DESCRIPTION
C100	TITLE SHEET
C102	SITE AND UTILITY PLAN
C110	GRADING AND DRAINAGE PLAN
C400	INITIAL & FINAL EROSION CONTROL PLAN
C500	DETAILS
	LANDSCAPING PLAN (By Others)
	TOWN OF McCORDSVILLE STANDARDS

PLANS PREPARED BY:
BANNING ENGINEERING
853 COLUMBIA ROAD, SUITE #101
PLAINFIELD, IN 46168
BUS: (317) 707-3700, FAX: (317) 707-3800
E-MAIL: Banning@BanningEngineering.com
WEB: www.BanningEngineering.com
CONTACT: ROBERT J. STATON

CONSTRUCTION DOCUMENTS

PROJECT MANAGER: _____ DATE: _____
THESE PLANS ARE NOT TO BE CONSIDERED FINAL OR TO BE UTILIZED FOR CONSTRUCTION UNLESS SIGNED AND DATED BY THE APPROPRIATE BANNING ENGINEERING PROJECT MANAGER.
THESE PLANS ARE NOT INTENDED TO BE REPRESENTED AS A RETRACEMENT OR ORIGINAL BOUNDARY SURVEY, A ROUTE SURVEY, OR A SURVEYOR LOCATION REPORT.




CERTIFIED BY: W. Chad Ziegler

Date: 10-28-19
Project No: 18003P-Pool
Sheet No:

C100

g:\012 P:\2018\18003P\PM\18003P\18003P-S1\Engineering\Sheet Files\PoolHouse\Sheets\18003P PoolHouse_s1plan.dwg Oct 28, 2019 - 2:49pm



DIMENSIONS ARE TO THE INSIDE FACE OF CURB UNLESS NOTED OTHERWISE.

PARKING SPACES ARE 9' WIDE UNLESS NOTED OTHERWISE.

PAVEMENT MARKINGS ARE 4" PAINTED WHITE UNLESS NOTED OTHERWISE.

ALL POOL PIPING PER ARCHITECT AND MECHANICAL CONTRACTOR.

FOR LEGEND, SEE SHEET C103.



SITE PLAN GENERAL NOTES

- All work shall be performed in conformance with the Subdivision Control Ordinance of the Town of McCordsville and all other ordinances which pertain to this type of work.
- No changes in or departure from the plans or specifications shall be made without prior approval, in writing, by the Engineer.
- The Contractor shall be responsible for obtaining all Federal, State, County and Town of McCordsville permits, or any other permits required.
- Before construction begins, the Contractor shall field verify the location of all utilities shown on the plans, and contact all utility companies to locate all mains, conduits, service lines, etc., in the construction area, and shall protect all such utilities during construction.
- Before construction begins, the Contractor shall notify the Owners, and/or the Owner's Engineer, so that an inspector may be present.
- It shall be the responsibility of the Contractor to maintain quality control throughout the project; failure to do so may result in removal and replacement of the defective work. It is recommended that the Owner have a qualified inspector on the job site at all times during construction.
- The Engineer shall be notified of all field tile located on the site during construction. All such field tile shall be incorporated into the storm sewer system so that it remains in working condition.
- Plans shall be bid as a working system. Any errors or omissions shall be brought to the attention of the Engineer prior to construction. In the event of the Contractor's failing to give such notice, they shall be held responsible for the results of any such errors or omissions, and the cost of rectifying the same.
- Geotechnical report is recommended by soil scientist / testing engineer prior to any construction.
- Liability Insurance Policy shall be furnished to the Owner before any work is started.
- The contractor shall notify the Town of McCordsville at least 72 hours prior to any bonded or bank credit letter site improvements are installed. A pre-construction meeting shall be set up with the Town of McCordsville, Contractor, engineer & owner prior to any construction.
- All accessible handicap pathways, sidewalks and drive crossings shall not exceed 5% running slope and 2% cross slope or the latest requirements of the Americans with Disabilities Act (ADA). Handicap ramps shall not exceed 1/12 slope and 2% cross slope or the latest requirements of the Americans with Disabilities Act (ADA).

UTILITY PLAN GENERAL NOTES

- Sanitary lateral piping and fittings shall comply with the Town of McCordsville standards which pertain to this type of work.
- A minimum horizontal distance of ten (10) feet shall be maintained between parallel water lines and sewer lines. Perpendicular or angled crossings of water and sewer lines shall generally be at a spacing of not less than eighteen (18) inches.
- Structural backfill is required when utility trench openings encroach within 5 feet of a street, private drive, or sidewalk.

PLANS NOTES

- (A) LIGHT DUTY ASPHALT, SEE DETAIL ¹/_{C500}
- (B) R/W PAVEMENT (SEE TOWN OF MCCORDSVILLE STANDARDS ON SHEET 2: LOCAL ARTERIAL PAVEMENT SECTION)
- (C) CONCRETE COLLAR, SEE DETAIL ³/_{C500}
- (D) CONCRETE SIDEWALK, SEE DETAIL ⁸/_{C500}
- (E) INTEGRAL CURB / WALK, SEE DETAIL ⁴/_{C500}
- (F) 6" STANDING CURB, SEE DETAIL ⁵/_{C500}
- (G) R/W HANDICAP RAMP (SEE TOWN OF MCCORDSVILLE STANDARDS ON SHEET 5)
- (H) HANDICAP RAMP, SEE DETAIL ⁶/_{C500}
- (I) HANDICAP PAINTED SYMBOL, SEE DETAIL ⁷/_{C500}
- (J) 4" PAINTED BLUE PAVEMENT STRIPING
- (K) 4" PAINTED WHITE CROSSWALK PAVEMENT STRIPING
- (L) TIE INTO EXISTING CURB; TAPER 6" CURB DOWN IN LAST 5 FEET
- (M) CONCRETE PAVEMENT, SEE DETAIL ²/_{C500}
- (N) BICYCLE RACK / CONCRETE PAD; (RACK PER OWNER) (USE CONCRETE SIDEWALK PAVEMENT)
- (O) FENCE (PER OWNER)
- (P) R/W SIDEWALK (SEE TOWN OF MCCORDSVILLE STANDARDS ON SHEET 5)
- (Q) TIE WATER SERVICE TO EXISTING WATER METER PIT; CONTRACTOR TO COORDINATE WITH CITIZENS ENERGY GROUP WITH WATER CONNECTION FOR REQUIRED DETAILS AND MECHANICAL CONTRACTOR FOR REQUIRED SIZE
- (R) CONNECT TO EXISTING SEWER LATERAL; CONTRACTOR TO VERIFY EXISTING LOCATION AND DEPTH PRIOR TO CONSTRUCTION
- (S) PROPOSED ELECTRIC / COMMUNICATION SERVICE LINES IN CONDUIT; VERIFY WITH APPROPRIATE SERVICE PROVIDERS AND MECHANICAL CONTRACTOR

SITE PLAN & UTILITY PLAN WEAVER'S LANDING POOL HOUSE WEAVERS LANDING, SEC. 1; "C.A. A" MCCORDSVILLE, INDIANA



W. Chad Ziegler

BANNING
ENGINEERING
853 COLUMBIA ROAD, SUITE #101
PLAINFIELD, IN 46168
BUS: (317) 707-3700 FAX: (317) 707-3800
E-MAIL: Banning@BanningEngineering.com
WEB: www.BanningEngineering.com

Project No: 18003P-Pool

Sheet No:



ELEVATION= 853.20

g:\atlz P:\2018\18003P\PM\18003P\18003P-PoolHouse\Sheets\18003P-PoolHouse_erosion_control.dwg Oct 26, 2019 - 3:02pm



SOILS DESCRIPTIONS

BROOKSTON SERIES

Br Brookston silt loam (0-2% slopes)
Brookston Series – (B/D) This is a very poorly drained nearly level soil on uplands. Permeability is moderately slow. The pH of the surface layer in non-limed areas is 6.0 to 7.3. This soil is hydric. Basements are not recommended because of wetness concerns. This soil responds well to tile drainage; it is not highly erodible. There is a seasonal high water table associated with this soil. High potential frost action and moderate shrink-swell potential are also construction concerns.

CROSBY SERIES

CrA Crosby silt loam (0-3% slopes)
Crosby Series – (C) This is a somewhat poorly drained gently sloping soil on uplands. Permeability is very slow. The pH of the surface layer in non-limed areas is 5.1 to 6.5. This soil responds well to tile drainage; it is potentially highly erodible. There is a seasonal high water table associated with this soil. High potential frost action and moderate shrink-swell are also construction concerns.

MIAMI SERIES

MmA Miami silt loam (0-2% slopes, eroded); MmB2 Miami silt loam (2-6% slopes, eroded)
Miami Series – (B) This is a well drained gently sloping soil on uplands. Permeability is moderate to moderately slow. The pH of the surface layer in non-limed areas is 5.6 to 7.3. This soil is potentially highly erodible. Moderate potential frost action and moderate shrink-swell are also construction concerns.

SOILS MAP

NO SCALE

EROSION CONTROL GENERAL NOTES

- Only those areas within the designated construction limits are to be disturbed during construction.
- Contractor to provide temporary surface stabilization of any area scheduled or likely to remain inactive for a period of 15 days or more.
- Contractor to provide temporary signage near the entrance of the project identifying the responsible parties and other information about the project. Contractor is responsible for obtaining any necessary sign permits for this.
- Contractor shall implement design concepts and storm water quality measures, which are shown on this plan, to reduce post construction pollutants discharging from the site.
- All erosion control measures shall meet the Phase 2 IDEM Rule 327 IAC 15-5 requirements.
- Refer to the "Indiana Storm Water Quality Manual", "The Urban Development Planning Guide", and Manufacturers Recommendations for installation for all required measures.
- Inspection and repair of erosion control measures shall be done weekly and after each $\frac{1}{2}$ " rainfall event.

- Setup a pre-construction meeting (at least 72 hours prior to construction) with Contractor, Developer, Engineer, and Town of McCordsville representative to discuss scheduling and sequencing of project.
- Contractor shall prepare a self-monitoring plan and procedure, including documentation of weekly self monitoring operations. These documents must be kept on file and made available upon request.
- Start construction log. This log will document the performance of each pollution prevention measure. A thorough site inspection should be completed weekly, and within 24 hours of every $\frac{1}{2}$ " rain event.
- Install construction entrance drive and construction staging area on site as delineated on this sheet.
- Establish concrete washout as delineated on this plan and associated details.
- Post the approved clean water permit issued by the Town of McCordsville. Notify IDEM at (317-233-1884) and the Town of McCordsville within forty-eight hours of the beginning of construction activities.
- Install perimeter silt fence and protection barriers.
- Remove trees and rubbish only as needed for construction.
- Begin mass earth work with the stripping of the topsoil. Stockpile topsoil in those areas designated on this plan. Any proposed offsite storage locations must receive prior written approval from the Developer and have a current clean-water permit. Temporary seed and mulch all stockpiles immediately upon completion.

FINAL EROSION CONTROL SEQUENCING

- Perform initial erosion control sequence.
- Rough grade site, install erosion control measures as required.
- Begin installation of the storm sewers. Install sediment barriers as storm sewers have been installed.
- Construct building.
- Install remaining utilities.
- Finish grade drive, parking areas, install curbs, stone base, asphalt and concrete. Install inlet protection as pavement installation is completed.
- Finish grade site and replace topsoil.
- Install erosion control blankets with permanent seeding, and other erosion control measures as shown.
- Temporarily seed and mulch all areas scheduled or likely to remain inactive for 15 days or more.
- Permanent seed and mulch all disturbed areas not covered by erosion control blankets or temporary seeding measures.
- After construction is completed, vegetation established and permission received from Plainfield representative, remove temporary erosion control measures.

EROSION CONTROL PLAN LEGEND

- | | | |
|--|---|---------|
| | EROSION CONTROL BLANKET W/PERMANENT SEEDING (NORTH AMERICAN GREEN S-150) SEE DETAIL ON SHEET C500 | 10 C500 |
| | PERMANENT SEEDING & MULCHING SEE DETAIL ON SHEET C500 | 11 C500 |
| | CURB INLET BASKET SEE DETAIL ON SHEET C500 | 12 C500 |
| | SILT FENCE INLET PROTECTION SEE DETAIL ON SHEET C500 | 13 C500 |
| | CONSTRUCTION LIMITS | |
| | SILT FENCE SEE DETAIL ON SHEET C500 | 14 C500 |

LATITUDE: 39°52'47.3" N
LONGITUDE: 85°56'14.7" W
HUC: 05120 2011 10020



INITIAL & FINAL EROSION CONTROL PLAN

WEAVER'S LANDING POOL HOUSE

WEAVERS LANDING, SEC. 1; "C.A. A"

MCCORDSVILLE, INDIANA



W. Chad Ziegler


BANNING
ENGINEERING
853 COLUMBIA ROAD, SUITE #101
PLAINFIELD, IN 46168
BUS: (317) 707-3700 FAX: (317) 707-3800
E-MAIL: Banning@BanningEngineering.com
WEB: www.BanningEngineering.com

Project No: 18003P-Pool

Sheet No:

C400


g:\p12\18033P\DW\18033P\18033P-S1\Engineering\Sheet Files\Poolhouse\Sheets\18033P Poolhouse_details.dwg Oct. 28, 2019 - 2:50pm



- Maintenance
1. Remove all accumulated sediment and debris weekly or after each 1/2" rainfall event.
 2. Remove sediment from bag after bag is 1/3 full.
 3. If bag is damaged, remove bag and replace with new.

INLET SACK PROTECTION (12) C500

NO SCALE



MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, then stabilize.

SILT FENCE (14) C500

NO SCALE

Stabilization Practice	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.
Permanent Seeding			A									
Dormant Seeding	B											B
Temporary Seeding			C	E								
Sodding			F									
Mulching	G											

A = Kentucky Bluegrass 40 lbs./acre; or 40 lbs. tall Fescue; plus 2 tons straw mulch/acre or add Annual Ryegrass 20 lbs./acre.

B = Kentucky Bluegrass 60 lbs./acre; or 40 lbs. tall Fescue; plus 2 tons straw mulch/acre or add Annual Ryegrass 30 lbs./acre.

C = Spring Oats 100 lbs./acre

D = Wheat or Rye 150 lbs./acre.

E = Annual Ryegrass 40 lbs./acre. (1 lb./1000 sq. ft.)

F = Sod

G = Straw Mulch 2 tons/acre.

** Irrigation needed during June, July, and/or September.

** Irrigation needed for 2 to 3 weeks after applying sod.

Lime and fertilizer to site specific soils tests or apply fertilizer at a rate of 1000 lbs. per acre or 12-12-12 or equivalent.

All swales shall be seeded with 2 lbs. Adelphi bluegrass and 2 lbs. Perennial Derby rye, or equivalent per 1000 square feet, mulch with one bale of straw per 1000 square feet. Fertilize with 5 lbs. of 20-5-5 per 1000 square feet unless specified otherwise.

SEEDING CHART (11) C500

NO SCALE

MAINTENANCE

Inspect weekly and after each 1/2" rainfall event, until the stand is successfully established. (Characteristics of a successful stand include: vigorous dark green or bluish-green seedlings; uniform density with nurse plants, legumes, and grasses well inter-mixed; green leaves; and the perennials remaining green throughout the summer, at least at the plant base.)

Plan to add fertilizer the following growing season according to soil test recommendations.


Repair damaged, bare, or sparse areas by filling any gullies, re-fertilizing, over- or re-seeding, and mulching. If plant cover is sparse or patchy, review the plant materials chosen, soil fertility, moisture condition, and mulching; then repair the affected area either by over-seeding or by re-seeding and mulching after re-preparing the seedbed.

If vegetation fails to grow, consider soil testing to determine acidity or nutrient deficiency problems. (Contact your SWCD or Cooperative Extension office for assistance.)

If additional fertilization is needed to get a satisfactory stand, do so according to the soil test recommendations.

NOTE: HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITICAL POINTS ALONG THE CHANNEL SURFACE.

REFER TO GENERAL STAPLE PATTERN GUIDE FOR CORRECT STAPLE RECOMMENDATIONS FOR CHANNELS.



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade, stabilize.

SILT FENCE INLET PROTECTION (13) C500


NO SCALE

CRITICAL POINTS

A. OVERLAPS AND SEAMS

B. PROJECTED WATER LINE

C. CHANNEL BOTTOM/SIDE SLOPE VERTICES



1. Prepare soil before installing blankets, including application of lime, fertilizer, and seed.
2. Begin at the top of the channel by anchoring the blanket in a 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
3. Roll center blanket in direction of water flow on bottom of channel.
4. Place blankets end over end (shingle style) with a 6" overlap. Use a double row of staggered staples 4" apart to secure blankets.
5. Full length edge of blankets at the top of side slopes must be anchored in 6" deep by 6" wide trench. Backfill and compact the trench after stapling.
6. Blankets on side slopes must be overlapped 4" over the center blanket and stapled. (2" for C350 matting)
7. In high flow channel applications, a staple check slot is recommended at intervals of 30 to 40 feet. Use a Row of staples 4" apart over entire width of the channel. Place a second row 4" below the first row in a staggered pattern.
8. The terminal end of the blankets must be anchored in a 6" deep x 6" wide trench. Backfill and compact the trench after stapling.

MAINTENANCE


*During vegetative establishment, inspect weekly and after each 1/2" rainfall event for any erosion below the blanket.

*If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

*After vegetative establishment, check the treated area periodically.

CHANNEL INSTALLATION (10) C500

NO SCALE



- NOTE:
1. SEE SILT FENCE DETAIL FOR MATERIAL SPECIFICATIONS
 2. SILT FENCE SHALL BE PREASSEMBLED BY SUPPLIER.

MAINTENANCE

*Inspect the silt fence weekly and after each 1/2" rainfall event.

*If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately.

*Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

*Take care to avoid undermining the fence during clean out.

*After the contributing drainage area has been