

K and K Fence Co., Inc.

www.kkfence.com

Proposal and Contract

Proposal Date:

July 10, 2020

Account Manager:

Matt Kreigh

Email:

mkreigh@kandkfence.com

Cell:

317-605-2998

Direct:

317-759-5880

Office:

317-359-5425 ext 113

Office Address:
6520 Brookville Road
Indianapolis, IN 46219

Remit Payment To:
PO Box 19833
Indianapolis, IN 46219

Customer Billing Address:
Customer: Town of McCordsville
Attention: Ron Crider
Address: 6280 W. 800 N.
City: McCordsville
State: IN **Zip Code:** 46055
P.O. #:
Office: 317-335-3493 **Cell:** 317-538-4408
Email: rcrider@mccordsville.org

Job Site Information:	Job #:
Job Name: Town of McCordsville	
Contact: Ron Crider	
Address: 6280 W. 800 N.	
City: McCordsville	
State: IN	Zip Code: 46055
County: Hancock	Township: Vernon
Office: 317-335-3493	Cell: 317-538-4408
Email: rcrider@mccordsville.org	

Proposal is Valid for 14 Days

K and K Fence, Inc. will have the Public and Private Underground Utilities Located

Furnish and install one 5' wide single swing gate, straighten three line posts, reattach top rail and retie fabric to top rail.	\$ 1,725.00
Furnish and install one 24'-26' wide sliding cantilever gate with nylon rollers and seting new tail post for the roller.	\$ 5,480.00
Furnish and install one Liftmaster SL595UL single phase 115V electric gate operator with thermostat controlled heater, free exit loop, safety vehicle loop sensor, safety photo beam, safety gate edge, fire department knox keyswitch, 7-day programable timer and one gooseneck stand.	\$ 10,975.00

Note: electric power to gate operator and transformer box, all conduits, and card reader/keypad to be by others.

Chain Link Fence Specifications:

9 Gauge, Black Vinyl Coated (KT) 2" Mesh
1-5/8" SS40 Top and Bracing Rail
2-1/2" SS40 Line Posts
3" SS40 Terminal Posts
4" SS40 Gate Posts
6 Gauge Bottom Tension Wire
All posts to be set in concrete footers

Note: Grounding of the fence and gate(s) is not the responsibility of the fence contractor and not included in the fencing scope of work for this contract. Grounding, when required, shall be completed by a licensed electrical contractor.

Our current lead time is 4 to 8 weeks from date of approval, weather permitting.

Total Installed Complete: \$ 18,180.00
Sales Tax Exempt

See below exclusions.

Unless specified above, these listed items are NOT included.

Sales Tax	Vacuum Extraction	Dirt Removal	Ground Penetrating Radar	Card Readers / Keypad
Fence Grounding	Core Drilling	Engineering / Testing	Electric Power / Conduits	Access Controls

Acceptance of Proposal and Contract:

Purchaser accepts that the above prices, specifications and conditions are satisfactory and hereby accepted. K and K Fence, Inc. is authorized to do the work as specified. This contract is payable in full upon substantial completion of work performed. This proposal, when accepted, becomes a contract between two parties and is not subject to cancellation. Should purchaser not fulfill the obligations of payment, purchaser will be liable for all court costs, attorney fees and other expenses incurred in the collection of any amount due for work performed. K and K Fence, Inc. will not be held responsible for any private underground utilities. This proposal and contract supersedes all other contracts pertaining to this project.

Printed Name:

Title:

Signature:

Date:

Purchase Order #:

Visa/MasterCard #:

Exp. Date:

CVV Code: