


# SUMMERTON AMENITY AREA CONSTRUCTION PLANS

## Lennar Homes of Indiana, LLC



### DEVELOPER:

ERIK ROBINSON  
LENNAR HOMES OF INDIANA, LLC  
11555 N. MERIDIAN ST., SUITE 400  
CARMEL, IN 46032  
317-659-3200  
erik.robinson@lennar.ocm

### CIVIL ENGINEER and SURVEYOR:

KYLE EICHHORN  
HWC ENGINEERING  
135 N. PENNSYLVANIA ST., SUITE 2800  
INDIANAPOLIS, IN 46204  
(317) 347-3663  
keichhorn@hwcengineering.com

ZONED SUMMERTON AMENDED PUD ORDINANCE NO. \_\_\_\_\_, AN  
ORDINANCE AMENDING THE TOWN OF MCCORDSVILLE ZONING  
ORDINANCE NO. 121410, AS AMENDED.  
DEVELOPMENT STANDARDS

#### AREA "A"

MINIMUM LOT AREA	7,200 SQ. FT
MINIMUM LOT WIDTH AT BUILDING LINE	60
MINIMUM FRONT YARD SETBACK	25 FEET
MINIMUM SIDE YARD SETBACK	5 FEET
MINIMUM REAR YARD SETBACK	15 FEET
MINIMUM LIVABLE FLOOR AREA	1,500 SF (SINGLE STORY) 1,800 SF (MULTI STORY)
MIN. GROUND FLOOR LIVING AREA	900 SF (MULTI STORY)
MAXIMUM LOT COVERAGE	60%
MAXIMUM HEIGHT - PRINCIPAL	35 FEET

PLAN COMMISSION APPROVAL	_____
DRAINAGE APPROVAL	_____
ADDRESS APPROVAL	_____
EROSION CONTROL APPROVAL	_____
COUNTY ENGINEER APPROVAL	_____
COUNTY SANITARIAN APPROVAL	_____
COUNTY COMMISSIONERS APPROVAL	_____



#### CONTACT INFORMATION:

CITIZENS ENERGY GROUP / CWA AUTHORITY, INC. (WATER)  
BRAD HOSTETLER  
2150 DR. MARTIN LUTHER KING JR. STREET  
INDIANAPOLIS, INDIANA 46202  
P: (317) 927-4351  
BHOSTETLER@CITIZENSENERGYGROUP.COM

MINESTAR CONNECT (Electric & Telecom)  
ERIC MEYER (317) 323-2074  
2243 East Main Street  
Greenfield, Indiana 46140  
EMEYER@MINESTARCONNECT.COM

TOWN OF MCCORDSVILLE  
PLANNING AND BUILDING DEPT  
RYAN CRUM  
6280 W 800 N  
McCordsville, Indiana 46055  
P: (317) 335-3604  
rcrum@mccordsville.org

MCCORDSVILLE FIRE DEPARTMENT  
7580 N Form Street  
McCordsville, Indiana 46055  
P: (317) 335-9236

TOWN OF MCCORDSVILLE  
ENGINEERING DEPARTMENT  
MARK WITSMAN  
6280 W 800 N  
McCordsville, IN 46055  
P: (317) 335-3604  
mwitsman@mccordsville.org

COMCAST  
WATT STRINGER  
5330 E. 65th Street  
Indianapolis, IN 46220  
P: (317) 774-3384  
F: (317) 219-5090  
matthew\_stringer@cable.comcast.com

TOWN OF MCCORDSVILLE  
PUBLIC WORKS  
RON CRIDER  
6280 W 800 N  
McCordsville, IN 46055  
P: (317) 335-3493  
rcrider@mccordsville.org

VECTREN  
SANDRA CASEY  
16000 Allisonville Road  
Noblesville, Indiana 46061  
P: (317) 776-5532,  
F: (317) 776-5553  
Mailing Address: P.O. Box 1700  
Noblesville, Indiana 46061  
sandra.casey@centerpointenergy.com



#### SOILS LEGEND

BR BROOKSTON SILTY CLAY LOAM  
CRA CROSBY SILT LOAM, 0 TO 3 PERCENT SLOPES  
MmB2 MIAMI SILT LOAM, 2 TO 6 PERCENT SLOPES, ERODED



### SHEET LIST TABLE

Sheet Title	Sheet Description
C1.0	COVER
C1.1	SITE IMPROVEMENTS PLAN
C1.2	SITE GRADING PLAN
C1.3	PRE-CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
C1.4	POST CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
C1.5	SITE UTILITY PLAN
C8.0	STORMWATER POLLUTION PREVENTION NOTES
C8.1-C8.4	STORMWATER POLLUTION PREVENTION DETAILS
L1.0	LANDSCAPE PLAN
L1.1	LANDSCAPE DETAILS
SHEETS 1-10	MCCORDSVILLE TOWN STANDARDS

### MCCORDSVILLE TOWN STANDARDS

#### SHEET LIST TABLE

Sheet Title	Sheet Description
1	DIRECTIONS FOR USE & GENERAL NOTES
2	RIGHT-OF-WAY SECTIONS & PAVEMENT SPECIFICATIONS
3	RIGHT-OF-WAY DETAILS
4	UTILITY LOCATION GUIDELINES
5	DRIVE WAY & HANDICAP RAMP DETAILS
6	STORM SEWER STRUCTURE DETAILS
7	STORM SEWER BEDDING DETAILS AND GENERAL NOTES
8	SANITARY SEWER SPECIFICATIONS
9	SANITARY SEWER DETAILS
10	SANITARY SEWER LIFT STATION STANDARDS & GUIDELINES

### REVISIONS

DATE	DESCRIPTION	BY



SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA

COVER




DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	

C1.0

COVER








KNOW WHAT'S BELOW.  
CALL BEFORE YOU DIG.

*Call 811 or 800-382-5544 Before you Dig!*



LEGEND:


EXISTING		PROPOSED
	RIGHT-OF-WAY LINE	
	EASEMENT LINE	
	SETBACK LINE	
	CENTERLINE	
	SWALE / FLOWLINE	
	SUBSURFACE DRAIN	
	SANITARY SEWER	
	STORM SEWER	
	STORM CULVERT	
	WATER MAIN	
	CONTOUR, MAJOR	
	CONTOUR, MINOR	
	FENCE	
	TREE LINE	
	POND SIGNAGE	
	STREET POST & LIGHT	
	SANITARY MANHOLE	
	STORM MANHOLE	
	STORM INLET	
	STORM END SECTION	
	FIRE HYDRANT	
	FLOW ARROW	
	SPOT ELEVATION	
	PAVEMENT ELEVATION	

ABBREVIATIONS:


BC	= BACK OF CURB
CL	= CENTERLINE
FG	= FINISHED GRADE
FL	= FLOW LINE
HP	= HIGH POINT
INV	= INVERT ELEVATION
LP	= LOW POINT
ME	= MATCH EXISTING GRADE
NP	= NORMAL POOL (ELEVATION)
PC	= POINT OF CURVATURE
PRC	= POINT OF REVERSE CURVATURE
PT	= POINT OF TANGENCY
PVC	= POLYVINYL CHLORIDE PIPE
PVI	= POINT OF VERTICAL INTERSECTION
RCP	= REINFORCED CONCRETE PIPE
R/W	= RIGHT-OF-WAY
TB	= TOP OF BANK GRADE
TC	= TOP OF CASTING GRADE
PAD	= PAD GRADE
MFPG	= MINIMUM FLOOD PROTECTION GRADE
MFFE	= MINIMUM FINISH FLOOR ELEVATION

THE DESIGN AND CONSTRUCTION SHALL COMPLY WITH THE CURRENT MCCORDSVILLE CONSTRUCTION SPECIFICATIONS AND STANDARD CONSTRUCTION DETAILS. THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT.

THE DESIGN AND CONSTRUCTION SHALL COMPLY WITH ALL ADA REQUIREMENTS.

[illegible]

**SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
SITE GRADING PLAN**




DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	

## C1.2

SITE GRADING PLAN

Plot Date: Apr 24, 2024 Plot Time: 1:58pm File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F Erosion Control Plan.dwg Layout: C1.3 By: keithhorn


THIS SHEET TO BE USED FOR  
EROSION CONTROL ONLY.



- LEGEND
- EX. TEMPORARY "DROP INLET PROTECTION BASKET"
  - EX. TEMPORARY CURB INLET PROTECTION SEE SHEET C8.1 FOR DETAIL
  - TEMPORARY "DROP INLET PROTECTION BASKET"
  - TEMPORARY CURB INLET PROTECTION SEE SHEET C8.1 FOR DETAIL
  - SILT FENCE
  - CONSTRUCTION LIMITS/SOIL DISTURBANCE AREA
  - PERMANENT SEEDING/SODDING
  - TEMPORARY SITE CONSTRUCTION ENTRANCE

- NOTES:
1. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED.
  2. THERE SHALL BE NO DIRT, DEBRIS OR STORAGE OF MATERIALS IN THE STREET.
  3. THIS SHEET TO BE USED FOR STORMWATER POLLUTION PREVENTION PURPOSES ONLY.
  4. GEOTEXTILE FABRIC SHALL BE PLACED UNDER STONE LAYER OF THE CONSTRUCTION ENTRANCE.
  5. ALL PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
  6. WHERE EXISTING DRAIN TILES OR FIELD TILES ARE ENCOUNTERED WHERE APPLICABLE, INTERCEPT EXISTING TILES AND TIE THEM INTO THE STORM SYSTEM.
  7. CONTRACTOR TO ABIDE BY THE 7 DAY RULE AND STREETS ARE TO HAVE THEIR STONE SUBBASE LAID DOWN AS SOON AS THEY ARE BROUGHT TO GRADE.

NOTE:  
SEE SHEET C8.0 FOR A LIST IN SEQUENCE  
OF CONSTRUCTION ACTIVITIES.



REVISIONS		
DATE	DESCRIPTION	BY

**HWC**  
**ENGINEERING**  
INDIANAPOLIS - TERRE HAUTE  
LAFAYETTE - MUNCIE - NEW ALBANY  
www.hwcengineering.com

SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
PRE-CONSTRUCTION STORMWATER  
POLLUTION PREVENTION PLAN




DRAWN BY TS	JOB NUMBER 2020-235-F SHEET
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	

C1.3  
PRE-CONSTRUCTION  
STORMWATER POLLUTION  
PREVENTION PLAN



Plot Date: Apr 24, 2024 Plot Time: 1:59pm File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F Erosion Control Plan.dwg Layout: C1.4 By: keichhorn

THIS SHEET TO BE USED FOR  
EROSION CONTROL ONLY.



GRAPHIC SCALE  
0' 20' 40' 60'  
(IN FEET)

LEGEND

- EX. TEMPORARY "DROP INLET PROTECTION BASKET"
- EX. TEMPORARY CURB INLET PROTECTION SEE SHEET C8.1 FOR DETAIL
- TEMPORARY "DROP INLET PROTECTION BASKET"
- TEMPORARY CURB INLET PROTECTION SEE SHEET C8.1 FOR DETAIL
- SILT FENCE
- CONSTRUCTION LIMITS/SOIL DISTURBANCE AREA
- PERMANENT SEEDING/SODDING

- NOTES:
- ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED.
  - THERE SHALL BE NO DIRT, DEBRIS OR STORAGE OF MATERIALS IN THE STREET.
  - THIS SHEET TO BE USED FOR STORMWATER POLLUTION PREVENTION PURPOSES ONLY.
  - GEOTEXTILE FABRIC SHALL BE PLACED UNDER STONE LAYER OF THE CONSTRUCTION ENTRANCE.
  - ALL PORTABLE TOILETS MUST BE ANCHORED TO PREVENT SPILLS.
  - WHERE EXISTING DRAIN TILES OR FIELD TILES ARE ENCOUNTERED WHERE APPLICABLE, INTERCEPT EXISTING TILES AND TIE THEM INTO THE STORM SYSTEM.
  - CONTRACTOR TO ABIDE BY THE 7 DAY RULE AND STREETS ARE TO HAVE THEIR STONE SUBBASE LAID DOWN AS SOON AS THEY ARE BROUGHT TO GRADE

NOTE:  
SEE SHEET C8.0 FOR A LIST IN SEQUENCE  
OF CONSTRUCTION ACTIVITIES.

REVISIONS		
DATE	DESCRIPTION	BY




**HWC**  
ENGINEERING

INDIANAPOLIS - TERRE HAUTE  
LAFAYETTE - MUNCIE - NEW ALBANY  
www.hwcengineering.com

SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
POST CONSTRUCTION STORMWATER  
POLLUTION PREVENTION PLAN

PROFESSIONAL ENGINEER

NOTED FOR CONSTRUCTION



DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	

C1.4

POST CONSTRUCTION  
STORMWATER POLLUTION  
PREVENTION PLAN





Plot Date: Apr 24, 2024  
Plot Time: 2:00pm  
File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F-SWPP Notes and Details.dwg, Layout: C8.0  
By: keichhorn

At stormwater pollution prevention BMPs shall be inspected and maintained as needed to ensure continued performance of their intended function during construction and shall continue until the entire site has been stabilized and a Notice of Termination has been issued. An inspection of the project site must be completed by the end of the next business day following each measurable storm event. If there are no measurable storm events within a given week, the site should be monitored at least once in that week. Maintenance and repair shall be conducted in accordance with the accepted site plans. This log shall be kept as a permanent record and must be made available to the Town Engineer, in an organized fashion, within forty-eight (48) hours upon request.

Stormwater Ordinance  
Technical Standards

Const. Insp. Page 1 of 2

July 2004

Type of Inspection: ☐ Scheduled Weekly ☐ Rain Event

If you answered "no" to any of the above questions, describe any corrective action which must be taken to remedy the problem and when the corrective actions are to be completed.

If you answered "no" to any of the above questions, describe any corrective action which must be taken to remedy the problem and when the corrective actions are to be completed.

Plot Date: Apr 24, 2024 Plot Time: 2:00pm

A1	PLAN INDEX	SEE COVER SHEET C1.0	B12	SCHEDULE OF STORMWATER MEASURES RELATED TO LAND DISTURBING ACTIVITIES	STORMWATER POLLUTION PREVENTION PLAN HAS BEEN DEVELOPED TO ELIMINATE SEDIMENT FROM LEAVING THE PROJECT DURING CONSTRUCTION ACTIVITIES PROTECTING ADJOINING PROPERTIES AND THE RECEIVING WATERS.
A2	VICINITY MAP	SEE COVER SHEET C1.0			
A3	PROJECT TYPE	THIS PROJECT IS: SUMMERTON AMENITY AREA			
A4	LATITUDE AND LONGITUDE	LATITUDE IS 39°54'55" N AND LONGITUDE IS 85°54'08" W.		PRE-CONSTRUCTION SCHEDULE	
A5	LEGAL DESCRIPTION	SEE PLAT FOR LEGAL DESCRIPTION.		1	CONTRACTOR TO CALL INDIANA UNDERGROUND 811 BY CALLING 811 OR 800-382-5544 TO VERIFY LOCATION OF EXISTING UTILITIES TWO (2) WORKING DAYS PRIOR TO START OF CONSTRUCTION.
A6	11X17 PLAT	PROVIDED IN OVERALL SUBMITTAL.		2	CONTRACTOR SHALL INSTALL STONE CONSTRUCTION ENTRANCE PRIOR TO THE START OF EARTHWORK IN ACCORDANCE WITH THE PLAN LOCATION ON SHEETS C1.7-C1.11 AND THE DETAIL ON SHEET C8.2.
A7	100 YEAR FLOODPLAINS, FLOODWAYS, AND FLOOD FRINGES	THE SITE LIES WITHIN FLOOD HAZARD ZONE AE, ZONE X (SHADED) AND ZONE X (UNSHADED) AS SAID ZONE PLOTS BY SCALE ON MAP NUMBERS 18059G00160 AND 18059G00170 OF THE FLOOD INSURANCE RATE MAPS FOR HANCOCK COUNTY INDIANA (MAP EFFECTIVE DATE DECEMBER 4, 2007).		3	CONTRACTOR TO INSTALL IDEM CONSTRUCTION STORMWATER GENERAL PERMIT INFORMATION POSTING, TRASH DUMPSTER, AND PORT-O-LET AS SHOWN ON SHEETS C1.7-C1.11.
A8	ADJACENT LAND USES	SEE SHEETS C1.1-C1.2. NORTH: SCHULTZ & SCHULTZ LEGAL DRAIN EAST: RESIDENTIAL SOUTH: AG / RESIDENTIAL WEST: RESIDENTIAL		4	CONTRACTOR TO INSTALL EXISTING STORM INLET PROTECTION AROUND THE PERIMETER OF THE SITE PRIOR TO CONSTRUCTION. CONTRACTOR SHALL EVALUATE EXISTING EROSION CONTROL MEASURES AND USE AND MAINTAIN, REPLACE AS NECESSARY.
A9	IDENTIFICATION OF U.S. EPA APPROVED OR ESTABLISHED TMDL	TMDL: NO, IMPAIRED: NO		5	CONTRACTOR SHALL INSTALL ALL REQUIRED SILT FENCE AROUND THE PERIMETER OF THE ENTIRE SITE (INCLUDING MASS GRADING AREAS OF FUTURE SECTIONS) AND ALL TREE PROTECTION FENCING ALONG THE NORTH BOUNDARY LINE PRIOR TO ANY EARTHWORK ACTIVITIES SUCH AS EARTH MOVING OR STRIPPING AS WELL AS TREE CLEARING.
A10	RECEIVING WATERS	SCHULTZ & SCHULTZ LEGAL DRAIN (NORTH FORK DRY BRANCH AUID: INW0189_1T010)		6	CONTRACTOR SHALL INSTALL CONCRETE WASHOUT AREA AND CONSTRUCTION STAGING AREA PRIOR TO THE START OF EARTHWORK ACTIVITIES AS SHOWN ON SHEET C1.5.
A11	IDENTIFICATION OF DISCHARGES TO A WATER ON THE CURRENT 303(d) LIST OF IMPAIRED WATERS AND THE POLLUTANT(S) FOR WHICH IT IS IMPAIRED.	TMDL: NO, IMPAIRED: NO		7	CONTRACTOR TO EVALUATE LOCATION OF SOIL STOCKPILE AREAS AND PREPARE BY PLACING SILT FENCE DEFINING LIMITS, SEE SHEETS C1.7-C1.11.
A12	SOILS MAP	SEE SHEET C1.0		8	CONTRACTOR AND DEVELOPER SHALL COORDINATE WITH ADJOINING PROPERTY OWNERS RELATED TO OFFSITE SANITARY SEWER, WATER MAIN, AND STORM SEWER WORK. CONTRACTOR SHALL INSTALL ALL REQUIRED SILT FENCE AROUND THE PERIMETER OF THE OFFSITE CONSTRUCTION LIMITS AS WELL AS ANY REQUIRED TREE PROTECTION FENCING PRIOR TO OFFSITE PHASE OF WORK.
A13	LOCATION OF WETLANDS, LAKES, WATER COURSES ADJACENT TO SITE	SEE SHEETS C1.1-C1.2		9	DEWATERING: ALL CONTRACTORS AND VENDORS ARE RESPONSIBLE FOR PREPARING AN APPROPRIATE DEWATERING PLAN BASED ON NEED FROM UTILITY INSTALLATION, LOWERING OF PONDS, HOME FOUNDATIONS/BASEMENTS ETC. IN NO CIRCUMSTANCES SHOULD DEWATERING OPERATIONS BEGIN BASED ON ASSUMPTION WATER IS CLEAN. OFTEN SEDIMENT LADEN WATER IS ENCOUNTERED TOWARDS THE END OF THE OPERATION AND NOT THE BEGINNING. DEWATERING REQUIRES INTENSIVE MEASURES FOR MAINTENANCE, FREQUENT MONITORING, CLEANOUT, REPAIR AND/OR REPLACEMENTS. SUBMIT DEWATERING PLAN PRIOR TO COMMENCING WORK TO LENNAR HOME PROJECT MANAGER FOR APPROVAL.
A14	STATE OR FEDERAL WATER QUALITY PERMITS	IDEM CONSTRUCTION STORMWATER GENERAL PERMIT		10	ONCE PERMETER ELEMENTS ARE INSTALLED, ANY UTILITY MODIFICATION OR RELOCATION PER SHEETS C1.2-C1.4 CAN COMMENCE IN FINAL PREPARATION FOR MASS EARTHWORK OPERATIONS. ALL INTERIM FLOW REQUIREMENTS SUCH AS ROCK CHECK DAMS AND TEMPORARY SWALES SHALL BE COMPLETED PRIOR TO MASS EARTHWORK OPERATIONS. THESE MEASURES SHALL BE MAINTAINED AND ADJUSTED AS NEEDED UNTIL COMPLETION OF EARTHWORK AND THE SITE HAS BEEN FULLY STABILIZED. AS SOON AS LAKE 3 HAS BEEN SUFFICIENTLY EXCAVATED, THE PERMANENT POND OUTFALL SHALL BE INSTALLED WITH A FAIRCLOTH SKIMMER TO SERVE AS A SEDIMENT BASIN. THE FAIRCLOTH SKIMMER SHALL REMAIN UNTIL THE SITE HAS BEEN FULLY STABILIZED. EROSION CONTROL ADJUSTMENTS DURING DIFFERENT PHASES OF CONSTRUCTION ARE LIKELY REQUIRED AND SUBJECT TO WEATHER CONDITIONS.
A15	IDENTIFICATION OF EXISTING VEGETATIVE COVER, INCLUDING NATURAL BUFFERS	SEE SHEETS C1.1-C1.2. NO NATURAL WATERWAY OR SURFACE WATERS WITHIN DEVELOPMENT SITE. OFFSITE POND IS ADJACENT TO NORTH FORK DRY BRANCH WHICH IS A COUNTY REGULATED DITCH.			CONSTRUCTION SCHEDULE
A16	EXISTING SITE TOPOGRAPHY	SEE SHEETS C1.1-C1.2		11	BEGIN CLEARING AND GRADING ACTIVITIES AFTER EROSION AND SEDIMENT CONTROL MEASURES ARE IN PLACE AND ITEMS 1-10 OF THE PRE-CONSTRUCTION SCHEDULE ARE COMPLETE. EARTHMOVING SHALL BE DONE IN A MANNER TO MINIMIZE EROSION. CONTRACTOR SHALL VERIFY ALL EXISTING STORM SEWER AND UTILITY CONNECTION LOCATIONS AND ELEVATION PRIOR TO MOVING EARTH. CONTACT ENGINEER WITH ANY DISCREPANCIES. AS GRADING PROGRESSES, INSTALL ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES TO CONTAIN SEDIMENT ON SITE.
A17	LOCATION(S) WHERE RUNOFF ENTERS PROJECT SITE	SEE SHEETS C1.1-C1.2. FROM WEST AND EAST - REFER TO DRAINAGE REPORT FOR DETAILS.		12	CONTRACTOR SHALL STRIP TOPSOIL AND GRADE THE SITE PER PLAN AND PLACE PERMANENT AND TEMPORARY SEED AS INDICATED ON THE PLAN, INCLUDING SEEDING WITH FIBER BLANKET ON MOUNDS, POND BANKS, SWALES. DURATION OF EXPOSED AREAS SHALL BE KEPT MINIMAL DEPENDANT ON WEATHER. ALL POTENTIALLY IDLE AREAS SHALL INITIATE STABILIZATION ON THE SEVENTH DAY (7 DAYS) SUCH AS TEMPORARY SEEDING AND MULCH. THE STABILIZATION ACTIVITY MUST BE COMPLETED WITHIN FOURTEEN (14) DAYS AFTER INITIATION PER IDEM CONSTRUCTION STORMWATER GENERAL PERMIT.
A18	LOCATION(S) WHERE RUNOFF DISCHARGES FROM THE PROJECT SITE PRIOR TO LAND DISTURBANCE	SEE SHEETS C1.1-C1.2. RUNOFF DISCHARGES FROM THE SITE TO SCHULTZ & SCHULTZ LEGAL DRAIN.		13	PERMANENT AND FINAL VEGETATION, IN ADDITION TO STRUCTURAL MEASURES SHALL BE INSTALLED AS SOON AS PRACTICAL PER SHEETS C1.1-C1.18.
A19	LOCATION OF ALL EXISTING STRUCTURES ON THE PROJECT SITE	SEE SHEETS C1.1-C1.2.		14	INSTALL STORM SEWER SYSTEM, SUBSURFACE DRAINAGE SYSTEM, AND SWALES.
A20	EXISTING PERMANENT RETENTION OR DETENTION FACILITIES, INCLUDING MANMADE WETLANDS, DESIGNED FOR THE PURPOSE OF STORMWATER MANAGEMENT.	SEE SHEETS C1.1-C1.2 FOR THE LOCATION OF DETENTION PONDS CONSTRUCTED AS A PART OF SUMMERTON SECTION 1.		15	CONTRACTOR SHALL INSTALL REMAINING UTILITIES AND RE-SEED ALL DISTURBED AREAS.
A21	LOCATIONS WHERE STORMWATER MAY BE DIRECTLY DISCHARGED INTO GROUNDWATER, SUCH AS ABANDONED WELLS, SINKHOLES, OR KARST FEATURES	NONE.		16	CONTRACTOR SHALL INSTALL ALL STREETS AS INDICATED ON PLANS.
A22	PROJECT AREA	35.93 ACRES±		17	INSTALL LOT SPECIFIC BMPs INCLUDING WASTE RECEPTACLES, CURB LINE BMPs, WASHOUTS, AND STABILIZED ENTRANCES.
A23	LAND DISTURBANCE	35.93 ACRES±		18	INSTALL HOME (VERTICAL) CONSTRUCTION CONCRETE WASHOUT. CONTRACTOR SHALL PROVIDE DIRECTION ON LOCATION FOR INSTALLATION. SEE DETAIL ON SHEET C8.3.
A24	PROPOSED SITE TOPOGRAPHY	SEE SHEETS C1.3-C1.6		19	BUILDING FOUNDATION EXCAVATIONS.
A25	LOCATIONS AND BOUNDARIES OF DISTURBED AREAS	SEE SHEETS C1.7-C1.18		20	VERTICAL CONSTRUCTION AND HOME BUILDING.
A26	LOCATIONS, SIZES, DIMENSIONS OF PROPOSED STORMWATER SYSTEM	SEE SHEETS C6.0-C6.3		21	INSTALL PERMANENT OR TEMPORARY SOIL STABILIZATION AND LANDSCAPING.
A27	POINTS WHERE STORMWATER WILL DISCHARGE SITE	RUNOFF WILL BE COLLECTED BY THE PROPOSED STORM SEWER SYSTEM AND ROUTED TO EAST FORK DRY BRANCH (SCHULTZ & SCHULTZ REGULATED DRAIN)		22	CONTRACTOR SHALL MAINTAIN EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION AND UNTIL SEDIMENTATION OF STREETS AND STORM SEWERS NO LONGER OCCURS. CONTRACTOR SHALL INSPECT ON A WEEKLY BASIS OR AFTER A SIGNIFICANT STORM EVENT (AN EVENT OF AT LEAST 0.5 INCHES OF RAINFALL). SEE SHEETS C8.0-C8.5 FOR DETAILS AND SPECIFICATIONS.
A28	LOCATION OF ALL PROPOSED SITE IMPROVEMENTS, INCLUDING ROADS, UTILITIES, LOT DELINEATION AND IDENTIFICATION, PROPOSED STRUCTURES AND COMMON AREAS.	SEE SHEETS C1.2-C1.6		23	COMPLETE FINAL GRADING AND INSTALL SEEDING AND LANDSCAPING. STABILIZE ALL REMAINING EXPOSED AREAS AS A RESULT OF CONSTRUCTION RELATED ACTIVITIES.
A29	LOCATION OF SOIL STOCKPILE	SEE SHEETS C1.7-C1.10		24	ALL EROSION AND SEDIMENT CONTROL SHALL COMPLY WITH IDEM CONSTRUCTION STORMWATER GENERAL PERMIT.
A30	CONSTRUCTION SUPPORT ACTIVITIES THAT ARE EXPECTED TO BE PART OF THE PROJECT	SEE SHEETS C1.7-C1.11 FOR CONSTRUCTION STAGING AND ASSOCIATED MEASURES			
A31	LOCATION OF ANY IN STREAM ACTIVITIES THAT ARE PLANNED FOR THE PROJECT INCLUDED BUT NOT LIMITED TO, STREAM CROSSINGS AND PUMP AROUNDINGS	OUTFALL INTO NORTH FORK DRY BRANCH WILL HAVE RIPRAP TO STABILIZE THE BANK.			
B1	POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES	ERODED SOILS AND SEDIMENTS; OILS, GREASES, COOLANTS, CONCRETE WASHOUT, PETROLEUM FUELS AND OTHER FLUIDS ASSOCIATED WITH OPERATION AND MAINTENANCE OF CONSTRUCTION EQUIPMENT PRESENT ON THE SITE; DEBRIS INCLUDING CUTTINGS, SEALANTS, ADHESIVES, AND COATINGS ASSOCIATED WITH INSTALLATION OF UNDERGROUND PIPES, INFRASTRUCTURE AND CONSTRUCTION OF THE BUILDING; PAINTS ASSOCIATED WITH PAVEMENT MARKING; FERTILIZERS ASSOCIATED WITH SEEDING AND PLANTING.			
B2	STABLE CONSTRUCTION ENTRANCE LOCATION AND SPECIFICATIONS	TEMPORARY GRAVEL CONSTRUCTION ENTRANCE FOR LOCATION: SEE SHEETS C1.7-C1.11 FOR DETAIL: SEE SHEET C8.2			
B3	TEMPORARY AND PERMANENT STABILIZATION	TEMPORARY SEEDING IS REQUIRED FOR ANY POTENTIAL IDLE AREA AND MUST INITIATE STABILIZATION ON THE			

SEE SHEET C8.2

MATERIAL HANDLING:

**MATERIAL HANDLING:**

1. THE PROPER MANAGEMENT AND DISPOSAL OF WASTE SHOULD BE PRACTICED ON-SITE AT ALL TIMES. HAZARDOUS WASTE SHOULD BE STORED IN A SECURE LOCATION TO PREVENT RUNOFF. HAZARDOUS WASTE SHOULD ALWAYS BE DISPOSED OF THROUGH A DESIGNATED HAZARDOUS WASTE MANAGEMENT OR RECYCLING FACILITY.

2. DESIGNATE A WASTE COLLECTION AREA ON-SITE THAT DOES NOT RECEIVE A SUBSTANTIAL AMOUNT OF TRAFFIC. PROVIDE A CONTAINER FOR THE COLLECTION OF ALL WASTE FROM THE BODY.

3. KEEP PRODUCTS IN ORIGINAL CONTAINERS WITH ORIGINAL LABELS AND MAINTAIN SAFETY DATA INFORMATION ATTACHED. MAKE SURE PRODUCTS ARE PROPERLY SEALED TO PREVENT LEAKS AND ARE STORED IN A SECURE AREA. PROVIDE A WASTE COLLECTION AREA FOR OILS, FUELS, PAINTS, AND FLAMES.

4. A PLAN FOR THE RECYCLING OR DISPOSAL OF MATERIALS ASSOCIATED WITH OR FROM THE PROJECT SITE SHALL BE ESTABLISHED BY THE CONTRACTOR. ALL RECYCLING CONTAINERS SHALL BE CLEARLY LABELED.

5. CONTAINER MAINTENANCE ACTIVITIES ARE TO BE MONITORED AND MAINTAINED BY THE CONTRACTOR, AS EACH NEW SUBCONTRACTOR COMES ON-SITE. THE CONTRACTOR WILL CONDUCT AND DOCUMENT A MEETING TO ENSURE AWARENESS OF THE POLLUTANT PREVENTION PROGRAM, GUIDELINES FOR CONTAINER HANDLING, AND THE POLLUTANT PREVENTION PROGRAM. ALL CONTAINERS MUST BE STORED IN THE STORAGE AND USE AREAS, AND WORKERS SHALL BE TRAINED IN THESE PRACTICES.

6. CONTAINERS AND EQUIPMENT MUST BE INSPECTED REGULARLY FOR LEAKS, CORROSION, SUPPORT DAMAGE, AND OTHER DEFECTS. DEFECTIVE CONTAINERS AND EQUIPMENT MUST BE IDENTIFIED BY SOUNDNESS, ANY FOUND TO BE DEFECTIVE SHOULD BE REPAIRED OR REPLACED IMMEDIATELY.

PURPOSE:

**PURPOSE:** THE INTENTION OF THIS SPILL PREVENTION, CONTROL AND COUNTERMEASURES (SPCC) IS TO ESTABLISH THE PROCEDURES AND EQUIPMENT REQUIRED TO PREVENT THE DISCHARGE OF OIL AND HAZARDOUS SUBSTANCES IN QUANTITIES THAT VIOLATE APPLICABLE WATER QUALITY STANDARDS, CAUSE A SHEEN UPON OR DISCOLORATION OF THE SURFACE OF NAVIGABLE WATERS OR ADJOINING SHORELINES, OR CAUSE SLUDGE OR EMULSION TO BE DEPOSITED BENEATH THE SURFACE OF THE WATER OR ADJOINING SHORELINES. THE PLAN ALSO ESTABLISHES THE ACTIVITIES REQUIRED TO MITIGATE SUCH DISCHARGES (I.E., COUNTERMEASURES) SHOULD THEY OCCUR.

DEFINITIONS:  
POLLUTANT: MEANS POLLUTANT OF ANY KIND OR IN ANY FORM, INCLUDING BUT NOT LIMITED TO SEDIMENT, PAINT, CLEANING AGENT, CONCRETE WASHOUT, PESTICIDES, NUTRIENTS, TRASH, HYDRAULIC FLUIDS, FUEL, OIL, PETROLEUM, FUEL OIL, SLUDGE, OIL REFUSE, AND OIL MIXED WITH WASTES OTHER THAN DREDGED SOIL.

DISCHARGE:  
INCLUDES BUT IS NOT LIMITED TO, ANY SPILLING, LEAKING, PUMPING, POURING, EMITTING, EMPTYING,  
OR DUMPING.

NAVIGABLE WATERS:  
MEANS ALL WATERS OF THE UNITED STATES THAT ARE CONNECTED WITH A NAVIGABLE STREAM,  
LAKE, OR SEA. [NOTE: THIS DEFINITION IS USUALLY INTERPRETED TO MEAN ANY WASTEWATER (EVEN  
NORMALLY DRY WASH OR STORM SEWER) THAT EVENTUALLY DRAINS INTO A NAVIGABLE STREAM.]

PLAN REVIEW AND AMENDMENTS:  
THIS PLAN SHALL BE REVIEWED AND/OR AMENDED, IF NECESSARY, WHENEVER THERE IS A CHANGE IN THE DESIGN OF THE SITE, CONSTRUCTION, OPERATION, OR MAINTENANCE WHICH MATERIALLY AFFECTS THE SITE'S POTENTIAL FOR THE DISCHARGE OF REGULATED MATERIAL.

PREDICTION OF POTENTIAL SPILLS:

1. NEAREST NAVIGABLE WATER: WHITE RIVER
2. DRAINAGE SYSTEM: ALL STORM DRAINAGE LEAVES THE SITE BY CLOSED STORM SYSTEMS TO EXISTING POND SOUTH OF THE SITE. POSSIBLE SPILL SOURCES (DURING AND POST CONSTRUCTION) ARE: FUEL TANKS, OIL TANKS, HYDRAULIC FLUID, GREASE, ANTIFREEZE, TRASH AND DEBRIS, BIOLOGICAL AGENTS FOUND IN TRASH AND DEBRIS, FERTILIZERS AND PESTICIDES, BUT NOT LIMITED TO CLEANING AGENTS, CHEMICALS, PAINT, HERBICIDES AND PESTICIDES.
3. GROUNDWATER CONTAMINATION:  
EXISTING WATER TABLE IS ABOVE GROUND OR UNDER GROUND STORAGE TANKS AT THIS SITE. THEREFORE, IT IS FELT THAT THERE IS LITTLE OR NO POSSIBILITY OF POST CONSTRUCTION GROUNDWATER CONTAMINATION. THE FACILITY DOES HAVE PUBLIC SANITARY SEWER AND PUBLIC WATER.

ALERT PROCEDURES FOR SPILLS:

1. ANY PERSONNEL OBSERVING A SPILL WILL IMMEDIATELY INSTIGATE THE FOLLOWING PROCEDURE:
  - A. DIALING "911" FROM ANY TELEPHONE.
  - B. NOTIFY THE APPROPRIATE EMERGENCY PERSONNEL.

2. THE EMERGENCY COORDINATOR WILL THEN TAKE THE FOLLOWING ACTIONS:

- A. BARRICADE THE AREA ALLOWING NO VEHICLES TO ENTER OR LEAVE THE SPILL ZONE.
- B. NOTIFY THE INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT, OFFICE OF EMERGENCY RESPONSE BY CALLING THE APPROPRIATE TELEPHONE NUMBER:  
OFFICE 317-233-7745  
TOLL FREE 800-233-7745

INFORMATION:

- TIME OF OBSERVATION OF THE SPILL
- LOCATION OF THE SPILL
- IDENTITY OF MATERIAL SPILLED
- PROBABLE SOURCE OF THE SPILL
- PROBABLE TIME OF THE SPILL
- VOLUME OF THE SPILL AND DURATION
- PRESENT AND ANTICIPATED MOVEMENT OF THE SPILL
- WEATHER CONDITIONS
- PERSONNEL AT THE SCENE
- ACTION INITIATED BY PERSONNEL

- C. NOTIFY THE TOWN OF ACCORDVILLE FIRE DEPARTMENT (PHONE 99-1-1)
- D. NOTIFY THE TOWN OF ACCORDVILLE POLICE DEPARTMENT (PHONE 99-1-1)
- E. NOTIFY WASTE RECOVERY CONTRACTOR, MAINTENANCE PERSONNEL OR OTHER CONTRACTUAL PERSONNEL AS NECESSARY FOR CLEANUP
- F. COORDINATE AND MONITOR CLEANUP UNTIL THE SITUATION HAS BEEN STABILIZE AND ALL SPILLS HAVE BEEN ELIMINATED.
- G. COOPERATE WITH THE IDEM-CER ON PROCEDURES AND REPORTS INVOLVED WITH THE EVENT

CLEANUP PARAMETERS:

THE DEVELOPER SHALL BE CONTINUALLY KEPT INFORMED, MAINTAIN LISTS OF QUALIFIED PERSONNEL AND AVAILABLE CLEAN-UP TRUCKS, TANK VEHICLES AND OTHER EQUIPMENT READILY ACCESSIBLE FOR CLEAN-UP OPERATIONS. IN ADDITION, CONTINUALLY UPDATED LIST OF AVAILABLE ABSORBENT MATERIALS AND CLEAN-UP SUPPLIES SHOULD BE KEPT ON SITE.

ALL MAINTENANCE PERSONNEL WILL BE MADE AWARE OF TECHNIQUES FOR PREVENTION AND CONTROL OF SPILLS OF OIL AND GREASE. THE PREVENTION AND PROCEDURES OUTLINED IN THIS PLAN, THEY WILL BE KEPT ABREAST OF CURRENT DEVELOPMENTS OR NEW INFORMATION ON THE PREVENTION OF SPILLS AND/OR NECESSARY ALTERATIONS TO THIS PLAN.

WHEN AN OIL SPILL OCCURS, THE OIL SPILLER SHALL IMMEDIATELY REPORT CONCERNING THE DISCHARGE OF THE LIFE SAVING PROTECTION FUNCTION WILL BE CARRIED OUT BY THE LOCAL POLICE AND FIRE DEPARTMENTS.

ALL MATERIALS THAT ARE USED IN CLEANING UP SPILLED MATERIALS, WILL BE DISPOSED OF IN A MANNER SUBJECT TO THE APPROVAL OF THE INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT.

THE FURNISHING OF SPILLED MATERIAL WITH WATER WILL NOT BE PERMITTED UNLESS SO AUTHORIZED BY THE INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT.

### VEHICLE & EQUIPMENT MAINTENANCE

DESCRIPTION AND PURPOSE:  
PREVENT OR REDUCE THE CONTAMINATION OF STORMWATER RESULTING FROM VEHICLE AND EQUIPMENT MAINTENANCE BY RUNNING A "DRY AND CLEAN SITE". THE BEST OPTION WOULD BE TO PERFORM MAINTENANCE ACTIVITIES AT AN OFFSITE FACILITY. IF THIS OPTION IS NOT AVAILABLE THEN WORK SHOULD BE PERFORMED IN DESIGNATED AREAS ONLY, WHILE PROVIDING COVER FOR MATERIALS STORED OUTSIDE, CHECKING FOR LEAKS AND SPILLS, AND CONTAINING AND CLEANING UP SPILLS IMMEDIATELY.

SUITABLE APPLICATIONS:  
THESE PROCEDURES ARE SUITABLE ON ALL CONSTRUCTION PROJECTS WHERE AN ONSITE YARD AREA IS NECESSARY FOR STORAGE AND MAINTENANCE OF HEAVY EQUIPMENT AND VEHICLES.

LIMITATIONS:  
ON-SITE VEHICLE AND EQUIPMENT MAINTENANCE SHOULD ONLY BE USED WHERE IT IS IMPRACTICAL TO SEND VEHICLES AND EQUIPMENT OFFSITE FOR MAINTENANCE AND REPAIR. SENDING VEHICLES/EQUIPMENT OFFSITE SHOULD BE DONE IN CONJUNCTION WITH A STABILIZED CONSTRUCTION ENTRANCE/EXIT. OUTDOOR VEHICLE OR EQUIPMENT MAINTENANCE IS A POTENTIALLY SIGNIFICANT SOURCE OF STORMWATER POLLUTION. ACTIVITIES THAT CAN CONTAMINATE STORMWATER INCLUDE ENGINE REPAIR AND SERVICE, CHANGING OR REPLACEMENT OF FLUIDS, AND OUTDOOR EQUIPMENT STORAGE AND PARKING (ENGINE FLUID LEAKS).

STORMWATER POLLUTION PREVENTION PLAN IS IN COMPLIANCE WITH THE REQUIREMENTS OF IDEM CONSTRUCTION STORMWATER GENERAL PERMIT (CSGP).

SEE SWPPP BOOK FOR TRAINING OF LENNAR  
ASSOCIATE AND DELEGATION LETTER

PERSON ONSITE RESPONSIBLE FOR EROSION CONTROL:

ERIK ROBINSON  
LENNAR HOMES OF INDIANA, LLC  
PHONE: (317) 659-3200  
EMAIL: erik.robinson@lennar.com



**HWC**  
**ENGINEERING**

INDIANAPOLIS - TERRE HAUTE  
LAFAYETTE - MUNCIE - NEW ALBANY  
[www.hwcengineering.com](http://www.hwcengineering.com)

**SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA**



DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	


# C8.0

## STORMWATER POLLUTION PREVENTION NOTES











Sequence Describing Storm Water Quality Measure Implementation Relative to the Vertical Construction Activity on an Individual Lot within a Larger Development.

Introduction – The project site owner has identified eight (8) phases within the vertical construction sequence. During the period of construction activities, all storm water quality measures necessary to meet the requirements of the Indiana storm water rule shall be maintained in working order. The SWPPP shall serve as a guideline for storm water quality, but should not be interpreted to be the only basis for implementing, in accordance with the Rule, all measures to adequately prevent polluted storm water run-off. Alternative measures to site stabilization are acceptable if the site owner or their representative can demonstrate they have implemented erosion and sediment control measures adequate to prevent sediment discharge. Generally, the project site owner will have permitted projects within multiple municipalities; therefore, BMP practices will be modified as required by the enforcement of applicable regulation. Please make reference to: ‘Protocol for when BMP Maintenance is Required’.

From time construction activity begins, and until the individual lot is stabilized, the lot owner will:

- Protect adjacent properties from sedimentation;
- Prevent mud/sedimentation from depositing on the public street;
- Protect drainage ways from erosion and sedimentation;
- Prevent sediment laden water from entering storm sewer inlets.

The following storm water quality measures will take place on an individual lot/home– site:

Phase 1 – Foundation – During the period of construction activities:

- A qualified professional shall install silt fence at front curb and rear swale; wattles may be utilized as permitted by applicable regulations (i.e. frozen ground conditions, feasibility for site access, transitional BMP, etc. Additional silt fence will be installed adjacent to establish lots or common areas, or the full perimeter of lot/home–site, as required by the enforcement of applicable regulation. A qualified professional shall verify the presence of appropriate BMP protection for nearby storm water inlets; if not present, the CM will be notified and these BMP devices will be installed promptly.
- The installation of the following House Keeping BMPs will be installed upon start of construction as required by enforcement of applicable regulations:
  - o Portable toilet(s) will be appropriately staged throughout the project site. Note: Please make reference to: ‘Protocol for Staging Portable Toilets’;
  - o Trash containers or location of trash placement;
  - o Concrete washout (May be a stationary location for the entire site, or may be portable devices on an individual lot).

- Townhome Projects: Typically, a gravel staging area will be established on the site to accommodate storage of construction materials and equipment, concrete washout, and portable toilets. Perimeter silt fence or silt sock will be installed around the staging area. The project Construction Manager will evaluate each site for the appropriate location for the staging area.

- A temporary construction entrance shall be installed, as required by the enforcement of applicable regulations.
- Foundation soil stock pile may remain active throughout the Foundation Phase. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil stock piles will be distributed on site by machine grade in a timely manner.
- Up to two loads of soil may remain on site after backfill of foundation. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- All concrete washout will occur at the designated concrete washout area. Washout may occur onsite on an individual lot utilizing portable washout devices.
- All construction trash/debris will be contained on site in a manner permitted the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater ‘toolbox talks’.

Phase 2 – Framing – During the period of construction activity:

- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up. Please refer to Builders Trash Act protocol.)
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater ‘toolbox talks’.

Phase 3 – Mechanical Rough – During the period of construction activity:

- All point washout shall be done utilizing paint containers. All paint containers shall be removed from the lot/home– site by the paint contractor.
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater ‘toolbox talks’.

Phase 4 – Insulation/Drywall – During the period of construction activity:

- All drywall scrap and debris shall be removed from the lot/home site by the drywall contractor. The drywall contractor will be responsible for the appropriate disposal of all drywall material. Washout of drywall spackling compounds shall be contained in buckets and removed from the lot/home site by the drywall contractor.
- While in the process of installing brick veneer, bagged dry mix mortar and brick material will be covered by a vapor barrier material to prevent exposure to a rain event. A vapor barrier material will be applied to the soil surface where brick mortar will be mixed. Washout of mortar material may occur on site when utilizing appropriate portable washout container. Hardened mortar debris and brick trash will be staged at curb side by the brick contractor for removal; or placed in the graded trash container (i.e. dumpster) as required by enforcement of applicable regulations. In addition to the aforementioned guidance, the following requirements shall apply for washout of brick mortar for all Lennar Townhome construction sites:
  - o The staging area for mixing brick mortar shall be adjacent to the Site concrete washout.
  - o All brick mortar washout shall occur (in semi–solid condition) directly into the concrete washout in lieu of utilizing a washout bag.
  - o Lennar will not provide a washout container bag for Townhome construction sites.
  - o Note: Please make reference to: Brick Mortar Washout Protocol – Lennar BMP for detailed staging guidance.
- All concrete washout will occur at the designated concrete washout area. Washout may occur onsite utilizing portable washout devices.
- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater toolbox talks.

Phase 5 – Exterior Finish – During the period of construction activity:

- A machine grade will occur on site to prepare for the installation of the permanent concrete driveway and walkways. During this transition, Curb back cut and/or wattles may be utilized as submittal BMP measures to adequately prevent polluted storm water run–off from the construction site.
- All concrete washout will occur at the designated concrete washout area. Washout may occur onsite utilizing portable washout devices.
- Washout of drywall spackling compounds, paint, tile grout, etc., shall be contained in buckets and removed from the lot/home site by the appropriate contractor.
- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater toolbox talks.

Phase 6 – Interior Finish – During the period of construction activity:

- Washout of drywall spackling compounds, paint, tile grout, etc., shall be contained in buckets and removed from the lot/home–site by the appropriate contractor.
- All concrete washout will occur at the designated concrete washout area. Washout may occur onsite utilizing portable washout devices.
- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater toolbox talks.

Phase 7 – Mechanical Trim – During the period of construction activity:

- A machine grade will be accomplished on site for purposes of filling ground settlement and surface erosion.
- Washout of drywall spackling compounds, paint, tile grout, etc., shall be contained and removed from the lot/home site by the appropriate contractor.
- All concrete washout will occur at the designated concrete washout area. Washout may occur onsite utilizing portable washout devices.
- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)
- Up to two loads of soil may remain on site. Soil stock piles shall be placed on the lot/home site in a manner as not to challenge the integrity of perimeter BMPs. Soil will be distributed on site by machine grade in a timely manner.
- A qualified person(s) shall inspect and maintain all storm water measures. Lennar site Associates will participate in bi-weekly stormwater toolbox talks.

Phase 8 – Home Site Finish – During the period of construction activity:

- During seasonal conditions, all silt fence will be removed, wattles or turf mat may be utilized as transitional BMP while awaiting final stabilization, a machine grade will be accomplished on site in preparation for final stabilization (Note: adverse soil conditions may limit winter grading). Sod will be installed at front yard to front corners of house structure. Side and rear yards will be seeded and PennMulch soil stabilizer/fertilizer applied to soil surface, a row of turf matting will be installed at the rear swale easement line, and one piece of sod will be placed at each downslope located within a seeded area of the lot. Other turf matting may be positioned on seeded areas due to extreme lot grade. When full sod option is chosen, sod will be installed at side and rear yard in–lieu–of seed, no turf mat will be applied rear easement line, rear swale shall be over seeded. During the New Home Orientation, the new property owner will be informed of the requirement for, and benefits of, final stabilization, and the prevention of stormwater pollution.
- Upon the completion of construction activity, and during unseasonable conditions, existing erosion and sediment control measures will remain in place on site, wattles or turf mat may be applied at curb in–lieu–of silt fence. A qualified person shall inspect and maintain all storm water measures. During the New Home Orientation, the new property owner will be informed of the requirement for, and benefits of, final stabilization, and the prevention of stormwater pollution.

- When seasonal conditions return, all perimeter BMPs will be removed, wattles or turf mat may be utilized as transitional BMP while awaiting final stabilization, sod will be installed at front yard, side and rear yards will be seeded and PennMulch soil stabilizer/fertilizer w/ tackifier applied to soil surface, and one piece of sod will be placed at each downslope located within a seeded area of the lot. A single row of turf matting will be installed at the rear swale easement line. If full sod option is chosen, sod will be installed at side and rear yard in–lieu–of seed, no turf mat will be applied rear easement line, rear swale shall be over seeded.


- Washout of drywall spackling compounds, paint, tile grout, etc., shall be contained in buckets and removed from the lot/home site by the appropriate contractor.
- All concrete washout may occur at the designated concrete washout area; or, washout may occur on site of an individual lot utilizing portable washout devices.

- All construction trash/debris will be contained on site in a manner permitted by the enforcement of applicable regulations (i.e. trash containers utilized as enforced by municipal authority, fly–a–way trash will be appropriately contained on site by end of day. Where permitted lumber trash /debris may be set at curb for weekly trash pick–up.)

- A qualified person(s) shall inspect and maintain all storm water measures, until transfer of ownership has occurred and the new property owner has been informed of the requirement for, and benefits of, final stabilization. Lennar site Associates will participate in bi-weekly stormwater toolbox talks.

## CONCRETE WASHOUT

### Concrete Washout (Above Grade System) Worksheet



254 Chapter 7 October 2007

## CONCRETE WASHOUT

- Metal pins or staples at a minimum of six inches in length, sandbags, or alternative fastener to secure polyethylene lining to the containment system.
  - Non-slopping and non-water holding cover for use during rain events (optional).
- Installation**
- Prefabricated Washout Systems/Containers
    - Install and locate according to the manufacturer's recommendations.
  - Designed and Installed Systems
    - Utilize and follow the design in the storm water pollution prevention plan to install the system.
    - Dependent upon the type of system, either excavate the pit or install the containment system.
    - A base shall be constructed and prepared that is free of rocks and other debris that may cause tears or punctures in the polyethylene lining.
    - Install the polyethylene lining. For excavated systems, the lining should extend over the entire excavation. The lining for bermal systems should be installed over the pooling area with enough material to extend the lining over the berm or containment system. The lining should be secured with pins, staples, or other fasteners.
    - Place flags, safety fencing, or equivalent to provide a barrier to construction equipment and other traffic.
    - Place a non-slopping, non-water holding cover over the washout facility prior to a predicted rainfall event to prevent accumulation of water and possible overflow of the system (optional).
    - Install signage that identifies concrete washout areas.
    - Post signs directing contractors and suppliers to designated locations.
    - Where necessary, provide stable ingress and egress (see Temporary Construction Ingress/Egress Pad on page 17) or alternative approach pad for concrete washout systems.

October 2007 Chapter 7 251

## ROCK CHECK DAM

- Overflow Areas**  
Stabilized to reduce sediment/runoff along sides and below the dam.
- Filter Medium**
  - Placed on up-slope side of dam.
  - Height – to base of overflow weir notch.
- Materials**
  - Geotextile fabric (8 ounce or heavier, nonwoven).
  - Indiana Department of Transportation Reemert riprap (see Appendix D) for dam.
  - INDOT CA No. 5 aggregate (see Appendix D) for use as filter medium (Aggregate must be well-graded).
- Note: INDOT CA No. 8 aggregate is acceptable if No. 5 aggregate is not available. The use of No. 8 aggregate may result in more frequent overtopping of the structure and will increase the frequency of structure maintenance.**
- Installation**
  1. Lay out the location of the check dam.
  2. Excavate a cutoff trench into the channel bottom and ditch banks, extending it a minimum of 18 inches beyond the top of the ditch bank.
  3. Install and anchor filter fabric in the channel and cutoff trench.
  4. Place riprap in the cutoff trench and channel to the lines and dimensions shown in the construction plans. The center of each dam must be at least nine inches lower than the upstream points of contact between the riprap dam and channel banks (see Rock Check Dam Worksheet on page 101).
  5. Extend the riprap at least 18 inches beyond the top of the channel banks to keep overflow water from eroding areas adjacent to the channel banks before it overtops the channel.
  6. Place filter medium (INDOT CA No. 5 aggregate) on the up-slope side of the dam. Place filter medium over the entire face of the dam up to the base of the overflow weir notch.
  7. Stabilize the channel above the upstream dam.
  8. Install an erosion-resistant lining in the channel below the downstream dam. The lining should extend a minimum distance of six feet below the dam.

98 Chapter 7 October 2007

## CONCRETE WASHOUT

- residual loads due to potential to exceed the design capacity of the washout system. Small amounts of excess or residual concrete (not washout water) may be disposed of in areas that will not result in flow to an area that is to be protected.
- Install systems at strategic locations that are convenient and in close proximity to work areas and in sufficient number to accommodate the demand for disposal.
  - Install signage identifying the location of concrete washout systems.

- Location**
- Locate concrete washout systems at least 50 feet from any creeks, wetlands, ditches, lawn features, or storm drains/natural resource systems.
  - To the extent practical, locate concrete washout systems in relatively flat areas that have established vegetative cover and do not receive runoff from adjacent land areas.
  - Locate in areas that provide easy access for concrete trucks and other construction equipment.
  - Locate away from other construction traffic to reduce the potential for damage to the system.

- General Design Considerations**
- The structure or system shall be designed to contain the anticipated washout water associated with construction activities.
  - The system shall be designed, to the extent practical, to eliminate runoff from existing the washout system.
  - Runoff from a rainstorm or snowmelt should not carry wastes away from the washout location.
  - Washout will not impact future land uses (i.e., open spaces, landscaped areas, lawn sites, parks).
  - Washout systems/containment measures may also be utilized on smaller individual building sites. The design and size of the system can be adjusted to accommodate the expected capacity.
- Prefabricated Washout Systems/Containers**
- Self-contained sturdy containment systems that are delivered to a site and located at strategic locations for concrete disposal.

248 Chapter 7 October 2007


## CONCRETE WASHOUT

- Maintenance**
- Inspect daily and after each storm event.
  - Inspect the integrity of the overall structure including, where applicable, the containment systems.
  - Inspect the system for leaks, spills, and tracking of soil by equipment.
  - Inspect the polyethylene lining for failure, including tears and punctures.
  - Once concrete wastes harden, remove and dispose of the material.
  - Excess concrete should be removed when the washout system reaches 50 percent of the design capacity. Use of the system should be discontinued until appropriate measures can be initiated to clean the structure. Prefabricated systems should also utilize this criterion, unless the manufacturer has alternate specifications.
  - Upon removal of the solids, inspect the structure. Repair the structure as needed or construct a new system.
  - Dispose of all concrete in a legal manner. Reuse the material on site, recycle, or land the material in an approved construction/demolition landfill site. Recycling of material is encouraged. The waste material can be used for multiple applications including but not limited to washbays and building. The availability for recycling should be checked locally.
  - The plastic liner should be replaced after every cleaning; the removal of material will usually damage the lining.
  - The concrete washout system should be repaired or enlarged as necessary to maintain capacity for concrete waste.
  - Concrete washout systems are designed to promote proper evacuation. However, if the liquids do not evaporate and the system is near capacity it may be necessary to vacuum or remove the liquids and dispose of them in an acceptable method. Disposal may be allowed at the local sanitary sewer authority provided their National Pollutant Discharge Elimination System permits allow for acceptance of this material. Another option would be to utilize a secondary containment system or basin for further dewatering.
  - Prefabricated units are often pumped and the company supplying the unit provides this service.
  - Inspect construction activities on a regular basis to ensure supplier, contractors, and others are utilizing designated washout areas. If concrete waste is being disposed of improperly, identify the violators and take appropriate action.

252 Chapter 7 October 2007

## ROCK CHECK DAM

9. Additional sediment storage can be provided by excavating a small sediment trap on the upstream side of the check dam.
- Maintenance**
- Inspect within 24 hours of each rain event and at least once every seven calendar days.
  - If significant erosion occurs between dams, install an erosion-resistant liner in that portion of the channel.
  - Remove accumulated sediment when it reaches one-half the height of the dam to maintain channel capacity, allow drainage through the dam, and prevent large flow from displacing sediment.
  - Add riprap and aggregate as needed to maintain design height and cross section of the dam.
  - When dams are no longer needed, remove the riprap and aggregate and stabilize the channel, using an erosion-resistant lining if necessary. (Riprap and aggregate from the dam may be removed or utilized to stabilize the channel.)



October 2007 Chapter 7 99

## CONCRETE WASHOUT

- These systems are manufactured to resist damage from construction equipment and protect against leaks or spills.
- Manufacturer or supplier provides the containers. The project site manager maintains the system or the supplier provides complete service that includes maintenance and disposal.
- Units are often available with or without ramps. Units with ramps lend themselves to accommodate pump trucks.
- Remove as much mud as possible when washing out.
- Maintain according to the manufacturer's recommendations.

- Designed and Installed Units**
- These units are designed and installed on site. They tend to be less reliable than prefabricated systems and are often prone to failure. Concrete washout systems can be constructed above or below grade. It is not uncommon to have a system that is partly below grade with an additional containment structure above grade.
- Washout systems shall utilize a pit or formed area designed and maintained at a capacity to contain all liquid and concrete waste generated by washout operations.
  - The volume of the system must also be designed to contain runoff that drains to the system and rainfall that enters the system for a two-year frequency, 24-hour storm event.

- Below Grade System**
- A washout system installed below grade should be a minimum of ten feet wide by ten feet long, but sized to contain all liquid and waste that is expected to be generated between scheduled cleanout periods. The size of the pit may be limited by the size of polyethylene available. The polyethylene lining should be of adequate size to extend over the entire excavation.
  - Include a minimum 12-inch freeboard to reasonably ensure that the structure will not overtop during a rain event.
  - Line the pit with ten millimeter polyethylene lining to control seepage.
  - The bottom of excavated pit should be above the seasonal high water table.
- Above Grade System**
- A system designed and built above grade should be a minimum of ten feet wide by ten feet long, but sized to contain all liquid and waste that is expected to be generated between scheduled cleanout periods. The size of the containment system may be limited by the size of the



October 2007 Chapter 7 249

## CONCRETE WASHOUT

- When concrete washout systems are no longer required, the concrete washout systems shall be closed. Dispose of all hardened concrete and other materials used to construct the system.
- Holes, depressions and other land disturbances associated with the system should be backfilled, graded, and stabilized.

October 2007 Chapter 7 253

## ROCK CHECK DAM



100 Chapter 7 October 2007

## CONCRETE WASHOUT

- polyethylene available. The polyethylene lining should be of adequate size to extend over the berm or containment system.
- The system design may utilize an embankment, straw bales, sandbags, or other acceptable barriers that will maintain its shape and support the polyethylene lining.
- Include a minimum four-inch freeboard as part of the design.

- Washout Procedures**
- Do not have excess mud in the chutes or hopper after the pour. Every effort should be made to empty the chutes and hopper at the pour. The less material left in the chute and hopper, the quicker and easier the cleaning. Small amounts of excess concrete (not washout water) may be disposed of in areas that will not result in flow to an area that is to be protected.
  - At the washout location, scrape as much material from the chutes as possible before washing them. Use non-water cleaning methods to minimize the chance for waste to flow off site.
  - Remove as much mud as possible when washing out.
  - Stop washing out in an area if you observe water running off the designated area or if the containment system is leaking or overflowing and ineffective.
  - Do not back flush equipment at the project site. Back flushing should be restricted to the plant as it generates large volumes of waste that more than likely will exceed the capacity of most washout systems. If an emergency arises, back flush should only be performed with the permission of an on-site manager for the project.

- Materials**
- Minimum of ten millimeter polyethylene sheeting that is free of holes, tears, and other defects. The sheeting selected should be of an appropriate size to fit the washout system without seams or overlap of the lining (**designed and installed systems**).
  - Signage.
  - Orange safety fencing or equivalent.
  - Straw bales, sandbags (bags should be ultraviolet-stabilized geotextile fabric), soil material, or other appropriate materials that can be used to construct a containment system (**above grade system**).

October 2007 Chapter 7 250

## RUNOFF CONTROL




- Purpose**
- To reduce erosion in a drainage channel by slowing velocity of flow. (Check dams are commonly used (a) in channels that are eroding, but where permanent stabilization is impractical due to their short period of usefulness, and (b) in eroding channels where construction delays or weather conditions prevent timely installation of erosion-resistant linings.)
  - To reduce flow velocities in a drainage channel.
- Note: Do not use check dams in perennial streams.**
- Specifications**
- Contributing Drainage Area**  
Two acres maximum.
- Riprap Check Dam**
- Dam height:
    - Two feet maximum.
    - center of the dam at least nine inches lower than the points of contact between the upstream points of the riprap dam and channel banks.
  - Side slope ratio of 2:1 or flatter.
  - Spacing use of the upstream dam at same elevation as overflow weir of the downstream dam.

October 2007 Chapter 7 97

## ROCK CHECK DAM

- Rock Check Dam Worksheet**
- 21 or flatter
- Reemert riprap
- Geotextile fabric
- Filter medium on up-slope side of check dam
- S<sub>1</sub> = Spilling Depth
- NOTE: For maximum dimensions see the "Specifications" section of this measure.**



**NOTE: For maximum dimensions see the "Specifications" section of this measure.**

Source: Adapted from North Carolina Erosion and Sediment Control Planning and Design Manual, 1980.

October 2007 Chapter 7 101

THIS SHEET TO BE USED FOR  
EROSION CONTROL ONLY.

PERSON ONSITE RESPONSIBLE FOR EROSION CONTROL:  
ERIK ROBINSON  
LENNAR HOMES OF INDIANA, LLC  
PHONE: (317) 659-3200  
EMAIL: erik.robinson@lennar.com

REVISIONS		
DATE	DESCRIPTION	BY

**HWC**  
**ENGINEERING**  
INDIANAPOLIS • TERRE HAUTE  
LAFAYETTE • MUNCIE • NEW ALBANY  
www.hwengineering.com

SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
STORMWATER POLLUTION  
PREVENTION DETAILS


PROFESSIONAL SEAL  
KATHLEEN K. EICHNER  
REGISTERED PROFESSIONAL ENGINEER  
STATE OF INDIANA  
11400758  
NOT FOR CONSTRUCTION  
DRAWN BY  
TS  
CHECKED BY  
KE  
DATE  
APRIL 22, 2024  
SCALE  
AS SHOWN  
SHEET  
JOB NUMBER  
2020-235-F

C8.3  
STORMWATER POLLUTION  
PREVENTION DETAILS



Half (1/2) Yard – One Ton Bag

OTB-04: Half (1/2) Yard One Ton Bag™



Holds a half yard of material and 2,600 pounds. It has an open top and a closed bottom. It is perfect to deliver smaller quantities of product. It can be used as a washout bag too.

Size: 31"w x 31"l x 24"h  
Capacity: 1/2 Cubic Yard, 2,600 lbs.

Protocol for Propane Tank Staging

The purpose of this memo is to establish protocol regarding the staging of 100# propane tank storage, and the occasional utilization of propane heaters within a structure in Lennar communities. The Lennar Injury & Illness Prevention Plan (IIPP), Code of Safe Work Practices requires that any propane storage on construction site be properly managed. This will ensure a safe working environment for Associates, Trade Partners, and Homeowners. The following guidelines shall be implemented by all Associates managing propane fuel on a construction site:

- Propane Tank Storage:
  - The staging area for propane storage must be located at least 20' behind the street curb.
  - Concrete washout lot is a good location when there is adequate space.
  - Tanks must be placed a minimum of 10' away from any structure or combustible material.
  - Tanks must always be in the upright position.
  - Tank staging area must be inspected weekly.
  - A appropriate fire extinguisher must be readily available.
  - It is not recommended that any Associate attempt to fill or relocate any 100# tank without assistance. Proper lifting techniques should always be utilized. Tanks larger than 100lbs should be only moved or handled by the Propane Supplier.
  - Tanks are to be placed on a level platform:
    - The platform can be built by your framer.
    - The platform should be substantial enough to accommodate no more than ten (10) one hundred pound propane tanks.
    - The platform should have rails and/or side panels on three sides to prevent tipping of tanks.
    - The open side of the platform should be always be chained or equivalent product.
    - "**Danger – Propane Gas**" signage should be posted so viewable from the public street or walkway.

- Considerations When Utilizing Propane / Natural Gas Heaters:
  - Do not allow Trade Partners to place any fuel source (i.e. Kerosene, etc.) for temporary heat while working within a structure.
  - Only a qualified Plumber or Fuel Supplier may install, connect, or disconnect any heater to the fuel source.
  - A propane heater may only be utilized within a structure when the following guidelines are implemented:
    - The fuel source is located outside the structure as required (10' from structure or combustible material).
    - The heater is set on a non-combustible surface.
    - The heater is placed away from any combustible material... minimum of 3' to 6'... Higher btu units may require more clearance per manufacturer specifications.
    - Tank supply hoses must never be placed thru door openings; rather, place hoses thru window openings. Block window sash to prevent crushing of the supply line.
    - The heater is monitored while workers are within the structure.
    - There must be adequate ventilation to prevent carbon monoxide exposure.

Remember, we can never be so busy that we cannot be safe. Work Safe... Work Smart!



Author: Kevin Rager Page 1 of 1 12/11/19

Protocol for the Transition from Land Development to Vertical Construction

The purpose for this sequence checklist is to identify how the transition will occur when a Land Development Project Section is ready to begin Vertical Construction. Vertical Construction will operate under the approval of the Project's Construction General Permit originally filed with the State. A copy of this checklist will remain in the Project Management Log.

The VP of Operations will determine when a Project Site Section is ready for the Pre-Construction Meeting. He will direct the VP of Land Development and the Director of Construction to schedule the meeting. The Land Project Manager, Director of Construction, Area Construction Manager, Construction Manager, Alpha Field Manager, and Division Environmental Manager will meet at the Project Site (participants might vary based on availability) to verify the following:

- ✓ The Site Plat has been recorded and all Permits are valid.
- ✓ The Project Site is compliant with the SWPPP / The PML documents are current (i.e. NOS included in book).
- ✓ All amendments regarding approved changes made to the site Plan are properly logged in the Project Management Log.
- ✓ All site BMPs are maintained and functioning as intended.
- ✓ Individual lots released for construction have established building pads, and swales.
- ✓ Access to all public utilities (water, sewer, gas, and electric) are present on all lots released for vertical construction.
- ✓ Once a section is released for Vertical Construction, there will be an understanding as to who is responsible for BMP maintenance related to individual lots not yet released for construction start, and including maintenance related to common areas (entry, ponds, swales, and recreational areas).
- ✓ BMP requirements for individual lots have been identified as may be required by the Municipal Authority and have been communicated to the site Construction Manager:
  - Perimeter all fence requirements;
  - Approved BMPs identified;
  - Appropriate trash Containment.
- ✓ The BMP maintenance Trade Partner has been identified for Vertical Construction.
- ✓ The SWPPP Inspection Provider has been informed the Site now includes Vertical Construction.
- ✓ The Vertical Construction SWPPP Box is on site and compliant, or has been ordered and location determined.
- ✓ The Land Project Management Log has or will be moved from the Land SWPPP Box to the Vertical Construction SWPPP Box.
- ✓ Third Party Developer Projects: A Lennar Land Project Manager has been assigned to the Project for resolving Land related issues with the Third Party Developer.
- ✓ There is an agreement / understanding as to responsibility for BMP maintenance and Plan design issues related to swales, common areas, and individual lots not released for construction.
- ✓ A Construction Manager has been assigned to the community.
- ✓ The Municipal Vertical Construction Inspection process and contact person has been identified, and information provided to the Construction Manager.



✓ The following has been provided to the Vertical Construction Manager:

Re-Fueling Gas Operated Small Equipment Protocol

The purpose of this memo is to provide instruction to all Trade Partners regarding protocol when re-fueling gas operated small equipment on a Lennar construction site:

- All fuel containers must meet OSHA standards for worker safety compliance, and DOT standards because fuel is being transported in a motor vehicle on a public roadway. Approved fuel containers must meet the following standards:
  - Must contain less than five gallons of fuel;
  - Must be equipped with the following:
    - flash arrester screen;
    - spill proof spring-closing lid;
    - child proof cap;
    - vent to release pressure and minimal vapor;
    - properly equipped metal cans are preferred;
    - plastic cans may be tolerated when meeting the above standards.
  - An appropriate fire extinguisher must be on site at all times when gas operated equipment is present and/or re-fueling is occurring.
- Proper Re-fueling of small equipment on any Lennar construction site falls under the SWPPP (Storm Water Pollution Prevention Plan) guidelines for each construction site. Since fuels are considered hazardous substances by the USEPA, utilizing proper re-fueling protocol is important. Considering that all OSHA /DOT requirements have been satisfied, proper re-fueling on a construction site should consider the following guidelines for compliance to the SWPPP:
  - Gas operated equipment and fuel containers should be securely staged on a non-permeable ground barrier or pan-like device;
  - Re-fueling of equipment may only be performed on a Lennar construction site when equipment is properly staged to prevent the spillage of fuel onto the ground.
  - In the event any fuel or motor fluid is spilled onto the ground, the contractor must immediately collect and remove polluted soils from the construction site for proper disposal by the contractor.
  - Leaking fuel containers or motor equipment should be removed from the construction site for proper repair / replacement.
  - Any spill of fuel and/or motor oil must be contained and cleaned by the subcontractor. Soils that meet or exceed "reportable" quantities must be immediately contained and reported to the site Construction Manager. The Construction Manager will assure proper protocol is followed for any clean-up of the spill, and determine if the Sub-Contractor is capable of managing the clean-up effort. The Construction Manager will determine when spill clean-up should be done by a professional remediation contractor.



Author: Kevin Rager Page 1 of 1 12/11/19

- Electronic access or paper copy of a full set of approved Project Plans;
  - Location of all outfalls and where stormwater discharges from the project site;
  - Community lot listing (including phase building order;
  - Community information;
  - Vertical Construction has been posted on SafetyPro and CM has access for inspections.
- ✓ The following items have been located on the project site for Vertical Construction as required by the SWPPP:
  - Portable Toilet is staged to required protocol;
  - Concrete Washout with proper signage.

Note: Any action items will be noted in punch list form. Punch list items will be accomplished in a timely manner and reported to the VP of Operations. Should punch items continue to be unresolved, the VP of Operations may choose to delay Vertical Construction until all items are completed, or if time runs out interfere with Vertical Construction Phase approve proceeding with construction.

Brick Mortar Washout Protocol – Lennar BMP

As required by the Federal EPA, the State of Indiana, and Local Municipal Authorities, Lennar has designed and implemented a Storm Water Pollution Prevention Plan (SWPPP) for all construction sites. The SWPPP protects waterways from construction storm water run-off. Improper washout practices on construction sites can be a significant contributor to the pollution of surrounding waterways when stormwater run-off is poorly managed. Lennar's SWPPP prohibits unlawful washout to occur on any construction site. In an effort to provide specific direction to Trade partners regarding brick mortar washout, the following instructions are provided:

Lennar Individual Lot Construction Sites:

- Brick mortar washout is never allowed onto unprotected ground (this includes temporary graveled construction entrances, often referred to the temp drive).
- Any spillage of brick mortar washout onto the ground shall be removed and contained immediately.
- Equipment utilized for the mixing of brick mortar must be staged on a non-permeable barrier to protect the ground from washout spillage.
- Brick mortar washout must be contained within a water tight (non-permeable) container (i.e. non-permeable washout bag, etc).
- Lennar will provide one – half (1/2) yard washout container bag for each individual construction site. It will be included with the delivery of brick materials. When possible, the brick mason is encouraged to maintain usable bags for reuse on Lennar job sites.
- Brick mortar washout must be made into a semi-solid condition before being emptied into an approved container (i.e. the adding of sand to mixer washout to absorb fluid).
- The washout container bag should be placed at curb for trash pickup. When possible, the container should be placed in the provided trash dumpster, or, its content emptied into the Site concrete washout.
- All hardened brick mortar and unused bags of mortar shall be treated as brick trash; collected and properly disposed per the Site trash disposal requirement. Unused mortar bags should never be broken open and stored onto the ground or temp drive.
- All fly-away trash (paper, wrappings, etc.) shall be contained in trash bags, or equivalent container; collected daily and properly disposed per the Site trash disposal requirement. Fly-away trash should never be left uncontained on the construction site.

In addition to the above practices, the following requirements shall apply for washout of brick mortar for all Lennar Townhome construction sites:

- The staging area for mixing brick mortar shall be adjacent to the Site concrete washout.
- All Brick mortar washout shall occur (in semi-solid condition) directly into the concrete washout in lieu of utilizing a washout bag.
- Lennar will not provide a washout container bag for Townhome construction sites.



Author: Kevin Rager Page 1 of 1 12/11/19

Protocol for when BMP Maintenance is Required for a Permitted Construction Site.

**Introduction** - The purpose of this protocol is to provide guidance as to when BMP maintenance is required on a permitted site, and should be noted on an inspection report. On occasion, guidance may be re-directed as required by the enforcement of applicable regulation.

When is maintenance required on a BMP?

- When the BMP is not permitted by applicable regulation.
- When the BMP is not installed correctly.
- When the BMP has failed.
- When the BMP no longer functions as intended.
- When the BMP is being utilized improperly.
- When the BMP is damaged to the extent that sediment is leaving or about to leave the site.

Note: Completed inventory home awaiting permanent stabilization. Continue to inspect and maintain perimeter BMPs routinely. A note will be made in comment section of inspection report regarding lot status.

Note: Transfer of Ownership of a home awaiting permanent stabilization. Perform inspection routinely. Only note maintenance when BMP is about to fail, or when BMP has failed, and creates the potential of a release of sediment into a swale, waterway, street, or stormwater inlet. A note will be made in the comment section of inspection report regarding the lot status.

Third Party SWPPP Inspector Responsibilities:

- The active project site must be inspected noting all BMP maintenance required.
- Rain event inspections will be specific to maintenance required due to the event.
- Inspections need even-flow to avoid bursts of high volume repair and costs related to it.
- Failed printer issues that prevent the provision of a report being placed in the Inspection Log Book, must be resolved within the next day. The Site Manager should be notified.
- Maintenance related to a Third Party Developer should not be listed as an action item on the report. It may be added to comments if the item is a significant failure of a BMP. The CM should be notified.
- When you have a question regarding an item on the report, the site CM is your immediate contact. Questions needing immediate response should communicated via phone or text.
- The Third Party Inspector will meet with the CM / LPM after every inspection to review maintenance items. The CM /LPM will provide final direction regarding items to be included in the report.

BMP Maintenance Trades Attention:

- Make certain all repairs on a report are accomplished within five days of the report;
- Notify the site CM when you will begin repairs and when you are finished;
- Repairs that are reported to be overnighted must be accomplished within the next day;
- When you have a question regarding an item on the report, the site CM is your immediate contact. Questions needing immediate response should communicated via phone or text.



Author: Kevin Rager Page 1 of 1 12/11/19

Solid Waste Trash Removal Protocol for an Individual Lot

The necessity to maintain clean and orderly job sites in our communities is a significant objective for Lennar Homes of Indiana, Inc. It is important that the first impression when entering a community or a new construction home, there is an appearance of the site being managed to achieve a clean and orderly job site. Keeping every job site free from accumulation of trash and debris will be beneficial to the builder, our customers, our homeowners, and provide a clean, safe, and professional work environment for all our Trade Partners. **Clean site... Done right... On time.**

Non-Construction trash (i.e. drink containers, food wrappers, other personal trash, etc.) shall not remain on any Lennar job site. Non-Construction trash must be removed from the site by the Trade Partner. All loose or fly-away construction trash must be contained in a trash bag or other disposable container.

Communities where trash containers (i.e. dumpsters) are not utilized for trash containment and removal. When allowed by the enforcement of applicable regulations, accumulated trash will be removed from each job site on a regularly scheduled basis, once every week. The Trade Partner providing solid waste removal services will provide the following on a weekly basis:

- Create and maintain a weekly trash route to collect trash from each job site.
- Remove all trash material left piled at the curb and/or left in the garage of each job site for disposal. (Note: Garage trash removal will begin after the drywall phase is completed, and will include sweeping the garage floor).

The following Trade Partners are allowed to leave construction trash in one pile placed in the front yard, located by the curb. All loose or fly-away construction trash must be contained in a trash bag or other disposable container. They are the following:

- Framer
- Brick Mason
- Roof Shingle Installer
- Wood Siding Installer



Author: Kevin Rager Page 1 of 4 12/11/19


THIS SHEET TO BE USED FOR EROSION CONTROL ONLY.

PERSON ONSITE RESPONSIBLE FOR EROSION CONTROL:

ERIK ROBINSON  
LENNAR HOMES OF INDIANA, LLC  
PHONE: (317) 659-3200  
EMAIL: erik.robinson@lennar.com

REVISIONS

DATE	DESCRIPTION	BY



SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
STORMWATER POLLUTION  
PREVENTION DETAILS




DRAWN BY TD  
CHECKED BY KE  
DATE APRIL 22, 2024  
SCALE AS SHOWN  
SHEET

JOB NUMBER 2020-235-F


C8.4  
STORMWATER POLLUTION  
PREVENTION DETAILS



File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F Landscape Plan.dwg, Layout: L1.0 By: keithhorn  
Plot Date: Apr 24, 2024 Plot Time: 2:01pm



Call 811 or 800-382-5544 Before you Dig!



#### LANDSCAPE LEGEND:

#	XXX	QUANTITY / KEY
•		SHADE TREE
○		DECIDUOUS SHRUB
●		EVERGREEN SHRUB

KEY	QTY	BOTANICAL NAME	COMMON NAME	CALIPER	HGT	ROOT	SPACING	REMARKS
SHADE TREES								
LIQ-S	2	LIQUIDAMBAR STYRACIFLUA 'ROTUNDALOBA'	FRUITLESS SWEETGUM	2"	-	B&B	SEE PLAN	CENTRAL LEADER
QUE-I	3	QUERCUS IMBRICARIA	SHINGLE OAK	2"	-	B&B	SEE PLAN	CENTRAL LEADER
SHRUBS								
HYD-P	29	HYDRANGEA PANICULATA 'LITTLE LIME'	LITTLE LIME HYDRANGEA	5 GAL.	18"	CONTAINER	SEE PLAN	FULL IN POT
ILE-G	35	ILEX GLABRA 'DENSEA'	DENSE COMPACT INKBERRY	5 GAL.	18"	CONTAINER	SEE PLAN	FULL IN POT
ITE-V	16	ITEA VIRGINICA	VIRGINIA SWEETSPICE	5 GAL.	18"	CONTAINER	SEE PLAN	FULL IN POT

#### LANDSCAPE GENERAL NOTES:

- NOTIFY THE LANDSCAPE ARCHITECT IF SITE CONDITIONS ARE UNSUITABLE OR OTHER UNFORESEEN CONDITIONS ARE FOUND.
- CONTRACTOR SHALL LOCATE AND VERIFY EXISTENCE OF ALL UTILITIES PRIOR TO STARTING WORK, AND SHALL COORDINATE ALL LANDSCAPE WORK WITH CIVIL AND ELECTRICAL DRAWINGS, PROVIDE ADEQUATE MEANS OF PROTECTION OF UTILITIES AND SERVICES DESIGNATED TO REMAIN, AND REPAIR UTILITIES DAMAGED DURING OPERATIONS AT CONTRACTOR'S EXPENSE.
- ALL PLANT MATERIAL SHALL BE IN CONFORMANCE WITH THE "AMERICAN STANDARD FOR NURSERY STOCK" ANSI Z60.1 LATEST EDITION.
- ALL LANDSCAPING SHALL BE INSTALLED PER LOCAL ZONING REQUIREMENTS.
- CONTRACTOR IS REQUIRED TO NOTIFY LANDSCAPE ARCHITECT OF ANTICIPATED INSTALLATION DATES ONE WEEK PRIOR TO ARRIVAL OF PLANT MATERIAL ON SITE. THE LANDSCAPE ARCHITECT WILL BE AVAILABLE TO REVIEW AND TAG TREES AT THE NURSERY. THE LANDSCAPE ARCHITECT SHALL INSPECT THE QUALITY OF PLANT MATERIAL ON-SITE BEFORE PLANTS ARE PLACED IN THE GROUND. THE LANDSCAPE ARCHITECT MAY REJECT ANY PLANT MATERIAL, AND IT SHALL BE REPLACED WITH ACCEPTABLE MATERIAL BY THE LANDSCAPE CONTRACTOR.
- NO SUBSTITUTIONS FOR THE SPECIFIED LANDSCAPE MATERIAL ARE ALLOWED UNLESS ACCEPTED IN WRITING BY THE LANDSCAPE ARCHITECT PRIOR TO PLANTING

OPERATIONS.

- CONTRACTOR TO THOROUGHLY WATER ALL PLANT MATERIAL WITHIN SIX (6) HOURS OF INSTALLATION AND AS SPECIFIED THROUGHOUT THE MAINTENANCE PERIOD. THE OWNER IS RESPONSIBLE FOR WATERING PER CONTRACTOR'S WRITTEN MAINTENANCE INSTRUCTIONS THROUGHOUT THE GUARANTEE PERIOD. SEE NOTE 19. FOR MAINTENANCE AND GUARANTEE PERIOD REQUIREMENTS.
- THE SITE IS TO BE LEFT IN A CLEAN AND NEAT CONDITION AT ALL TIMES.
- MULCH: FINELY SHREDDED HARDWOOD BARK, AGED TO BE APPLIED AT A THREE (3) INCH DEPTH FOR ALL PLANTING BEDS AND TREE SAUCERS. RENEWAL OF MULCH DURING THE GUARANTEE PERIOD SHALL BE PERFORMED BY THE OWNER AS NEEDED. SEE NOTE 19. FOR MAINTENANCE AND GUARANTEE PERIOD REQUIREMENTS. ALL INTERIOR PARKING LOT PLANTING AREAS TO RECEIVE MULCH UNLESS NOTED OTHERWISE.
- SEED WITH TURF GRASS/LAWN ALL DISTURBED AREAS NOT SCHEDULED FOR OTHER IMPROVEMENTS.
- ALL PLANTING BEDS WITH ADJOINING LAWN AREAS SHALL BE EDGED WITH A SPADE, UNLESS NOTED OTHERWISE.
- CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUALITY AND QUANTITIES

SUFFICIENT TO COMPLETE THE PLANTING AS SHOWN ON DRAWINGS. IF THERE IS A DISCREPANCY BETWEEN THE PLANS AND THE PLANT LIST, THE PLANS SHALL TAKE PRECEDENCE. IF THERE IS A DISCREPANCY BETWEEN THE QUANTITY OF PLANT SYMBOLS AND THE QUANTITY LABEL, THE PLAN SYMBOLS SHALL TAKE PRECEDENCE.

- NO PLANT SHALL BE PUT INTO THE GROUND BEFORE ALL PAVEMENT AND ROUGH GRADING HAS BEEN FINISHED AND APPROVED. LANDSCAPE INSTALLATION SHALL NOT BE PHASED UNLESS APPROVED BY THE LANDSCAPE ARCHITECT. ALL PLANT MATERIAL SHALL BE INSTALLED IN ONE MOBILIZATION AT THE END OF THE PROJECT UNLESS OTHERWISE NOTED.
- PRIOR TO PLANTING, THE LOCATIONS OF ALL TREES AND SHRUBS SHALL BE STAKED FOR APPROVAL BY THE OWNER'S REPRESENTATIVE.
- STAKES AND GUY WIRES USED TO SUPPORT PLANTING MATERIALS SHALL BE REMOVED AFTER ONE YEAR.
- ALL PLANTS SHALL BE BALLED AND WRAPPED OR CONTAINER GROWN AS SPECIFIED. NO CONTAINER GROWN STOCK WILL BE ACCEPTED IF IT IS ROOTBOUND. ALL ROOT WRAPPING MATERIAL MADE OF SYNTHETICS OR PLASTICS SHALL BE REMOVED AT THE TIME OF PLANTING. ALL TWINE OR ROPE SHALL BE REMOVED FROM AROUND CROWN OF TRUNK TO PREVENT GIRDLING OF TREE. ALL PLANTS SHALL BE PLANTED SO THAT THE ROOT CROWN IS PLANTED 1/2 - 1" ABOVE GRADE LEVEL.

- WITH CONTAINER GROWN STOCK, THE CONTAINER SHALL BE REMOVED AND THE CONTAINER BALL SHALL BE CUT THROUGH THE SURFACE IN THREE VERTICAL LOCATIONS.

- CONTRACTOR SHALL REPAIR ANY DAMAGE TO PROPERTY FROM PLANTING OPERATIONS AT NO COST TO THE OWNER.


- MAINTENANCE PERIOD: CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PLANT MAINTENANCE AND REPLACEMENT THROUGHOUT CONSTRUCTION. UPON RECEIVING WRITTEN ACCEPTANCE FROM THE LANDSCAPE ARCHITECT, CONTRACTOR'S MAINTENANCE PERIOD IS COMPLETE AND GUARANTEE PERIOD BEGINS. OWNER ACCEPTS MAINTENANCE OF PLANTS AND LANDSCAPE BEDS AT START OF GUARANTEE PERIOD PER CONTRACTOR'S WRITTEN MAINTENANCE INSTRUCTIONS.

- WARRANTY: LANDSCAPE CONTRACTOR SHALL WARRANTY ALL NEW PLANT MATERIAL THROUGH ONE YEAR FROM THE TIME OF WRITTEN ACCEPTANCE BY THE LANDSCAPE ARCHITECT ESTABLISHING THE START OF THE GUARANTEE PERIOD.

- REPLACEMENTS: AT THE CONCLUSION OF THE GUARANTEE PERIOD, THE LANDSCAPE ARCHITECT WILL PERFORM A FINAL INSPECTION. ANY MATERIAL DEEMED DEAD OR UNSATISFACTORY BY THE LANDSCAPE ARCHITECT AT THAT TIME WILL BE REPLACED EQUIVALENT IN SIZE AND SHAPE AT NO COST TO THE OWNER. REPLACEMENT PLANT MATERIAL IS TO BE PROVIDED WITH AN ADDITIONAL ONE-YEAR WARRANTY AND SHALL BE REPLACED IF DEAD, DYING, OR OTHERWISE UNACCEPTABLE TO THE LANDSCAPE ARCHITECT ONE FINAL TIME AT THE CONCLUSION OF THAT PERIOD.

#### REVISIONS


DATE	DESCRIPTION	BY



**HWC**  
ENGINEERING

INDIANAPOLIS - TERRE HAUTE  
LAFAYETTE - MUNCIE - NEW ALBANY  
www.hwcengineering.com

## SUMMERTON AMENITY AREA MCCORDSVILLE, INDIANA LANDSCAPE PLAN



*Christopher K. Eickhorn*


DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	
SHEET	

# L1.0


LANDSCAPE PLAN




File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F Landscape Plan.dwg, Layout: L1.1 By: keichhorn Plot Date: Apr 24, 2024 Plot Time: 2:01pm




1 TYPICAL TREE PLANTING DETAIL  
NOT TO SCALE




4 PLANTING BED PERIMETER  
NOT TO SCALE



# SHRUB PLANTING DETAIL  
NOT TO SCALE



3 PERENNIALS & GRASSES DETAIL  
NOT TO SCALE



5 PLANT LAYOUT  
NOT TO SCALE


#### PLANTING NOTES:

- PLANT LOCATION SHALL BE STAKED BY THE CONTRACTOR AND REVIEWED BY THE LANDSCAPE ARCHITECT BEFORE PLANTING OPERATIONS COMMENCE. ADJUST AS REQUESTED TO AVOID UTILITY CONFLICTS.
- NOTE THAT PLANT LIST QUANTITIES ARE FOR THE CONTRACTOR'S CONVENIENCE ONLY. CONTRACTOR SHALL VERIFY ALL QUANTITIES PRIOR TO SUBMITTING THEIR BID FOR THIS PROJECT.
- ALL PLANT MATERIAL SHALL CONFORM TO ANSI Z60.1 STANDARDS. LANDSCAPE ARCHITECT PRESERVES THE RIGHT TO REJECT ANY PLANT MATERIAL NOT MEETING INDUSTRY STANDARDS.
- STREET TREES ARE TO BE SPACED AT 40' O.C., TYPICAL. HOWEVER, TREES WILL REQUIRED A MINIMUM 10' SEPARATION FROM SANITARY SEWER MAINLINES/LATERALS AND WATER MAINS.
- PLANTING BEDS SHALL RECEIVE A 3" LAYER OF SHREDDED BARK MULCH.
- SEED AND STRAW MULCH ALL LAWN AREAS DISTURBED DURING CONSTRUCTION, UNLESS NOTED OTHERWISE.
- REMOVE ALL STAKING AS SOON AS THE TREE HAS GROWN SUFFICIENT ROOTS TO OVERCOME THE PROBLEM THAT REQUIRED THE TREE TO BE STAKED. STAKES SHALL BE REMOVED NO LATER THAN THE END OF THE FIRST FULL GROWING SEASON AFTER PLANTING. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REMOVED STAKING MATERIALS.
- EXCAVATION FOR TREE PITS SHALL BE 2.5 TIMES DIAMETER OF ROOT BALL, SET ON UNDISTURBED SUBBASE.
- REMOVE ALL RIBBONS OR TREE TAGS AFTER APPROVAL BY LANDSCAPE ARCHITECT.
- TREES SHALL BE ALIGNED AND PLUMB AFTER WATERING AND SETTLING.
- PRUNE TREES AS REQUIRED, AND AS DIRECTED BY THE LANDSCAPE ARCHITECT.
- STAKING AND GUYING TO BE AT THE DISCRETION OF THE CONTRACTOR. TREES SHALL NOT SWAY EXCESSIVELY.
- TREE SHALL BE TURNED SO BEST SIDE FACES FRONT
- CONTRACTOR SHALL INSTALL TWO REINFORCED RUBBER HOSE SECTIONS WITH A DOUBLE STRAND OF #14 WIRE. WRAP WIRE A MINIMUM OF TWO TIMES AROUND EACH POST.
- THE FIRST STAKE SHALL BE DIRECTLY SOUTHWEST OF THE TREE TRUNK.

PREPARED BY:  
HWC ENGINEERING  
135 N. PENNSYLVANIA ST., SUITE 2800  
INDIANAPOLIS, IN 46204  
P: 317-347-3663

#### REVISIONS

DATE	DESCRIPTION	BY



**HWC**  
**ENGINEERING**

INDIANAPOLIS - TERRE HAUTE  
LAFAYETTE - MUNCIE - NEW ALBANY  
www.hwcengineering.com

SUMMERTON AMENITY AREA  
MCCORDSVILLE, INDIANA  
LANDSCAPE DETAILS

PROFESSIONAL ENGINEER  
STATE OF INDIANA  
11400758  
NOT FOR CONSTRUCTION

*Kristopher K. Eichhorn*

DRAWN BY TS	JOB NUMBER 2020-235-F
CHECKED BY KE	
DATE APRIL 22, 2024	
SCALE AS SHOWN	

SHEET

L1.1

LANDSCAPE DETAILS

File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenty\Design\CAD\20235-F McCordsville Standard Details.dwg, Layout: Detail 1 of 10  
Plot Date: Apr 24, 2024  
Plot Time: 2:01pm  
By: leitchhorn

# McCORDSVILLE, INDIANA

## TOWN STANDARDS

### DIRECTIONS FOR USE

- 1.) The entire set of full size drawings shall be attached to the construction drawings and shall be considered part thereto. A partial set may be used for small projects when whole sections are not applicable. Approval of use of a partial set will be made by the Town Engineer at the time of approval of the construction drawings.
- 2.) Details prepared by outside sources shall not be included in the construction drawings when the said drawings cover work which is covered by McCordsville Standards.
- 3.) Individual McCordsville Standards that do not apply may be crossed out by the design engineer through placement of a single large X over the detail. Minor reference notations may be placed adjacent to individual standard titles for coordination. However, the standards themselves shall not be modified in any way.
- 4.) Details prepared by outside sources covering work which is not covered by the McCordsville Standards are the sole responsibility of the design engineer and shall be placed on sheets other than the McCordsville Standards.


### GENERAL NOTES


- 1.) Contractor shall verify the exact location of all existing utilities at least 48 hours prior to any construction or excavation. All utilities shall be adequately supported to minimize damage. The contractor shall be responsible for repairing damaged utilities to the satisfaction of the Town of McCordsville and the owner of the utility.
- 2.) All benchmarks and elevations shall be from NAD 1983 (Conus) Datum. All coordinates shall conform with the Hancock County GIS standard.
- 3.) Wherever proprietary equipment is specified, all proposals for substitution shall be submitted in writing to the Town Engineer and shall be subject to the findings of the Town Engineer and may be appealed to the Public Works Committee.
- 4.) Whenever trench opening encroaches within 5 feet of an existing or proposed street or sidewalk, "B"-Borrow compacted in accordance with the most recent INDOT standard specifications shall be required. Approved backfill may be used under proposed sidewalks provided sidewalks are constructed six months after backfilling of the trench.
- 5.) Installation of or provisions for installation of all underground utilities (including service laterals) to be placed under pavement areas shall be established prior to the construction of pavements including lime stabilization.


### REVISION LOG


SHEET NO.	SHEET DESCRIPTION	ISSUED	REVISED	REVISED	REVISED	REVISED
SHEET 1	DIRECTIONS FOR USE, GENERAL NOTES & REVISION LOG	06/14/05				
SHEET 2	RIGHT-OF-WAY SECTIONS & PAVEMENT SPECIFICATIONS	06/14/05				
SHEET 3	RIGHT-OF-WAY DETAILS	06/14/05				
SHEET 4	UTILITY LOCATION GUIDELINES	06/14/05				
SHEET 5	DRIVE WAYS, SIDEWALKS, AND HANDICAP RAMPS	06/14/05				
SHEET 6	STORM SEWER STRUCTURE DETAILS	06/14/05				
SHEET 7	STORM SEWER BEDDING DETAILS AND GENERAL NOTES	06/14/05				
SHEET 8	SANITARY SEWER SPECIFICATIONS	06/14/05				
SHEET 9	SANITARY SEWER DETAILS	06/14/05				
SHEET 10	SANITARY SEWER LIFT STATION STANDARDS & GUIDELINES	06/14/05				

### TOWN OF McCORDSVILLE

  
THOMAS STRAYER  
TOWN COUNCIL PRESIDENT

  
GRANT ADAMS  
PUBLIC WORKS CHAIRMAN

  
TONYA GALBRAITH  
TOWN MANAGER

  
RONALD D. CRIDER  
PUBLIC WORKS COMMISSIONER

HOLEY MOLEY SAYS  
"DIG SAFELY"



"IT'S THE LAW"  
CALL 2 WORKING DAYS BEFORE YOU DIG  
1-800-382-5544  
CALL TOLL FREE  
PER INDIANA STATE LAW ICB-1-26,  
IT IS AGAINST THE LAW TO EXCAVATE  
WITHOUT NOTIFYING THE UNDERGROUND  
LOCATION SERVICE TWO (2) WORKING DAYS  
BEFORE COMMENCING WORK.

### REVISIONS

REV. NO.	DESCRIPTION	DATE



RECOMMEND  
FOR APPROVAL

  
DESIGN ENGINEER

7/12/05  
DATE

### TOWN OF McCORDSVILLE

### DIRECTIONS FOR USE, GENERAL NOTES & REVISION LOG

SHEET  
1  
OF  
10



LIME STABILIZATION

DESCRIPTION: This work shall consist of upgrading of mostly fine grained soils by uniformly mixing small amounts of lime (3 to 6%) by weight to provide a working platform for the road subbase.

MATERIALS: Material shall meet the requirements of the Section 913 of the INDOT Standard Specification

LIME:

- a)High calcium or dolomite Hydrated Lime (Ca(OH)2 +Mg(OH)2) shall have a minimum of 90% total available calcium hydroxide content and the hydrates must contain no more than 5 % carbon dioxide content if sampled at the lime plant, or no more than 7 % if sampled at the job site.
- b)High calcium hydrated lime shall have a minimum available calcium hydroxide Ca(OH)2 content of 90%. The method used for determination of available lime shall conform to AASHTO T219-72 or ASTM C25.
- c)Maximum Mechanical Moisture content shall be 4%.
- d)Gradation: All hydrated lime shall conform to the following gradation requirement. At least 85% passing a #200 sieve (0.075 mm). Determination of particle size shall conform to the provision for wet sieving on ASTM C110.
- e)Other lime products such as quicklime - high calcium (CaO) or Dolomite (CaO- MgO) may be substituted with written approval by the Town Engineer. By-product lime (kiln dust) shall not be used.

WATER: Water used for lime modification shall be in accordance with all applicable requirements of 913 and 913.01 of the INDOT Specifications, except that the minimum acceptable pH is 6.5.

STORAGE AND HANDLING

- a)Hydrated lime shall be stored and handled in closed weatherproof containers until immediately before distribution on the subgrade. Hydrated lime in bags shall be stored in weather protected conditions with adequate protection from ground dampness, and the facility shall be approved by the Town Engineer prior to commencement of any lime work.
- b)Each shipment shall be accompanied by a bill of loading and by a certificate of compliance stating conformance to the applicable specification requirements. The certificate of compliance shall be submitted to the Town Engineer prior to the proof roll on the subgrade.
- c)The Contractor shall take appropriate preventive and protective (safety) measure that shall be exercised by those working with this material. All safety measures shall comply with applicable OSHA requirements.

MIXTURE COMPOSITION:

- a)Mix Design: Lime will be proportioned within a range of 3 to 6 percent of soil (oven - dry basis). The required proportion of lime will be recommended by the Contractor and approved by the Town Engineer prior to construction using samples of soil and lime. The Town Engineer reserves the right to make such adjustments of lime proportioning as are considered necessary during the progress of the work within the range specified.
- b)Source or type of lime shall not be changed during the progress of the work without permission of the Town Engineer. However, the Town Engineer may choose to use different types of lime on different portions of the project, but shall not be mixed.

CONSTRUCTION REQUIREMENTS:

- a)Temperature and Weather Limitations: No lime modification shall be performed at a soil temperature less than 45 degrees Fahrenheit (7 degrees C) and the air temperature rising, of subgrade soil when it is measured 4" (100 mm) below the surface. Lime shall not be mixed with frozen soils or with soil containing frost.
- b)Preparation of Existing Roadway: All deleterious material, such as stumps, roots, turf, etc. and aggregate larger than 3" (75 mm) shall be removed. Any soft organic soils shall be removed as directed by the Town Engineer.
- c)Spreading of Lime: The roadbed shall be scarified or disked prior to distribution of the lime. The machine shall be of such design that a visible indication is given at all times that the machine is cutting to the required depth; The lime shall than be distributed uniformly over the surface by means of cyclone, screw-type, or pressure manifold type distributor. The Town Engineer may reject any procedure which does not provide even distribution of lime.

Lime shall not be applied when wind conditions are such that blowing lime becomes objectionable to adjacent property owners or creates a hazard to traffic on adjacent roadways.

The spreading of lime shall be limited to the amount which can be incorporated after mixing. In no case shall compaction be started later than three (3) days after mixing into the soil. In the event that rain intervenes causing cessation of work and exposure of the lime to washing or blowing, the Town Engineer may require additional lime to be spread.

- d)Mixing: The lime, soil and water (if necessary) shall be thoroughly blended by rotary speed mixers or a disc harrow. The mixing shall continue until a homogeneous layer of the required thicknesses has been obtained and clods are broken down so that 100 %, exclusive of rock particle, will pass a one-inch (25 mm) sieve and at least 60% will pass a 4 sieve (4.75 mm). The loose thickness of a single lime modified layer shall not exceed eight (8) inches (200 mm) if a disc harrow is used and fourteen (14) inches (355 mm) if a rotary speed mixer is used.
- e)Compaction: Compaction of the mixture shall begin as soon as is practicable mixing unless approved by the Town Engineer. If compaction is to be delayed, the surface of the lime modified soil shall be crown-graded and sealed by either blade dragging or light rolling immediately after mixing.


Compaction shall be continued until the Contractor has shown that the lime modified layer has a density not less than 100 percent within the special subgrade treatment zone and/or 95 percent below special subgrade treatment zone, of the maximum dry density.

The standard dry density of the lime treated soil shall be obtained by AASHTO 99. The field in-place dry density will be obtained by the Contractor in accordance with AASHTO T 191.

Aeration by means of further mixing, or the addition of water and further mixing, may be required by the Town Engineer to achieve the required compaction.


- f) Finishing: When compaction of the lime modified soil is nearing completion, the surface shall be shaped to the required line, grades and cross section, and compaction continued until uniform and adequate compaction if obtained.

The Town Engineer reserves the right to determine the actual thickness of the completed and cured layer by coring or other means at the owner's expense, and any deficient areas shall be acceptably corrected.



MULTI-USE PATH DETAIL

SCALE: NONE



LOCAL ROAD

d = 12"

- ① 1" HMA, TYPE A, 9.5 MM SURFACE
- ② 3" HMA, TYPE A, 19.0 MM INTERMEDIATE
- ③ 4" COMPACTED AGGREGATE BASE #53  
4" COMPACTED AGGREGATE BASE #2

LOCAL ARTERIAL ROAD

d = 15"

- ① 1" HMA, TYPE A, 9.5 MM SURFACE
- ② 3" HMA, TYPE A, 19.0 MM INTERMEDIATE
- ③ 3" HMA, TYPE A, 25.0 MM BASE
- ④ 4" COMPACTED AGGREGATE BASE #53  
4" COMPACTED AGGREGATE BASE #2

COLLECTOR ROAD

d = 18"

- ① 1" HMA, TYPE B, 9.5 MM SURFACE
- ② 3" HMA, TYPE B, 19.0 MM INTERMEDIATE
- ③ 6" HMA, TYPE B, 25.0 MM BASE
- ④ 4" COMPACTED AGGREGATE BASE #53  
4" COMPACTED AGGREGATE BASE #2

PAVEMENT CONSTRUCTION

SCALE: NONE

PAVEMENT CONSTRUCTION

- 1.) Subgrade shall be lime stabilized per the lime stabilization specification on this sheet.
- 2.) Adequacy of existing subgrades shall be determined solely by the town based on a contractor performed proof roll with a fully loaded tri-axle dump truck. A proof roll shall be performed on all street subgrade prior to placing stone, under drains and installing curb. A second proof roll shall be performed on the stone prior to placing the asphalt base. The adequacy of the stone and subgrade shall be determined solely by the town.
- 3.) Place tack coat in accordance with the most recent INDOT standard specifications for asphalt pavement sections.
- 4.) Local Arterial Road is defined as a low capacity and low speed roads within subdivisions whose function is to become a collector street for local subdivision traffic and move traffic from within the community to other locations in the community and to the existing county roads. Whether a street is defined as a Local Arterial Road is at the sole discretion of the Public Works Commissioner.
- 5.) Installation of or provisions for installation of all underground utilities (including service lines and laterals) shall be placed prior to the construction of pavement including lime stabilization.

REVISIONS		
REV. NO.	DESCRIPTION	DATE




RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. C. ...</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>...</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE

<b>TOWN OF McCORDSVILLE</b>	<b>SHEET 2 OF 10</b>
<b>TOWN STANDARDS RIGHT-OF-WAY SECTIONS &amp; PAVEMENT SPECIFICATIONS</b>	



File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F-McCordsville Standard Details.dwg, Layout: Detail 3 of 10  
Plot Date: Apr 24, 2024  
Plot Time: 2:01pm  
By: leichhorn



UNDERDRAIN DETAIL  
SCALE: NONE

STREET SIGN STANDARDS

All traffic and road name signs in and as a result of a major subdivision or a minor subdivision with newly constructed streets, shall be supplied and installed by the developer. The placement of the signs shall be as shown on the traffic sign plan that is to be submitted with the construction drawings. The traffic sign plan shall show the type of sign, size of sign, location of sign with dimensions and the streets to scale. A five (5) year maintenance bond shall be posted on the signs. The installer or developer shall notify the Town Engineer in writing when the signs are installed, so they can be inspected. Also include the date and time of installation of each sign. The plat shall not be recorded until the signs have been accepted.

TRAFFIC SIGNS

- 1.) Traffic signs shall be designed and installed to conform with the applicable requirements of the Indiana Manual of Uniform Traffic Control Devices, latest edition.
- 2.) No spliced sheeting unless acceptable by the Indiana Department of Transportation standard specifications, latest edition.
- 3.) Reflective sheeting for traffic signs shall be encapsulated lens (high intensity).
- 4.) Posts used for traffic signs shall be 3 lb. galvanized channel posts.
- 5.) Traffic sign height shall comply with the Indiana Manual of Uniform Traffic Control Devices, latest edition.
- 6.) Posts shall be installed with no less than three (3) feet of post in the ground.
- 6.) Backing material will be made of sheet aluminum.
- 7.) Bolts for mounting shall be 5/16" galvanized, stainless steel or plated carriage bolts.
- 8.) The number of posts for mounting and the minimum thickness or gage of sheet shall be as shown for the appropriate sign width:

WIDTH(inches)	NO. OF POSTS	THICKNESS (inches) ALUMINUM SHEET
Up to 24"	1	0.080
25" to 30"	1	0.080
31" to 60"	2	0.100
61" and over	2	0.125


STREET NAME SIGNS

- 1.) Intersections shall have one (1) road name sign for each street.
- 2.) All road name signs shall be made of an aluminum extruded blade.
- 4.) Reflective sheeting for road name signs shall be inclosed lens (high intensity), green in color.
- 5.) Letters and numerals for the road name signs shall be high intensity reflective sheeting, series B letters, and white in color.
- 3.) Posts used for road name signs shall be 2 lb. galvanized channel posts.
- 6.) Minimum height to bottom of sign for road name signs shall be seven (7) feet.
- 7.) Posts shall be installed with no less than three (3) feet of post in the ground.
- 8.) Material for posts shall be galvanized steel.
- 7.) Bolts for mounting shall be 5/16" galvanized, stainless steel or plated carriage bolts.




ROAD NAME SIGN DETAIL  
SCALE: NONE


1. THE EXISTING PAVEMENT IS TO BE SAW CUT TO PROVIDE A CLEAN JOINT.
2. TRENCH SPOIL IS TO BE REMOVED FROM THE WORK SITE AND DISPOSED OF OUT OF THE RIGHT-OF-WAY AT A PREDESIGNATED APPROVED AREA.
3. FLOWABLE FILL IS TO BE POURED INTO THE TRENCH TO SERVE AS BACKFILL, TO THE DIMENSIONS AND SPECIFICATIONS LISTED IN THIS DETAIL.
4. THE ASPHALT PATCH IS TO CONSIST OF A MINIMUM OF 5 (FIVE) INCHES OF #8 HAC BITUMINOUS BINDER AND 1 (ONE) INCH OF #11 HAC BITUMINOUS SURFACE. IF THE EXISTING PAVEMENT IS THICKER THAN 6 (SIX) INCHES, ADDITIONAL BINDER IS TO BE USED TO MATCH THE EXISTING PAVEMENT THICKNESS. IN NO CASE IS LESS THAT 6 (SIX) INCHES OF ASPHALT TO BE USED.
5. THE EXISTING PAVEMENT IS TO BE TACK COATED PRIOR TO THE LAYING OF NEW ASPHALT. TACK COAT IS TO BE APPLIED AS SPECIFIED IN THE LATEST INDOT SPECIFICATIONS, SECTIONS 409 AND 902.
6. THE NEW SURFACE IS TO BE SLOPED AT THE SAME RATE AS THE EXISTING SURFACE.
7. A 2 (TWO) INCH WIDE BAND OF CRACK SEALANT IS TO BE APPLIED ALONG THE JOINT BETWEEN THE EXISTING AND NEW ASPHALT SURFACE. SEALANT IS TO BE APPLIED IN ACCORDANCE WITH INDOT SPECIFICATIONS, SECTION 305.
8. THE FLOWABLE FILL MIX IS TO CONTAIN, FOR EVERY CUBIC YARD OF BATCH MATERIAL, NO MORE THAN 50 LBS OF PORTLAND CEMENT, NO MORE THAN 500 LBS OF WATER.
9. THE COMPRESSIVE STRENGTH OF THE FLOWABLE FILL IS NOT TO EXCEED 100 PSI AT 28 DAYS.



ROAD CUT PATCH DETAIL  
NOT TO SCALE




TYPICAL PAVEMENT TIE-IN  
SCALE: NONE




(TYPE I)

2' CONCRETE ROLL  
CURB & GUTTER  
SCALE: NONE



(TYPE II)

2' COMBINED CONCRETE  
CURB AND GUTTER  
SCALE: NONE



CONCRETE CURB (BARRIER)  
SCALE: NONE

REVISIONS		
REV. NO.	DESCRIPTION	DATE



RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
	DESIGN ENGINEER	DATE
APPROVED	<i>Ronald D. C. ...</i>	7/12/05
	PUBLIC WORKS COMMISSIONER	DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
	TOWN COUNCIL PRESIDENT	DATE


TOWN OF McCORDSVILLE

TOWN STANDARDS  
RIGHT-OF-WAY DETAILS

SHEET  
3  
OF  
10




Plot Date: Apr 24, 2024 Plot Time: 2:02pm File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F McCordsville Standard Details.dwg, Layout: Detail 4 of 10 By: leitchorn



TYPICAL LOT UTILITY LOCATION  
NOT TO SCALE

**GENERAL NOTES:**  
1.) The location of proposed utilities as indicated hereon are based upon the orderly development of the land. Strict adherence to the indicated location is required. Requests to change the location of the proposed utilities shall be submitted in writing to the Public Works Commissioner. Utilities not meeting these requirements shall be removed and replaced as directed by the Public Works Commissioner at the owner's expense.



TYPICAL LOCAL ROAD UTILITY LOCATION  
NOT TO SCALE


REVISIONS			<div>MARK J. WITSMAN REGISTERED No. 10100264 STATE OF INDIANA PROFESSIONAL ENGINEER</div>	RECOMMEND FOR APPROVAL		<div>TOWN OF McCORDSVILLE</div> <div>TOWN STANDARDS UTILITY LOCATION GUIDELINES</div>	SHEET 4 OF 10
REV. NO.	DESCRIPTION	DATE		APPROVED	DATE		
				DESIGN ENGINEER	7/12/05		
				PUBLIC WORKS COMMISSIONER	7/12/05		
				TOWN COUNCIL PRESIDENT	7/12/05		




Plot Date: Apr 24, 2024  
Plot Time: 2:02pm  
File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F McCordsville Standard Details.dwg, Layout: Detail 5 of 10  
By: leichhorn

## RESIDENTIAL DRIVES

- 1.) THE MAXIMUM ALGEBRAIC DIFFERENCE IN GRADE FOR ANY 10 FOOT INTERVAL SHALL NOT EXCEED 8% FOR CREST VERTICAL CURVES. NOR 10% FOR SAG VERTICAL CURVES.
- 2.) ALL LOTS SHALL DRAIN TO ADJACENT STREETS EXCEPT WITH THE PRIOR APPROVAL OF THE PUBLIC WORKS COMMISSIONER.
- 3.) CONCRETE DRIVES REQUIRE CONTROL JOINTS EVERY 10 FEET EACH WAY.




SECTION "A-A"




1. CROSS HATCHED AREAS SHALL BE EITHER 6" PLAIN CONCRETE OR 1" SURFACE ON 2" BITUMINOUS BASE ON 4" #53 COMPACTED AGGREGATE BASE, EXTENDING TO THE SIDEWALK OR R/W LINE WHICHEVER IS NEAREST TO THE ROADWAY.
2. SUBGRADE UNDER ALL SIDEWALKS AND DRIVES SHALL BE IN ACCORDANCE WITH SECTION 207.02 OF CURRENT INDOT STANDARD SPECIFICATIONS.
3. SIDEWALKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPROPRIATE STANDARD AND SHALL BE CONTINUOUS ACROSS THE DRIVEWAY. SIDEWALK SECTION ACROSS DRIVEWAY SHALL BE SAME THICKNESS AS DRIVEWAY WITH A 6-INCH MINIMUM.

## RESIDENTIAL DRIVEWAY DETAIL


SCALE: NONE



SECTION "A-A"



SECTION "C-C"



## HANDICAP RAMP CONSTRUCTION

SCALE: NONE

## HANDICAP RAMP CONSTRUCTION

- 1.) All handicap ramps shall meet the requirements of the American Disabilities Act, the most recent INDOT standard specifications, and the Town of McCordsville's most recent standards. Curb modifications required for handicap ramps shall be provided at time of initial construction.
- 2.) Minimum width of curb ramp shall be 5 feet not including flares. Maximum slope of ramps and flares shall be 12:1.
- 3.) Handicap ramps are to be located as shown on the plans or as directed by the Public Works Commissioner.
- 4.) Ramps shall be provided at the centerline of radius at all corners of every street intersection where there is an existing or proposed sidewalk and curb. Ramps shall also be provided at walk locations at mid-block in vicinity of hospitals, medical centers, or athletic stadiums. The use of details contrary to those shown hereon shall require the prior written approval of the Public Works Commissioner.
- 5.) Surface texture of the ramp shall be ramp grooves located 2" on center and 0.3" deep.
- 6.) Care shall be taken to assure a uniform grade on all ramps with no breaks in grade.
- 7.) Drainage structures shall not be placed in line with the ramps except where existing drainage structures are being utilized in the new construction. Location of the ramps shall take precedence over location of drainage structures.
- 8.) The normal gutter line profile shall not be maintained through the area of the ramp. Drainage inlets should be located uphill from the curb ramps to prevent puddles at the path of travel.
- 9.) Expansion joint for the ramp shall be a maximum 1/2" wide. The top of the joint filler for all ramp types shall be flush with adjacent concrete.
- 10.) Crosswalk and stop line marking, if used, shall be so located as to stop traffic short of ramp crossing.

## SIDEWALK CONSTRUCTION

- 1.) Sidewalks shall be constructed of plain concrete four (4) inches thick except where crossing driveways where the sidewalk shall be a minimum of six (6) inches thick.
- 2.) Sidewalks shall be constructed on 2" of crushed stone or sand.
- 3.) Control joints shall be placed every 5 feet on center.
- 4.) Expansion joints shall be placed every 40 feet on center.
- 5.) Broom finish across the direction of travel and include a 1" steel trowel finish along both sides of the sidewalk and along either side of all expansion and control joints.

REVISIONS		
REV. NO.	DESCRIPTION	DATE



RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. C. ...</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE


TOWN OF McCORDSVILLE

TOWN STANDARDS  
DRIVE WAY AND  
HANDICAP RAMP DETAILS

SHEET  
5  
OF  
10



File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F McCordsville Standard Details.dwg, Layout: Detail 6 of 10  
Plot Date: Apr 24, 2024  
Plot Time: 2:02pm  
By: leichhorn





- NOTES:
- 1.) MANHOLE CONFORMS TO A.S.T.M. C-478.
  - 2.) TONGUE AND GROOVE JOINT WITH MASTIC, BUTYL ROPE OR GASKETED PER ASTM C-443 AS REQUIRED.

MANHOLE TYPE	MANHOLE DIAMETER "F"	MAXIMUM PIPE SIZE	
		PIPE ENTERING / PIPE EXITING AT 0°-45° BEND	PIPE ENTERING / PIPE EXITING AT 45°-90° BEND
J	60"	36"	33"
K	72"	48"	36"
L	96"	54"	48"
M	102"	72"	66"
N	108"	84"	72"

#### STORM MANHOLES TYPE "J - K - L - M & N"


NOT TO SCALE



#### CATCH BASIN

NOT TO SCALE

- NOTE:
- 1.) STRUCTURE SHALL COMPLY WITH INDOT SPECIFICATIONS
  - 2.) MINIMUM CONCRETE COMPRESSIVE STRENGTH 4000 PSI
  - 3.) MAXIMUM OF FOUR 2" ADJUSTING SECTIONS, STRIKE CLEAN INSIDE




- NOTE:
- 1.) MANHOLE CONFORMS TO A.S.T.M. C-478.


MAXIMUM PIPE SIZE	
PIPE ENTERING / PIPE EXITING AT 0°-45° BEND	PIPE ENTERING / PIPE EXITING AT 45°-90° BEND
24"	21"

#### STORM MANHOLES TYPE "C"

NOT TO SCALE



NOTE: ALL CASTINGS SHALL BE STAMPED "DUMP NO WASTE"



#### BEEHIVE GRATE CASTING WITH FRAME - NEENAH R-2560-E2


NOT TO SCALE

#### MANHOLE NOTES:

- 1.) Type "J, K, L, M & N" manholes as detailed hereon require a certain minimum depth. In cases where the depth of the storm sewer is not sufficient to meet the minimum depth as by the detail, "F" diameter manhole section may be used required by the detail, "F" diameter manhole section may be used throughout the depth of the manhole.
- 2.) Manholes shall conform to ASTM C-478. Joints shall conform to ASTM C-443. The use of cast-in-place concrete structures shall require the prior written approval of the Town Engineer. Regardless of the type of casting used, the casting shall be centered over the manhole steps.
- 3.) Manhole steps shall be made from a steel reinforcing rod encapsulated in a copolymer polypropylene resin. The manhole steps shall equal or exceed OSHA requirements manhole steps, PS1-PF as manufactured by M.A. Industries, Inc. Peachtree City, Georgia, or approved equal.

#### CASTING NOTES:

- 1.) Castings which drain combined curb and gutter, Type II curbing shall be Neenah R-3286-8V or Neenah R-3287-10V or as approved by the Town Engineer. Manholes shall not be used to drain combined curb and gutter, Type II curbing.
- 2.) Castings which drain roll curb and gutter, Type I curbing shall be Neenah R-3501-TR, or Neenah R-3501-TL or as approved by the Town Engineer. Manholes shall not be used to drain roll curb and gutter, Type I curbing.
- 3.) Castings for inlets which drain open pavement areas without curbing shall be Neenah R-3402-E or as approved by the Town Engineer.
- 4.) Castings for manholes which drain open pavement areas without curbing shall be Neenah R-2501 or as approved by the Town Engineer.
- 5.) Castings for use on inlets or manholes which drain swales or dry bottom detention basins shall be Neenah R-2560 or as approved by the Town Engineer.
- 6.) Castings for manholes which do not collect surface water shall be Neenah R-1772-A or as approved by the Town Engineer.
- 7.) All castings shall be stamped "DUMP NO WASTE".



#### R-3501-T(L&R) NEENAH CURB INLET FRAME, GRATE & CURB BOX DETAIL


NOT TO SCALE

CATALOG NO.	D	Wt. Lbs.
R-1772	25"	250
R-1772-A	25"	285

HEAVY DUTY

FURNISHED WITH PLATEN LID, SIMILAR TO R-1706-1

NOTE: ALL CASTINGS SHALL BE STAMPED "DUMP NO WASTE"



#### STORM MANHOLE R-1772-A WITH CONCEALED PICK HOLES

NOT TO SCALE

REVISIONS		
REV. NO.	DESCRIPTION	DATE



RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. C. ...</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE

#### TOWN OF McCORDSVILLE

#### TOWN STANDARDS STORM SEWER STRUCTURE DETAILS

SHEET  
6  
OF  
10



**SHEET  
7  
OF  
10**



GENERAL NOTES

- 1.) Sanitary sewer pipe of other material not meeting Town of McCordsville Standards shall require the prior written approval of the Town Engineer.
- 2.) The Contractor shall submit information to the Town Engineer showing conformance with these specifications upon request.
- 3.) Forty-eight (48) hours notice shall be given to the Town Engineer prior to the start of sewer construction and prior to any testing.
- 4.) The contractor shall be responsible for verifying that all state highways, city, and county permits have been obtained by the developer prior to start of construction.
- 5.) Backfill around all structures and all cuts under paved areas with B-barrow as defined by current INDOT specifications. Trenches opening within 5-feet of paved roadways shall be backfilled with B-barrow as defined by current INDOT specifications. Backfill under sidewalks shall be B-barrow; unless the walks are constructed a minimum of 6 months after backfill has been in place. The Town of McCordsville may require an analysis of the B-barrow to confirm its compliance with INDOT specifications at the contractor's expense.
- 6.) Water and sewer line crossings and separations shall be in accordance with 327 IAC 3-6-9.
- 7.) Trench shall be opened sufficiently ahead of pipe laying to reveal obstruction, and shall be properly protected and/or barricaded when left unattended.
- 8.) No water shall be permitted to flow into the sanitary sewer system during construction. The contractor shall utilize a pump to keep the water level below the pipe. Pump discharge shall be directed to a storm outlet in accordance with local, state and federal laws and regulations. Any pipe entering existing sewers shall be plugged with screw type mechanical, braced plug and tied in place until such time as all tests on the sewers have been completed and the lines have passed all punch lists.
- 9.) The contractor shall use a laser and target wherever possible to insure proper construction at the planned grade.
- 10.) The contractor shall provide measurements of the slope of the sewer for each manhole section as construction progresses. Such measurements shall be certified by a registered land surveyor or engineer and be available on-site for observation by the Town Engineer. No more than three manhole sections can be constructed in advance of such measurements.
- 11.) The contractor shall be required to furnish the developer's engineer with a set of prints, marked in red pencil, showing actual sewer location and invert, to include lateral location, depth and length. Such asbuilt prints must be received by the developer's engineer before the final contract payment can be authorized. The sanitary sewer laterals and stubs termination shall be indicated on the surface with a 2"x4" wood board or other appropriate marker set immediately above the said termination point.
- 12.) Record drawings shall be provided to the Town Engineer for review and approval. Once approved, two copies and electronic images of the approved record drawings will be provided. The electronic images will be in an acceptable format approved by the Town Engineer. A site plan in state plane coordinates compatible with the Hancock County GIS system will also be provided with the electronic files showing the property lines, easements, streets and right-of-ways and as-built locations of the sanitary sewer, storm sewer and water lines.

SANITARY SEWER PIPE

- 1.) Sanitary sewer pipe between 6 and 15 inches in diameter shall be SDR 35 PVC in accordance with ASTM D3034 and ASTM 2321. Sanitary sewer pipe buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic in accordance with ASTM D1784.
- 2.) Sanitary sewer pipe greater than 15 inches in diameter shall be either:
- a. PVC SDR 35 in accordance with ASTM D3034 and ASTM 2321. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic as defined in ASTM D1784. Sanitary sewer pipe buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034.
- b. Profile sewer in accordance with ASTM F949. The pipe and fittings shall have a minimum cell classification of 12454 in accordance with ASTM D1784. The joints shall be push-on bell and spigot type using elastomeric ring gaskets conforming to ASTM D3212 and ASTM F477. The pipe shall have a minimum stiffness of 46 PSI when measured in accordance with ASTM D2412. Profile sewer pipe is not permitted at depths 15 feet or greater.
- 3.) PVC sewer fittings shall be SDR 26 in accordance with ASTM D3034. Fittings in sizes through 8-inches shall be molded in one piece with elastomeric joints and minimum socket depths as specified in sections 6.2 and 7.3.2. Fittings 10-inches and larger shall be molded or fabricated in accordance with section 7.11 with manufacturers standard pipe bells and gaskets. Gaskets for elastomeric joints shall be molded with a minimum cross-sectional area of 0.20 square inches and conform to ASTM F-477 specification.
- 4.) The minimum slope for sewer acceptance by the Town of McCordsville are:
- | Size of pipe | Minimum constructed slope |
|--------------|---------------------------|
| 8-inch       | 0.40%                     |
| 10-inch      | 0.28%                     |
| 12-inch      | 0.22%                     |
| 15-inch      | 0.15%                     |
| 18-inch      | 0.12%                     |
| 21-inch      | 0.10%                     |
| 24-inch      | 0.08%                     |
- In the event the contractor does not meet the minimum slopes, the sewer section and any other affected sewer sections shall be reconstructed to meet such minimum slopes.

SANITARY SEWER LATERALS OUTSIDE OF THE RIGHT OF WAY/EASEMENT

- 1.) Only approved contractors may install sewer laterals. Contractors must provide proof of liability insurance and a reference list for consideration to be added to the approved list.
- 2.) If working within an existing right-of-way, the contractor must obtain a right-of-way permit from the appropriate local jurisdiction.
- 3.) Contractors are responsible for obtaining all appropriate permits prior to construction. No deviations from the approved plot plan are permitted unless instructed by the Office of Public Works. Immediately notify the office of Public Works of any conflicts or discrepancies noted on the approved plot plan. It is the sole responsibility of the owner to ensure all contractors and subcontractors comply with the approved plot plan. A copy of the approved plot plan is to be provided to the Inspector at the time of inspection.
- 4.) The portion of the lateral installed from the right-of-way/easement to the building shall be inspected by the Office of Public Works prior to being backfilled.
- 5.) Lateral inspections shall be scheduled forty-eight (48) hours in advance with the Office of Public Works.
- 6.) A 6" diameter pipe Type I clean out shall be installed 3' away from building. A threaded plug shall be used to ensure the pipe is 100% watertight. For laterals greater than 100 LF as measured along the pipe, clean outs shall be installed at the right-of-way or property line or at 100 feet increments to provide access every 100 feet.
- 7.) Clean outs are not to be installed in sidewalks, driveways, or any other paved or unpaved traffic areas or pedestrian paths.
- 8.) All clean outs except within 3 feet of the building are to be Type II cleanouts.
- 9.) The connection of the building plumbing to the lateral shall be made with a fernco coupling within three (3) feet of the building before the cleanout except when the building has a basement. If the connection is made at the basement and there is not an adjacent slab or craw space, then a glued joint connection shall be made.
- 10.) The connection point shall not be made under porches or foundations.
- 11.) The fernco coupling shall be sealed watertight using steel band clamps. The piping on either side of the connection point shall be aligned and have no offsets or angles.

SANITARY SEWER LATERALS - GENERAL NOTES

- 1.) Laterals are to be constructed to the right-of-way/easement line and plugged tight with a braced plastic disc or cap capable of withstanding a low pressure air test without leakage. Only after the sanitary sewer has been tested and accepted by the Town Engineer is further installation of the laterals outside the right-of-way/easement permitted.
- 2.) Normal lateral slope is 1/4" per foot. Minimum lateral slope is 1/8" per foot. Any areas found not to comply with the minimum slope shall be removed and reinstalled.
- 3.) Lateral pipe shall be a minimum of 6" diameter and shall be SDR 35 PVC in accordance with ASTM D3034 and ASTM 2321. Laterals with any portion buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034 to the terminus point either the right-of-way or easement line. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic conforming to ASTM D1784. Size and conformance shall be clearly labeled on pipe for inspection.
- 4.) All PVC sewer fittings shall be SDR 26 in accordance with ASTM D3034. Fittings shall be molded in one piece with elastomeric joints and minimum socket depths as specified in sections 6.2 and 7.3.2. Gaskets for elastomeric joints shall be molded with a minimum cross-sectional area of 0.20 square inches and conform to ASTM F-477 specification.
- 5.) All sewer laterals shall be bedded the same as the main line sewer. A minimum D/4 or 6-inches of compacted #8 stone under the pipe, 6-inches on either side of the pipe, and 12" above the pipe are required.
- 6.) Laterals are not to be installed under driveways.
- 7.) Full depth granular backfill is required for the lateral trench in areas within five (5) feet of drive ways, sidewalks or other traffic areas.
- 8.) Laterals are to be traced along the top of the pipe with a minimum size of 14 gauge wire from the wye to the clean out within three (3) feet of the building and extended above grade. The contractor will install the tracer wire utilizing a method does not require any splices in the tracer wire. The tracer wire will be mounted to the top of the pipe in at least three locations along each stick of pipe. Any splices that become necessary during construction will be sealed water tight.
- 9.) Laterals will be separated from water mains and water service lines by ten (10) feet when measured horizontally from the outside edge of the lateral to the outside edge of any existing or proposed water mains or water service lines except when crossing water mains or water service lines which shall be separated by eighteen (18) inches when measured vertically. Crossings must be at a minimum angle of 45 degrees.

SANITARY MANHOLES AND CASTINGS

- 1.) All sanitary manholes shall be precast concrete manholes in accordance with ASTM C-478 and section 720. O-rings shall conform to C-443. Kent seal or approved equal shall also be applied to all joints and between riser rings and castings. Manhole step spacing shall be no more than 16-inches.
- 2.) The casting elevations are set by plan. However, the castings are to be adjusted in the field by the Town's representative should a discrepancy occur between plan grade and existing grade. A new manhole ring and cover shall be installed to establish grade. Maximum height of adjusting rings from the top of the cone to the bottom of the casting shall be 12-inches.
- 3.) Butyl rubber coating shall be applied around each manhole joint from 6-inches above to 6-inches below each joint. The appropriate primer shall be applied prior to applying the double row of kent seal. Each manhole joint will then be wrapped four times with minimum 15 inch wide 80 gage (0.8 mil) polyethylene plastic stretch wrap. Inside joints to be filled with non-shrink grout or precoat plug material.
- 4.) The manhole chimneys, including all riser rings shall be sealed the same as the manhole joints. The butyl rubber and plastic stretch wrap shall extend over the flange of the casting.
- 5.) Manhole castings shall be East Jordan casting 1022-2 or approved equal with a heavy duty self-sealing lid stamped "SANITARY SEWER." Waterproof castings shall be East Jordan casting 1022-2 WT with a heavy duty lid stamped "SANITARY SEWER" or approved equal.

TESTING

- 1.) Manholes shall be air tested for leakage in accordance with ASTM C1244-93, standard test method for concrete sewer manholes by the negative air pressure (vacuum) test.
- a. Installation and operation of vacuum equipment and indicating devices must be in accordance with manufacturer's recommendations and performance specifications which have been provided by the manufacturer and accepted by the engineer.
- b. With the vacuum tester set in place:
1. Using a plate testing device, connect the vacuum pump to the outlet port with the valve open.
2. Draw a vacuum of ten (10) inches of hg. And close the valve.
- c. Accepted standards for leakage will be established from the elapsed time for a negative pressure change from ten (10) inches to nine (9) inches of mercury. The maximum allowable leakage rate for a four (4) foot diameter manhole must be in accordance with the following:
- Minimum elapsed time for a manhole depth pressure change of 1 inch hg
- |                       |            |
|-----------------------|------------|
| 10 feet or less       | 60 seconds |
| >10 feet but <15 feet | 75 seconds |
| >15 feet              | 90 seconds |
- For manholes five (5) feet in diameter, add an additional fifteen (15) seconds and for manholes six (6) feet in diameter, add an additional thirty (30) seconds to the time requirements for four (4) foot diameter manholes.
- d. If manhole joint sealants are pulled out during the vacuum test, the manhole must be disassembled and the joint sealants replaced.
- e. Manholes will be subject to visual inspection with all visual leaks being repaired.
- 2.) All sanitary sewer lines upon completion will be required to pass a low pressure air test. The test shall be conducted according to ASTM 1417-92, and witnessed by a representative of the Town of McCordsville. The testing shall be in accordance with Table 1. Add 0.5 psig for each foot of water above the sewer line being tested.
- 3.) Deflection tests shall be performed on all flexible" pipe after the final backfill has been in place at least 30 days. No pipe shall exceed a vertical deflection of 5% deflection test results. (the following are considered non-flexible pipes: concrete pipe, ductile iron pipe, and cast iron pipe). The deflection test shall be performed with a nine-point mandrel. Proving rings shall be available.
- 4.) All sanitary sewer lines upon completion and six months prior to the expiration of the maintenance bond will be televised. The sanitary sewer lines will also be cleaned if necessary in the judgment of the Town's representative after observing the televising tapes.
- 5.) All testing shall be observed by a representative of the Town of McCordsville.

OIL/GREASE TRAP REQUIREMENTS

- 1.) All new commercial of industrial entities, which either generate and/or waste oil, grease or their by-products, shall construct a 1,000 gallon (minimum) grease trap. The design engineer shall submit detailed calculations for size justification of the trap. Calculations shall be accompanied with references, specifically denoted origin of sizing calculation method.
- 2.) Toilets, urinals and other similar fixtures shall not waste through the grease interceptor. All other waste shall enter through the grease interceptor, through the inlet pipe only.
- 3.) The grease interceptor and grease trap shall be sized such that it is easily accessible at all times for inspection/sampling and cleaning. The grease trap shall have a minimum of two (2) compartments with fittings designed for grease interception.
- 4.) The oil/ grease trap shall be located outside the building and at a distance far enough to allow soluble grease/oil to become insoluble.

SPECIFICATION TIME REQUIRED FOR A 0.5 PSIG PRESSURE DROP  
FOR SIZE AND LENGTH OF PIPE INDICATED FOR Q=0.0015

1 Pipe Diameter (in.)	2 Minimum Time (sec)	3 Length For Minimum Time (ft)	4 Time for Longer Length (sec)	Specification Time for Length (L) Shown (min:sec)							
				100 ft	150 ft	200 ft	250 ft	300 ft	350 ft	400 ft	450 ft
8	3:47	298	0.760 L	3:47	3:47	3:47	3:47	3:48	4:26	5:04	5:42
10	4:43	239	1.187 L	4:43	4:43	4:43	4:56	5:56	6:55	7:54	8:54
12	5:40	199	1.709 L	5:40	5:40	5:42	7:07	8:32	9:58	11:23	12:49
15	7:05	159	2.671 L	7:05	7:05	8:54	11:07	13:21	15:34	17:48	20:02
18	8:30	133	3.846 L	8:30	9:37	12:49	16:02	19:14	22:26	25:38	28:51
21	9:55	114	5.235 L	9:55	13:05	17:27	21:49	26:11	30:32	34:54	39:16
24	11:23	100	6.846 L	11:23	17:07	22:49	28:31	34:14	39:56	45:38	51:21

REVISIONS		
REV. NO.	DESCRIPTION	DATE




RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i> DESIGN ENGINEER	<i>7/12/05</i> DATE
APPROVED	<i>David D. C...</i> PUBLIC WORKS COMMISSIONER	<i>7/12/05</i> DATE
APPROVED	<i>Mark J. Witsman</i> TOWN COUNCIL PRESIDENT	<i>7/12/05</i> DATE


<b>TOWN OF McCORDSVILLE</b>		<b>SHEET 8 OF 10</b>
<b>TOWN STANDARDS SANITARY SEWER SPECIFICATIONS</b>		




File Name: W:\Lennar\2020-235-F Lennar - Summerton Amenity\Design\CAD\20235-F McCordsville Standard Details.dwg, Layout: Detail 9 of 10  
Plot Date: Apr 24, 2024  
Plot Time: 2:02pm  
By: leitchom




PIPE BEDDING DETAILS  
NOT TO SCALE




SANITARY MANHOLE  
NOT TO SCALE




DROP SANITARY MANHOLE  
NOT TO SCALE




CLEAN OUT TYPE II  
SCALE: NONE




CLEAN OUT TYPE I  
SCALE: NONE




PLAN VIEW




PLAN VIEW




TYPICAL RAILROAD AND HIGHWAY BORING DETAIL  
NOT TO SCALE



TYPICAL UTILITY CROSSING  
NOT TO SCALE



ELEVATION



ELEVATION

SERVICE CONNECTION FOR SHALLOW SEWERS  
LESS THAN 15' DEEP

SERVICE CONNECTION FOR DEEP SEWERS (2 ALTERNATIVES)  
15' DEEP AND OVER


REVISIONS		
REV. NO.	DESCRIPTION	DATE




RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. C.</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE

TOWN OF McCORDSVILLE	SHEET 9 OF 10
TOWN STANDARDS SANITARY SEWER DETAILS	





LIFT STATION - PLAN  
SCALE: NONE



ALL SURFACES CONTACTING  
CONCRETE SHALL HAVE A  
BITUMINOUS COATING

MATERIALS SCHEDULE				
INFLUENT SEWER I.D.	"A"	"B"	"C"	"D"
8"-10"Ø	19"	5"	13"	10"
10"-14"Ø	23"	5"	18"	10"
14"-18"Ø	27"	5"	23"	10"
18"-22"Ø	31"	5"	28"	10"
22"-26"Ø	35"	5"	37"	10"

DEFLECTION PLATE DETAILS  
SCALE: NONE

GENERAL NOTES

- Actual lift station dimensions, control settings, & pump selection to be indicated by the design engineer's certification sheet.
- Pumps "A" and "B" shall be identical, centrifugal, submersible, solids handling, non-clog design capable of handling 3" sphere solids, fibrous material, sludge, and material found in typical raw sewage. Fit replaceable bronze wear ring to volute. Pumps shall be Flygt, Hydromatic or approved equal. Manufacturer shall warrant the pumps for five years after installation.

All mating surfaces intended to be watertight shall be machined and fitted with nitrile rubber o-rings with sealing complete when metal-to-metal contact is made, resulting in controlled compression of o-rings without specific torque limit. Fasteners shall be 316 S.S.

Mechanical shaft seal system running in an oil reservoir shall have separate, constantly lubricated lapped seal faces. The lower seal unit between media and oil reservoir shall consist of one stationary seat and one rotating ring held in place by its own spring. The rotating seat ring and the stationary seat ring shall be made of Tungsten-Carbide. The lower seal shall be removable without disassembling the seal chamber. The upper seal between seal chamber and motor shall be of the same design with its own spring. Seals shall be maintenance free, but shall be easily inspectable.

The lift station control panel shall be stainless steel construction, NEMA 4X rating mounted on an aluminum pedestal. The control cabinet shall house the following controls and indication: Warning lights for each pump, Indicator lights, Common alarm, H-O-A switches, Silence button, Pump alternator, Warning reset buttons, Relays, Heater, Surge protection, Phase monitoring, Hour meters, and a GFI 110 volt, single phase convenience outlet. Lower seal failure alarm shall be engaged by seal failure sensor provided in the seal chamber, which senses water intrusion through lower seal. A mini-float in the motor chamber which signals pump shutdown and alarm upon water intrusion through upper seal may be acceptable when approved by Town of McCordsville.

Over temperature alarm and pump shutdown shall be engaged by heat sensor attached to the motor windings. Motor winding and stator lead insulation shall be class F with maximum temperature capability of 155 degree C. Housing shall be filled with High-Dielectric Oil. Air filled housing may be acceptable when approved by Town of McCordsville. Pump and motor shall be designed to operate partially or fully submerged in pumped media without the use of cooling jackets.

Rail system shall enable the easy removal of the pump without the need for a person to enter the wet well. A non-corrosive FRP I-beam or schedule 40 stainless steel guide rails shall be provided for each pump. The guide rail shall be supported at the bottom by the discharge elbow, aligned perfectly plumb and securely affixed to access frame. One intermediate guide rail support is required for each 9' of guide rail length.

3.) Check valve shall use packing material to seal the integral shaft or hinge pin. O-ring side plugs and O-ring shall not be used to seal integral shaft or hinge pin. Check valve shall be provided with bolted covers for easy access to the discs and shall be outside adjustable weight & Lever and shall be Clow F-5382 or approved by Town of McCordsville.

4.) Provide sufficient lift chain, float mounting cable, and pump power & control cable to enable non-spliced field adjustment. 304L stainless steel lift chain w/ 4:1 safety factor shall have a minimum workload limit of 1100 pounds. Pump power & control cables shall be suitable for submersible pump applications and this shall be indicated by a code/legend permanently embossed on the cable. Provide sleeve and pin on pump control cable and locate on bracket near hatch.

5.) Plug valve shall be hand lever operated and shall be Dezurik Fig. 118, Clow F-5412, or Town of McCordsville approved equal.

6.) Pressure gauge shall be Terrice Model 450 LFB or Town of McCordsville approved equal. Drill & tap run of pipe to install pressure gauge.

7.) Piping not within 2 feet of wet well and valve pit shall be DI Class 53, PVC ASTM D2241 SDR 21, PVC AWWA C900 or C905, or Town of McCordsville approved equal.

8.) Piping in and within 2 feet of wet well and valve pit shall be class 53 flanged ductile iron pipe.

9.) Piping, valves, and fittings in wet well and valve pit shall be factory primed Tnemec series 140 - 1211 to a dry film thickness of 5.0 to 11.0 mils and shall be field painted with Tnemec series 69 to a dry film thickness of 5.0 to 6.0 mils.

10.) Lift station and valve pit manholes shall be pre-cast concrete in accordance with ASTM C-478, with rubber gaskets equal to ASTM-443 with double row of 1/2" Hamilton Kent-Seal Extrudable Preformed Gasket material or Town of McCordsville approved equal. Exterior joints to have butyl rubber applied over the joint to a minimum of 1'-0" above and below the joint. Interior joints are to be sealed with non-shrink grout or precoat plug material.

11.) Valve pit shall be constructed on undisturbed soil or compacted granular material compacted with ½ inch nominal size to 95% standard proctor density.

12.) Horizontal projections from precast integral base and riser may be required to enable the weight of the vertical soil ring above the projection to resist buoyancy forces. See design engineer's certification sheet.

13.) Camlock flanged coupler and dust cap shall be used within valve vault. Camlock coupling and eccentric plug valve on by-pass line shall be 6" diameter with transition to force main size occurring with concentric reducer placed on top of base elbow. Fix operating nut for eccentric plug in vertical position to enable wrench operation from surface. Layout of all valve vault fittings and equipment to be based upon by-pass line being up close to hatch opening as shown.

14.) Aluminum hatches shall be Bilco, Halliday or Town of McCordsville approved equal. Leaf shall be ½" aluminum diamond plate live load rated to 300PSF. Access frames and covers shall be 1/4 inch thick one-piece, mill finish, extruded aluminum frame, incorporating a continuous concrete anchor. All surfaces contacting concrete shall have a bituminous coating. Hatch shall be provided with type 316 S.S. hardware throughout, compression spring operators, automatic hold-open arm with release handle, and non-corrosive locking bar used in conjunction with a Town of McCordsville supplied padlock.

15.) Sewer connection to wet well shall be KOR-N-SEAL, A-LOK, DURA-SEAL, or Town of McCordsville approved equal.

16.) Force main penetrations of wet well shall be KOR-N-SEAL, A-LOK, DURA-SEAL, or Town of McCordsville approved equal.

17.) Automatic pump control system shall include all necessary items and appurtenances, which might normally be considered a part of a complete system. System shall be supplied by one manufacturer, shall be factory assembled, wired and tested, and shall be per complete electrical drawings and instructions. Major components and sub-assemblies shall be identified as function with laminated, engraved, bakelite nameplates. System shall be built in a NEMA 4X S.S. enclosure suitable for the specified horsepower and voltage of the pumps. The outer door of the panel shall be a hinged dead front with provisions for padlocking. Inside shall be a separate hinged panel to protect all electrical components, H-O-A switches, run lights, circuit breakers, etc., mounted such that only the faces protrude through said panel with no wiring fixed to said panel. The manufacturer shall warrant the control center for one year after installation covering 100% parts and labor.

Provide the services of a factory-trained, qualified representative to inspect, to adjust, and to place the system in trouble-free operation and to instruct the operating personnel in the proper operation and care of the system.

All major components of control center shall be available from local sources. Pump manufacturer shall accept the control center in writing to ensure unit responsibility and warranty.

Provide a disconnect switch housed in a separate NEMA 4X S.S. enclosure with external operation handle capable of being locked in the "on" position. Provide 480 volt, 200 amp, 4 wire weatherproof receptacle, Crouse Hinds AR204 or equal, to match plug on existing portable generator.

Provide a Omni-site.net Crystall WM housed within the NEMA 4X control panel.


An incoming power terminal block shall be located at the bottom of the control enclosure. A lightning arrestor shall be provided at the terminal block and connected to each line of the incoming side of the power input terminals. A single main fusible/breaker disconnect switch of adequate size to provide power for control, operation, and appurtenant components shall be provided. Provide a circuit breaker and magnetic starter with each leg manual reset overload protected for each pump. Starters shall have auxiliary contacts on 3Ø applications to operate both pumps simultaneously. Provide a circuit breaker and transformer to power the control panel with 1Ø, 115 volt service for all control functions. Provide a green "run" light and H-O-A switch to enable field connections.

Materials and installation of the required equipment grounding shall be in accordance with NEC section 250-83(c). All wiring shall have not less than 600 volt insulation. Wiring and buss shall be in accordance with NEC, state, local, and NEMA standards. All wiring shall be color coded.

Minimum 4" diameter, schedule 40 conduit shall be provided from wet well to control panel enabling pump power & sensor cables and float switch cables to be easily pulled. Seal conduit at control panel to prevent sewer gases from entering. All conduits, fittings, or connections shall enter from the bottom of enclosures.

Sump level rise to lead pump run float causes lead pump to operate. Lead pump operating and sump level falling to pumps off float causes lead pump to shut off. Lead pump operating and sump level rising to lag pump run float causes lag pump to operate. Lag pump operating and sump level falling to pumps off float causes both pumps to shut off. Sump level rise to high level alarm causes high level alarm to operate. An alternating relay shall be provided to cause pumps to alternate whenever pumps off float is de-energized. If one pump fails for any reason, the remaining pump shall operate upon sump level rise to lag pump run float. An hour meter shall be provided for each pump to record the elapsed operating time of each pump.

18.) Four manuals shall be presented to the owner, which shall include the following minimum information: 1) Operation instructions, 2) Maintenance instructions, 3) Recommended spare parts list, 4) Lubrication schedule, 5) Structural diagrams, 6) As-built wiring diagrams, & 7) Bill of materials.



LIFT STATION SECTION  
SCALE: NONE

REVISIONS		
REV. NO.	DESCRIPTION	DATE



RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05 DATE
APPROVED	<i>Ronald D. C...</i>	7/12/05 DATE
APPROVED	<i>...</i>	7/12/05 DATE

<b>TOWN OF McCORDSVILLE</b>	<b>SHEET</b>
<b>TOWN STANDARDS SANITARY SEWER LIFT STATION STANDARDS &amp; GUIDELINES</b>	<b>10 OF 10</b>