

ESTIMATE	#11290
ESTIMATE DATE	Oct 10, 2025
TOTAL	\$21,975.00

Silvers Concrete & Paving

Nick Brown 7520 Civic Dr McCordsville, IN 46055

(317) 414-0526

rcrider@mccordsville.in.gov

CONTACT US

1311 W. 96th Street Indianapolis, IN 46260

(317) 835-8991

office@silverscap.com

ESTIMATE

Services amount

Full Depth Asphalt Replacement and New Asphalt Radii

\$21,975.00

- 1. Demo and haul away asphalt up to 7". Demo earth and haul away. THIS DOES NOT INCLUDE ANY CONCRETE DEMO.
- 2. Add additional aggregate as needed and 6" of stone brought in for the radii.
- 3. Pave with 5 inches of 19mm binder course and 2 inches of 9mm surface course for a total of 7".
- 4. Power roll for proper compaction.
- 5. 1-3 day project.

https://www.silversconcreteandpaving.com/

Services subtotal: \$21,975.00

Total \$21,975.00

PLEASE SEND ALL CHECKS TO 1311 W. 96TH ST. INDIANAPOLIS, IN 46260 THANK YOU!!