



www.americanpumprepair.com
Phone (317)861-6791
Fax (317)861-6846

Walsh Construction
Ref: Town of McCordsville WWTP
Expansion, Phase 5, **Change Order**
Attn: Zac Partlow

1/12/21

American Pump Repair & Service, Inc. is pleased to offer the following equipment for the above project:

Appendix G, Digester Pump Package
Custom-built Sludge Shack control panel

Total Adder (including freight): \$10,360.00

Thanks,

James B. Parks III

American Pump Repair & Service, Inc.

Scope of Supply Contained Below



Quality Controls Inc.

Industrial Control Panels

EQUIPMENT PROPOSAL

DATE: January 12, 2021

PROJECT: Town of McCordsville Sludge Shack

TO: American Pump Repair & Service, Inc. **QUOTATION:** Q191269A Rev.2

Attn: Jordan Harrell

We are pleased to propose the following quotation based on our interpretation of the furnished specifications. Any additional equipment not listed will be subject to pricing review.

Enclosure Type:	NEMA 4X (304) S.S. Enclosure
Enclosure Mounting:	Wall mounted
Power Requirements:	120 Volt 1 Phase
Horsepower:	
Station Type:	Quadraplex Stations

Equipment

- _____ Power distribution block
- _____ 120 Volt control circuit breaker
- _____ 120 Volt Running (LED) Indicator lights, Door mounted
- _____ Primary Level Control
 - Transducer and Floats (Furnished by others)
- _____ Secondary Level Control (Maintaining Operation)
 - Flow meter (Furnished by others)
 - Flow totalizer w/ totalizer resettable feature
- _____ Horner 5in Touch Screen Controller
 - Ethernet connectivity available
 - Programming
 - 24vdc Power Supply
 - Ethernet Switch
- _____ Telemetry Contacts as required
- _____ Terminals and ground bar for field connections
- _____ UL 508A Listed for industrial control panels

Plus any Federal, State, Local, or Applicable Taxes to be the responsibility of the buyer. One (1) copy of submittal information is included in the above price. Additional copies can be supplied at \$5.00 a copy. Estimated delivery is **3 to 4** weeks after receipt of Complete Engineering Approved Drawings and/or acceptable order in our office located in Cincinnati, Ohio. Price valid for 60 days from the date of this proposal/agreement. Projects extended past this time period are subject to adjustments based on prevailing material costs. Established customers payment terms are NET 30 Days from date of shipment.

Submitted by: Jerry Yates _____



Huston Electric
1105 E. 181st Street
Westfield, IN 46074
Telephone: 317-804-9009
Contact: Todd Hutchins
E-mail: toddh@hustonelectric.com

CHANGE NOTICE

Client Address:

Walsh Construction

Contact: Zac Partlow
6081 E. 82nd Street
Indianapolis, IN 46250

Site Address:

8260 N. 600 West
McCordsville, IN 46055

CCN #

6

Date:

1/12/2021

Project Name:

McCordsville WWTP Phase 5

Project Number:

IC1282

Contract #:

220075S0002

Page Number:

1

Work Description

We reserve the right to correct this quote for errors and omissions.

This quote covers direct costs only and we reserve the right to claim for impact and consequential costs.

Unless otherwise stated below, this quote assumes the following:

- Full accessibility to work areas.
- Labor completed during regular work hours. No overtime or additional manpower included.
- There may be lead time for some material. We are not responsible for delays due to availability.
- Excavations by others.

This price is good for acceptance within **10** days from the date of receipt.

This change will require an additional **2** days duration in project schedule.

We will supply and install all materials, labor, and equipment for:

Provide 120v power connection to control panel in Sludge Shack.

Provide 2" raceway from Sludge Shack to Processing Building.

Provide ethernet cable connection from Sludge Shack to Digester Panels and from Processing to Digester Panels.

Summary

MATERIAL

General Materials

688.73

Total Material

688.73

LABOR

(76.02 Hrs @ \$73.00)

5,549.46

PLANNING & LOGISTICS

(7.60 Hrs @ \$84.00)

638.40

Total Labor

6,187.86

SMALL TOOLS & CONSUMABLES

331.05

SAFETY

198.63

Subtotal

7,406.27

Markup

(@ 10.000 %)

740.63

Subtotal

8,146.90

Final Adjustment

0.10

Final Amount

\$8,147.00

CLIENT ACCEPTANCE

ORIGINAL

CHANGE NOTICE

CCN # 6
Date: 1/12/2021
Project Name: McCordsville WWTP Phase 5
Project Number: IC1282
Contract #: 220075S0002
Page Number: 2

CCN # 6
Final Amount: \$8,147.00

Name: _____

Date: _____

Signature: _____

Change Order #: _____

I hereby accept this quotation and authorize the contractor to complete the above described work.

ORIGINAL