

CONSTRUCTION PLANS FOR:


GREEN TOUCH

MCCORDSVILLE

6312 RAILROAD ST


TOWN OF MCCORDSVILLE, HANCOCK COUNTY, INDIANA

NE 1/4, SECTION 26, TOWNSHIP 17N, RANGE 5E



COUNTY LOCATION MAP

NOT TO SCALE



SITE VICINITY & ZONING MAP

NOT TO SCALE

PLANS PREPARED FOR:

MACDOUGALL PIERCE CONSTRUCTION

12720 FORD DRIVE

FISHERS, IN 46038

Contact Person: ROB WOODCOCK

317-596-6371

RWOODCOCK@MACDOUGALLPIERCE.COM

OPERATING AUTHORITIES:

Town of Mccordsville Engineering

6280 W 800 N
McCordsville, IN 46055
(317) 335-3604

Town of Mccordsville Planning

6280 W 800 N
McCordsville, IN 46055
(317) 335-3604

Town of Mccordsville Stormwater

6280 W 800 N
McCordsville, IN 46055
(317) 335-3493

Town of Mccordsville Streets

6280 W 800 N
McCordsville, IN 46055
(317) 335-3493

Town of Mccordsville Water and Wastewater

6280 W 800 N
McCordsville, IN 46055
(317) 335-1044

Hancock County Surveyor

111 American Legion Place,
Suite 171
Hancock County Annex
Greenfield, IN 46140
317-477-1150

Hancock County Soil and Water Conservation District

1101 W Main St N. Greenfield,
IN 46140
317-462-2283

Vectren Energy - Gas

16000 Allisonville Road
Noblesville, IN 46061
317-776-5560

Ninestar Connect - Electric and Fiber Optic

2243 E Main St.
Greenfield, IN 46140
317-326-3131

GENERAL NOTES:

- THE CONSTRUCTION PLANS SHALL GOVERN OVER ANY OTHER FORM OF MEDIA, WHICH INCLUDES DIGITAL FILES OF THIS PROJECT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING OR VERIFYING THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE RESPECTIVE CITY, COUNTY, STATE & FEDERAL AGENCIES PRIOR TO STARTING CONSTRUCTION.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO DETERMINATE THE EXACT LOCATION OF ALL EXISTING UTILITIES IN THE VICINITY OF THE CONSTRUCTION AREA PRIOR TO STARTING CONSTRUCTION. ONCE ALL UTILITIES HAVE BEEN LOCATED, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN IN SERVICE ALL EXISTING UTILITIES ENCOUNTERED DURING CONSTRUCTION UNLESS OTHERWISE INDICATED IN THE CONSTRUCTION DRAWINGS.
- BEFORE WORKING WITH OR AROUND EXISTING UTILITIES, THE APPLICABLE UTILITY COMPANY SHALL BE CONTACTED BY THE CONTRACTOR. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY AND COORDINATE CONSTRUCTION WITH ALL RESPECTIVE UTILITIES.
- ALL CONSTRUCTION METHODS AND MATERIALS MUST CONFORM TO CURRENT STANDARDS AND SPECIFICATIONS FOR THE GOVERNING MUNICIPALITY REQUIREMENTS.
- MAINTENANCE OF TRAFFIC NEEDED FOR THIS PROJECT SHALL BE INSTALLED AND MAINTAINED PER INDOT SPECIFICATIONS / STANDARD DRAWINGS, INDOT DESIGN MANUAL, AND THE INDIANA MUTCD MANUAL, ALONG WITH GOVERNING MUNICIPALITY REQUIREMENTS. COORDINATE WITH THE ENGINEER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL FIELD DIMENSIONS AND SHALL VERIFY ALL DIMENSIONS ON THE SITE PRIOR TO START OF CONSTRUCTION. IF ANY DISCREPANCIES ARE FOUND IN THESE PLANS FROM ACTUAL FIELD CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY.
- IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER AND CONTRACTOR TO MAINTAIN QUALITY CONTROL THROUGHOUT THIS PROJECT.
- ALL GRADES AT THE BOUNDARY SHALL MEET EXISTING GRADES.
- NO WORK SHALL BE CONSTRUCTED OFFSITE UNLESS SHOWN OR DENOTED OTHERWISE WITHIN THESE PLANS.
- NO CONSTRUCTION WORK SHALL BE PERFORMED WITHIN THE ADJACENT OR ONSITE WATER TRIBUTARIES / WATERCOURSES UNLESS SHOWN AND DENOTED AS SUCH OTHERWISE WITHIN THESE PLANS.
- CONTRACTOR SHALL MINIMIZE DAMAGE TO ANY EXISTING TREES UNLESS NOTED OTHERWISE.
- ALL CONSTRUCTION ACTIVITY ON THIS SITE IS TO BE PERFORMED IN COMPLIANCE WITH ALL APPLICABLE O.S.H.A. STANDARDS FOR WORKERS SAFETY.
- BEARINGS, DIMENSIONS, AND EASEMENTS ARE SHOWN FOR REFERENCE ONLY. SEE RECORD SURVEYS AND PLATS FOR EXACT INFORMATION.

SITE DATA:

TOTAL SITE ACREAGE - 2.4 AC.
TOTAL ACREAGE OF DISTURBANCE - 1.5 AC.
GROSS SQUARE FOOTAGE OF BUILDING - 7,200 S.F.

PROPOSED CONSTRUCTION START - JUNE 1, 2024
PROPOSED CONSTRUCTION END - NOVEMBER 30, 2024
WORK IS SCHEDULED TO BE COMPLETED IN ONE CONTINUOUS CONSTRUCTION PHASE.

SURVEY CONTROL AND VERTICAL DATUM (BENCHMARK) INFORMATION:

- SURVEY CONTROL BY OTHERS: FRITZ ENGINEERING SERVICES, LLC (SEE ATTACHED SURVEYS FOR ADDITIONAL INFORMATION)
- HORIZONTAL DATUM: NAD83
- COORDINATE SYSTEM / BASIS OF BEARING: INDIANA STATE PLANE EAST
- VERTICAL DATUM: NAVD88
- PUBLISHED / CHECK-IN BENCHMARK: SEE SURVEY
- ORTHOMETRIC HEIGHT (ELEVATION) = SEE SURVEY

SPECIFICATIONS:

- ALL WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE MCCORDSVILLE STANDARDS, DETAILS, AND SPECIFICATIONS (STANDARDS), LATEST EDITIONS, UNLESS SPECIFICALLY NOTED OTHERWISE.
- INDIANA STATE DEPARTMENT OF TRANSPORTATION (INDOT) STANDARD DRAWINGS AND SPECIFICATIONS, LATEST EDITIONS, SHALL BE INCORPORATED INTO AND UTILIZED WITH THESE PLANS (SUPPLEMENTAL SPECIFICATIONS AND DETAILS).
- CITIZENS WATER STANDARDS, DETAILS, AND SPECIFICATIONS, LATEST EDITIONS, SHALL BE INCORPORATED INTO AND UTILIZED WITH THESE PLANS AS IT PERTAINS TO WATER LINE CONSTRUCTION.
- CITIZENS AND MT VERNON TWP. FIRE DEPARTMENT STANDARDS, DETAILS AND SPECIFICATIONS SHALL BE UTILIZED FOR ALL FIRE PROTECTION WATER LINES AND APPURTENANCE CONSTRUCTION AS IT RELATES TO THIS PROJECT.
- MCCORDSVILLE SANITARY SEWER STANDARDS, DETAILS, AND SPECIFICATIONS, LATEST EDITIONS, SHALL BE INCORPORATED INTO AND UTILIZED WITH THESE PLANS AS IT PERTAINS TO SANITARY MAINS AND LATERAL CONSTRUCTION.
- THE INDIANA MUTCD MANUAL, LATEST EDITION, SHALL BE INCORPORATED INTO AND UTILIZED WITH THESE PLANS.

MAINTENANCE OF TRAFFIC (MOT) NOTES:

ALL MAINTENANCE OF TRAFFIC SHALL BE DESIGNED TO, FOLLOW, AND BE INSTALLED PER THE INDIANA MUTCD MANUAL, INDIANA DEPARTMENT OF TRANSPORTATION (INDOT) SPECIFICATIONS AND STANDARD DRAWINGS, AND INDOT DESIGN MANUAL.

SIGNS & PAVEMENT MARKING NOTES:

ALL SIGNS AND PAVEMENT MARKINGS AND STRIPING SHALL MEET THE CURRENT EDITION OF THE INDIANA MUTCD MANUAL, TRAFFIC CONTROL FOR BICYCLE FACILITIES, AND INDOT STANDARD DRAWINGS AND SPECIFICATIONS AND SHALL BE INSTALLED PER THE INDIANA MUTCD MANUAL, INDIANA DEPARTMENT OF TRANSPORTATION (INDOT) SPECIFICATIONS AND STANDARD DRAWINGS, AND INDOT DESIGN MANUAL.

SHEET LIST TABLE

SHEET NUMBER	SHEET TITLE
C100	COVER SHEET
C101	GENERAL INFORMATION PLAN
V1	SURVEY
V2	SURVEY
C102	EXISTING CONDITIONS & DEMOLITION PLAN
C103	SURVEY INFO
C201	SITE PLAN
C301	GRADING PLAN
C401	UTILITY & DRAINAGE PLAN
C402	STORM PLAN & PROFILES
C403	STORM PLAN & PROFILES, STORM DATA TABLES
C501	INITIAL EROSION CONTROL SWPPP
C502	MASS GRADING & CONSTRUCTION SWPPP
C503	POST CONSTRUCTION SWPPP
C504	SWPPP SEQUENCING & SOILS INFORMATION
C505	CSGP REPORT & SPILL PREVENTION
C506	EROSION CONTROL DETAILS
C601	CURB RAMP & ADA DIAGRAMS
C602	INDOT CURB RAMP DETAILS
C801	SITE DETAILS
C802	SITE DETAILS
C803	UTILITY DETAILS
C804	DRAINAGE DETAILS
C901	GENERAL SPECIFICATIONS
L101	LANDSCAPE PLAN
1-10	MCCORDSVILLE STANDARD DETAILS

STORMWATER INFRASTRUCTURE SUMMARY TABLE (PRIVATE)

DESCRIPTION	QUANTITY	UNITS
12" HDPE	308	LF
30"x30" BOX INLET	2	EACH
OUTLET CONTROL STRUCTURE	1	EACH
FLARED END SECTION	3	EACH
NEW STORMWATER QUALITY MEASURE	NORTHING COORDINATE	EASTING COORDINATE
DETENTION BASIN	16#####	22#####


QUANTITIES NOTE:

ANY AND ALL QUANTITY TABLES, NOTES OR VALUES AS SHOWN ON THESE PLANS ARE FOR REFERENCE ONLY. THE PLANS, DETAILS, AND SPECIFICATIONS GOVERN. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW THE ENTIRE CONSTRUCTION SET AND DETERMINE ALL THE FINAL QUANTITIES FOR ALL NECESSARY ITEMS REQUIRED TO COMPLETE THIS PROJECT. THE OWNER OR THE ENGINEER WILL NOT BE HELD LIABLE OR RESPONSIBLE FOR ESTIMATES NOT CONFIRMED BY THE CONTRACTORS. THE CONTRACTOR SHALL VERIFY ALL QUANTITIES PRIOR TO BIDDING AND CONSTRUCTION. IF DISCREPANCIES ARE FOUND, CONTACT THE ENGINEER IMMEDIATELY.



PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY






Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
Br	Brookston silt clay loam, 0 to 2 percent slopes	0.0	0.2%
MpC3	Miami complex, 6 to 12 percent slopes, severely eroded	0.0	2.9%
YbVA	Brookston silt clay loam-Urban land complex, 0 to 2 percent slopes	0.6	33.6%
YcuA	Crosby silt loam-Urban land complex, 0 to 2 percent slopes	1.0	59.3%
YmcC3	Miami-Urban land complex, 6 to 12 percent slopes, severely eroded	0.1	3.9%
Totals for Area of Interest		1.7	100.0%

SOILS MAP AND INFORMATION

National Flood Hazard Layer FIRMette



FLOOD ZONE:

THE PROJECT SITE IS LOCATED WITHIN THE FEMA COMMUNITY PANEL MAP NO. 18059C0018D WITH AN EFFECTIVE DATE OF 12/4/2007. REVIEW OF THE MAP INDICATES THE SITE IS LOCATED WITHIN THE FLOOD DESIGNATION "ZONE AE" (SHADED). "AREAS DETERMINED TO BE INSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN".

FLOOD MAP & FLOOD ZONE INFORMATION

DEMOLITION NOTES:

- It shall be the responsibility of the contractor to remove any materials and/or structures not located on this survey.
- It shall be the responsibility of the contractor to verify all existing utilities and their locations pertaining to their phase of work, and to verify which utilities will be removed by the utility company. Any and all utilities not removed by the utility company shall be removed by the contractor.
- Utility locations shown are approximate and shall be relocated and/or capped at the Right-Of-Way line and abandoned before construction at no additional cost to the owner.
- The owner gets the first right of salvage.
- All demolition material not being salvaged shall be properly disposed of offsite by the contractor.
- The contractor shall obtain all demolition permits required by the local and state agencies.
- The contractor shall maintain streets and shared drives free and clear of sediment and debris.
- The contractor is responsible for the protection of all existing utility lines unless otherwise stated.
- Contractor shall coordinate all temporary shut down of existing utility services with the appropriate utility department, owner, authority, etc.
- Contractor shall coordinate any necessary street or drive closures required.

SITE/LAYOUT NOTES:

- See architectural plans for all building dimensions. Any dimensions shown herein shall be considered conceptual.
- All dimensions are to edge of pavement or face of curb, unless noted otherwise.
- All dimensions are to face of brick or facing material, unless noted otherwise.
- All parking area stripes are to be 4 inch white paint. Handicapped parking areas and access aisles shall be 4 inch blue paint.
- Provide smooth transitions from new areas to existing features as appropriate.
- The edge of existing asphalt pavement shall be properly sealed with a tack coat material in all areas where new asphalt pavement is indicated to join existing pavement.
- Provide chamfer ends at curbs.
- Verify sign locations & sign requirements with local governing municipality. Signs shall meet Indiana MUTCD Manual and specifications.

GRADING NOTES:

- Earthwork & grading shall not start until erosion control measures have been properly installed.
- Occupational safety and health administration (OSHA) standards for excavations; Final Rule 29 CFR Part 1926, subpart "P" applies to all excavations exceeding five (5) feet in depth.
- Provide positive drainage that assures no ponding in all areas. After installation, contractor to test for, and correct, if any, standing water conditions are present.
- All proposed spot elevations are the final pavement and grade elevations. See appropriate details and specifications to determine the subgrade elevations below finish grade elevations for construction.
- All sanitary manholes in non-paved areas shall be 3" above grade.
- The maximum slope to be used in non-paved areas shall be 3:1 unless specifically noted otherwise.
- Minimum swale slopes are 1.0% unless noted or graded otherwise.
- All A.D.A. parking spaces & access aisles shall be level with surface slopes not to exceed 2% (1:50) in any direction as which to comply with A.D.A. requirements.
- ADA sidewalk ramps shall meet ADA requirements and INDOT standard drawings and specifications.
- All sidewalks cross slopes shall not exceed 2% (1:50) unless noted otherwise.
- Provide smooth transitions from new areas to existing features as appropriate.
- All grades shall match existing grades at the project property lines / limits.

UTILITY NOTES:

- The utilities indicated on these construction plans and on the survey may not be a complete inventory of all existing utilities currently on or near the site. The size and location of these utilities may be approximate. The engineer shall not be held liable for any inaccurate utility information indicated, or not indicated on this survey.
- For viewing clarity of these construction plans, the pipes, structures, and appurtenances may not be drawn to scale.
- Coordinate with Architect / M.E.P. and corresponding utility companies for exact size, type, and location for the electric, telephone, gas, fiber optic, and water line services. Utility service providers may require installation of onsite conduits. Contractor shall coordinate requirements for conduits including number, location, pull string, etc. with respective utility providers prior to bidding.
- Location of the utility service connections into the buildings are approximate. See Architectural / M.E.P. plans for exact locations.
- The contractor is responsible with coordinating with the utility companies for connection of the proposed utility lines for this project site.
- Contractor shall coordinate final location of transformers and primary service to transformers with utility at time of service request. Contractor shall provide transformer pads as required by utility company.
- The underdrains depicted on these plans for the storm structures located within the pavement are 10 liner feet minimum (unless specified otherwise within the plans) of 6 inch diameter perforated HDPE pipe. All underdrains shall maintain 18 inches of vertical and 10 feet of horizontal separation from all water and sanitary lines as measured from the outside of pipe walls.
- Underdrains shall have a minimum slope of 1.0% and inverts shall be set a minimum of 6 inches above the outlet pipe, unless noted otherwise.
- All storm HDPE pipe (except for underdrains or underground storage facilities) shall be N-12 (smooth walled) pipe, unless noted otherwise.
- A minimum of 54 inches of cover over the entire water line shall be provided unless the water service utility company requires more stringent (deeper) specifications, and if so, the contractor shall meet those water company specifications.
- All proposed water lines and sanitary lines / laterals shall have a minimum of 18 inches of vertical separation to be maintained when crossing under or over each other, any other utilities, and storm sewer pipes and appurtenances.
- The underdrains depicted on these plans for the storm structures located within the pavement are 10 liner feet minimum (unless specified otherwise within the plans) of 6 inch diameter perforated HDPE pipe. All underdrains shall maintain 18 inches of vertical and 10 feet of horizontal separation from all water and sanitary lines as measured from the outside of pipe walls.
- Full depth granular backfill required for all water lines, sanitary sewers, and storm sewers under and within 5 feet of pavement. / hardscapes.
- All private hydrants shall have an isolation valve installed at the point of branching.
- When connections are to be made to existing piping and structures, or where construction is in the vicinity of existing piping, structures, or appurtenances, the exact locations and elevations of the existing piping, structures and / or appurtenances shall be field verified onsite by the contractor prior to construction. If any discrepancies are found, then the engineer shall be notified immediately. Fritz Engineering Services, LLC shall not be responsible for any discrepancies that may arise between the plan information and actual field verified information as determined from any final onsite investigation from the contractor.

ABBREVIATIONS AND TERMS

IE / INV	= INVERT ELEVATION
BC	= BOTTOM OF CURB
TC	= TOP OF CURB
RIM	= RIM / TOP OF CASTING
GUT	= GUTTER
RCP	= REINFORCED CONCRETE PIPE
HDPE	= HIGH DENSITY POLYETHYLENE PIPE
SSD	= SUB-SURFACE DRAIN
UD	= UNDERDRAIN
MH	= MANHOLE
STR	= STRUCTURE
DE	= DRAINAGE EASEMENT
RD&UE	= REGULATED DRAIN AND UTILITY EASEMENT
D&UE	= DRAINAGE AND UTILITY EASEMENT
SD&UE	= SANITARY, DRAINAGE, AND UTILITY EASEMENT
W&UE	= WATER AND UTILITY EASEMENT
SE	= SANITARY EASEMENT
SAN	= SANITARY SEWER
HC	= HANDICAP RAMP
ME	= MATCH EXISTING
STM	= STORM SEWER
MPE	= MINIMUM PAD ELEVATION
NP	= NORMAL POOL
ELEV	= ELEVATION
TYP	= TYPICAL
PR	= PROPOSED
EX	= EXISTING
R	= RADIUS
B-B	= BACK TO BACK
ROW or R/W	= RIGHT OF WAY
LF	= LINEAR FEET

PROPOSED LEGEND

HYDRANT	FLOW LINE, PAVEMENT
VALVE	FLOW LINE, SWALE (GRASS)
TEE	FOUNDATION DRAIN
ADAPTER	CABLE TV LINE**
BEND	ELECTRIC LINE**
TEMP. FLUSH HYDRANT	FIBER OPTIC LINE
BLOW-OFF	SUB-SURFACE DRAIN
THRUST BLOCK	STORM UNDERDRAIN
PLUG	STORM SEWER
REDUCER	SANITARY SEWER
M.J. SLEEVE	FORCE MAIN
CROSS	GAS LINE
WATER METER	TELEPHONE LINE**
POST INDICATOR VALVE	WATER LINE
FIRE CONNECTION	
TRANSFORMER PAD	**PREFIX FOR UTILITY LINES:
RELOCATED ELECTRIC/TELEPHONE POLE	UG - UNDERGROUND
SIGN	OH - OVERHEAD
HANDICAP PARKING	
CLEAN OUT	FLOW ARROW
STORMTECH STORM CHAMBER	EXISTING CONTOURS
SEWER MANHOLE	PROPOSED CONTOURS
STORM COMBINATION INLET	
STORM GRATE INLET	
STORM BEEHIVE/YARD DRAIN	
STORM END SECTION	
BMP/AQUA-SWIRL	
STORM STRUCTURE NUMBER	

F.E.S.TOPOGRAPHIC LEGEND

CONTOUR LINE	FENCES
DRIP LINE	FIELD DIVISION
	GARDEN & LANDSCAPING
	VEGETATION (HEDGE - BUSH - PLANT) ROW
	WOODS/BRUSH LINE
	WATERS EDGE AND FLOW LINE
	WATER FLOW LINE / DITCH LINE
	GUARDRAIL
	RIPRAP
	RAILROAD
	ELECTRIC TRANSFORMER
	OVERHEAD UTILITY
	UNDERGROUND ELECTRIC
	UNDERGROUND GAS
	UNDERGROUND CABLE
	UNDERGROUND FIBER OPTIC LINE
	UNDERGROUND TELEPHONE
	UNDERGROUND WATER
	UNDERGROUND STORM (DRAINAGE) SEWER
	UNDERGROUND COMBINATION SEWER
	UNDERGROUND SANITARY SEWER
	UNDERGROUND SEWER MISC. (UNKNOWN TYPE)
HOUSE / BUILDING	ASPHALT PAVEMENT
CONCRETE PAVEMENT / SIDEWALK	GRAVEL / STONE

SURVEY CONTROL

- SURVEY CONTROL
- TEMP. BENCHMARK
- SURVEY POINT I.D.

PROPERTY

- GATE POST
- FENCE POST
- "T" POST
- RIGHT-OF-WAY MONUMENT
- AIR CONDITIONING UNIT
- BOLLARD - CONCRETE
- BOLLARD - WOOD
- COLUMN / SUPPORT POST
- FLAG POLE
- SINGLE MAILBOX
- DOUBLE MAILBOX
- MULTIPLE MAILBOX
- SATELLITE DISH
- GAS STATION MANHOLE
- GAS STATION MONITORING WELL

SANITARY

- CISTERN
- GREASE INTERCEPTOR
- GRINDER PUMP
- SANITARY CLEANOUT
- SANITARY LATERAL STUB MARKER
- SANITARY MANHOLE
- MISC. OR COMBINE SEWER STR.

WATER

- SEPTIC TANK
- FIRE DEPARTMENT CONNECTION
- FIRE HYDRANT
- POST INDICATOR VALVE
- SPRINKLER HEAD
- WELL

UTILITY APPURTENANCES

- INDICATES UTILITY TYPE
- CABINET
- MANHOLE
- METER
- PEDESTAL
- RISER
- UTILITY TUB
- VALVE
- VENT PIPE
- WARNING MARKER

UTILITY DESIGNATIONS ("##")

- TV - CABLE
- E - ELECTRIC (ELEC.)
- G - GAS
- I - IRRIGATION
- S - SANITARY
- T - TELEPHONE (TELE.)

- FM - FORCE MAIN
- S - SPRINKLERS
- TR - TRAFFIC
- F / FO - FIBER OPTICS
- R / RR - RAILROAD
- U - UTILITY
- W - WATER

FRITZ
ENGINEERING SERVICES

14020 MISSISSINNEWA DRIVE
CARMEL, INDIANA 46033
P: 317.324.8695 F: 317.324.8717
www.Fritz-Eng.com

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY

GENERAL NOTES / LEGEND:



Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.

PROJECT:

GREEN TOUCH SERVICES

GREEN TOUCH MCCORDSVILLE

PROJECT LOCATION:

6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY

SECTION, TOWNSHIP, RANGE:

NE 1/4, S26, T17N, R5E

CLIENT:

MacDOUGALL PIERCE CONSTRUCTION

12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:

3/8/2024

DESIGN: AF CHECK: AF DRAWN: KG

PROJECT NO:


2308005

SHEET NAME:

GENERAL INFORMATION PLAN

SHEET NO.

C101



GENERAL NOTES, UTILITY NOTES AND DISCLAIMERS:


- For viewing clarity of this map or plat, the pipes, structures, and appurtenances may not be drawn to scale.
- The utilities indicated on this survey plat may not be a complete inventory of all existing utilities currently on or near the site. The size and location of these utilities may be approximate. Indiana 811 was contacted for this survey. Private utility locates were NOT contacted for this survey per the survey scope. No attempt was made as part of this survey to obtain or show data concerning existence, size, depth, condition, capacity, or location of any utility, public service facility, or utility service lines to the property. No excavations were made during the course of this survey to locate underground utilities and/or structures. Only what was marked by the utility companies via Indiana 811 were field located and shown on the survey. No assumptions were made connecting utilities observed and located to other appurtenances or how they enter or connect into adjoining houses or buildings unless observed or identified by Indiana 811. Before design or construction is to begin, locations should be confirmed with the appropriate agencies. Underground utilities depicted on the attached plat of survey have been measured and located per above grade field observations, utility markings, and/or scaled off utility plans only. No warranty, either expressed or implied, is made to the accuracy and/or completeness of information presented on underground utilities, or as to its fitness for any particular purpose or use. In no event will Fritz Engineering Services, LLC, its employees, agents, and/or assigns be liable for any damages arising out of the furnishing and/or use of such information. The path of the utility lines on said plat of survey should be considered approximate until they are either relocated, by calling Indiana 811 and other utility locate companies, or until they are excavated to verify the location and path of the utility lines.
- Unless otherwise stated, sewer measurements were performed with limited access. Field measurements were determined as physically observed (sometimes with limited visibility) and without confined space entry. Pipe sizes and measurements under certain conditions may be provided from other sources (as stated) in electronic format via GIS data or from record drawings provided by other agencies.
- Storm, sanitary, or combined sewers were located per visible, observed evidence only. Excavations of sewers, or corresponding structures, were not conducted by Fritz Engineering Services, LLC.
- Sewer pipe lengths as shown per this survey are from each field located shot of the structures and are not shortened or lengthened to adjust for the size, orientation, or shape of structures, and therefore the pipe lengths as depicted on this survey are approximate.
- Measure down data (Structure Details) for sewer structures is considered approximate, and while extensive effort was made to get all pertinent information and measurements for each sewer structure, physical and safety issues do cause limitations in the ability to always collect and measure accurately the field data associated with each structure. Depth, orientation, and condition of the structures and incoming pipes can make determining sizes, material types, and inverts difficult to determine or evaluate. Fritz Engineering Services, LLC employees do not enter sewer structures to collect and measure data due to safety, health, and liability issues. Fritz Engineering Services, LLC, its employees, agents, and/or assigns shall not be held liable or their work be considered incomplete if discrepancies are found between the measure down data collected for this project and onsite field checks and/or observations performed by other parties. For some sewer structures, the accuracies for inverts may have an uncertainty up to 0.5 feet and pipe sizes may vary up or down one pipe size.

UTILITY REQUEST (INDIANA 811) NOTES:

Indiana 811 was requested via their website on 09/25/2023.
The Indiana 811 ticket numbers are as follows: 2309252624 & 2309252744

- Per the Indiana 811 ticket, the follow utilities may be located near or onsite:
- CENTERPOINT ENERGY (gas)
 - CHARTER COMMUNICATIONS INDIANAPOLIS (cable tv, fiber)
 - CHARTER COMMUNICATIONS MARION - FORMERLY BRIGHT HOUSE (cable tv, fiber)
 - CITIZENS WATER (water)
 - INDIANAPOLIS POWER AND LIGHT COMPANY (electric)
 - AT&T-TRANSMISSION (fiber)
 - NINE STAR CONNECT (telephone)
 - MCCORDSVILLE PUBLIC WORKS (storm, sewer)

See the "Utility Notes and Disclaimers" in regards to the location of utilities and how this item relates to the survey.



U.S. PUBLIC LAND SURVEY SYSTEM (USPLSS) SECTION LINE

RECOVERED MONUMENTS:

The recovery of section corner monuments and the establishment of section lines for the Northeast Quarter of Section 26, Township 17 North, Range 5 East, worthy of mention are as follows:

Four (4) of the section corner monuments required for this survey had County Surveyors Office Section Corner Records. The County Surveyors Office Section Corner Records provide corresponding published coordinates (Indiana State Plane East) for the section corner monuments / locations. These published coordinates coordinate system is based upon the same coordinate system utilized for this survey. The difference between the measured coordinates obtained for this survey as compared to the published coordinates for all section corners located as part of this survey were within 0.04 to 0.23 feet, which is within allowable measurement tolerances for this survey.

Northeast Corner of Section 26 (Pt. No. 1000):

A brass disc monument 0.1 feet below grade was recovered per the Hancock County Surveyors Office Section Corner Records. There is considered to be no uncertainty associated with this corner.

Northeast Corner of the Northwest Quarter of the Northeast Quarter of Section 26 (Pt. No. 1001):

A brass disc monument in 10 inch by 10 inch concrete pad flush with grade was recovered per the Hancock County Surveyors Office Section Corner Records. There is considered to be no uncertainty associated with this corner.

North Quarter Corner of Section 26 (Pt. No. 1002):

A brass pin monument 0.1 feet below grade was recovered per the Hancock County Surveyors Office Section Corner Records. There is considered to be no uncertainty associated with this corner.

Southeast Corner of the Southwest Quarter of the Northeast Quarter of Section 26 (Pt. No. 1005):

A 5/8 inch diameter rebar leaning west (located at apparent center) was recovered. No County Surveyors Office Section Corner Records were found online or shown on the County GIS for this section corner location. Per the recovered evidence and documentation available, it is believed that this is the best prima facie evidence to re-establish this section corners location. There is considered to be anywhere from 0.1 feet to 39 feet of uncertainty associated with this corner location.

East Quarter Corner of Section 26 (Pt. No. 1009):

A mag nail with washer stamped "Wimmer LS20200013" was recovered. Per the Hancock County Surveyors Office Section Corner Records a bras monument is denoted at this section corner location. Per comparison between this survey's measured coordinates for this stamped mag nail with washer to the County Surveyors published coordinates for this section corner location, the two coordinates were within 0.11 feet of one another. Therefore this mag nail with washer was held as such. There is considered to be no uncertainty associated with this corner location.

Southwest Corner of the Southwest Quarter of the Northeast Quarter (Center of Section) of Section 26 (Calculated Location):

No monument was recovered at this location. No County Surveyors Office Section Corner Records were found online or shown on the County GIS for this section corner location. This section corner location was established per a boundary survey received by the client / owner as prepared by Gibson Surveying Group, Inc dated 02/20/2008 with a job number of 3294. Per this Gibson survey, a boat spike was recovered and held as this section corner. This monument was not found. This section corner location as established by this Gibson survey was correlated into this survey's coordinate system / basis of bearings. This correlation, and therefore section corner location, was established based on holding the angular and distance relationships between the corresponding section corner monuments recovered for both this survey and this Gibson boundary survey. Per the recovered evidence and documentation available, it is believed that this is the best prima facie evidence to re-establish this section corners location. There is considered to be between 1.0 feet to 9.0 feet of uncertainty associated with this corner location.

Southwest Corner of the Northwest Quarter of the Northeast Quarter of Section 26 (Calculated Location):


No County Surveyors Office Section Corner Records were found online or shown on the County GIS for this section corner location. Two (2) square, flat, flush with grade stones were found near this location. These stones appeared to be placed, but also do not appear to be monuments. By connecting the North Quarter corner of Section 26 to the calculated location for the Southwest Quarter of the Southwest Quarter of the Northeast Quarter of Section 26 (center of section) to establish this west section line of the Northeast Quarter of Section 26, these stones fell within 0.2 and 0.4 feet of said west section line as measured from their centers. An old wood fence post was also found at this location. The wood fence post line was located 3.2 feet east of said west section line. This old wood fence post was initially used as this section corner location, but when the section lines as established from this fence post were compared to onsite field evidence, lines of occupations, and distance calls in the subject tracts, it was concluded that this fence post was not the section corner location. Ultimately, this section corner location was established by subdivided into aliquot parts this quarter section by survey protraction methods to establish said corner location. There is considered to be up to 6.6 feet of uncertainty associated with this corner location.

Southeast Corner of the Northeast Quarter of the Northeast Quarter of Section 26 (Calculated Location):

No monument was recovered at this location. No County Surveyors Office Section Corner Records were found online or shown on the County GIS for this section corner location. The quarter section was subdivided into aliquot parts by survey protraction methods to establish this section corner location. There is considered to be an unknown amount of uncertainty associated with this corner location.

Center of Quarter Section of the Northeast Quarter of Section 26 (Calculated Location):

No monument was recovered at this location. No County Surveyors Office Section Corner Records were found online or shown on the County GIS for this section corner location. The Center of this Quarter Section location was established by the intersection of 16th section lines as established between recovered and calculated 16th section corner locations. There is considered to be an unknown amount of uncertainty associated with this corner location.



VICINITY MAP

(NOT TO SCALE)

SUBJECT TRACT 1 LAND DESCRIPTION OF RECORD:

Per Instrument Number 070010933 (Office of the Recorder of Hancock County, Indiana).

Ownership per Deed and County Parcel Report: G.T. Real Estate, LLC

Please note, any errors (spelling, grammar, intent, etc.) or omissions in the land description is not a representation of Fritz Engineering Services, LLC (FES). FES did not create the land description, but said land description is shown below exactly as worded / written per the deed of record and/or title commitment.

A part of the Northeast Division of the Northeast Quarter of Section 26, Township 17 North, Range 5 East described as follows: Beginning at a point 14 rods, 21.3 feet west of the southeast corner of the Northwest Quarter of the Northeast Quarter of Section 26. Township and Range aforesaid: thence east one rod, one and one half (1 - 1/2) feet; thence southeasterly at right angles to the C.C.C. & St. L. Railroad to the north line of the Union Traction Company's right-of-way thence northeasterly on the north line of said Traction Company's right of way 227 - 1/2 feet; thence west and parallel with the south line of the Northwest Quarter of said Northeast Quarter to the line dividing the lands of Conrad H. Crosley and Margaret Bolander as formerly owned; thence south on said division line to the south line of said Northwest Quarter of said Northeast Quarter; thence east on said south line 283.3 feet to the place of beginning, containing 1.15 acres, more or less, and being the same real estate conveyed to said grantor, Gertrude Crawford, as appears in Deed Record 99, page 291 and also in Deed Record 100, page 53 in Recorders Office of Hancock County, Indiana.

SUBJECT TRACT 2 LAND DESCRIPTION OF RECORD:

Per Instrument Number 9708964 (Office of the Recorder of Hancock County, Indiana).

Ownership per Deed and County Parcel Report: G.T. Real Estate, LLC

Please note, any errors (spelling, grammar, intent, etc.) or omissions in the land description is not a representation of Fritz Engineering Services, LLC (FES). FES did not create the land description, but said land description is shown below exactly as worded / written per the deed of record and/or title commitment.

A strip of land owned by Indiana Railroad and formerly used as a right of way for an interurban electric railroad situated in the Northeast Quarter of Section Twenty-six (26), Township Seventeen (17) North, Range Five (5) East, in Hancock county, Indiana, said strip of land being 53 feet in width and 268.5 feet in length lying North of, parallel to and adjoining the Northerly boundary line of a certain parcel of land as was conveyed to Omer E. Stoner by Bertie E. Smith, Administrator by a deed dated December 30, 1927 recorded in the Recorder's Office of Hancock County, Indiana, in Deed Record 102, page 252.

A part of the West Half of the Northwest Quarter of Section Twenty-six (26), Township Seventeen (17) North, Range Five (5) East, located between the right of way of the Union Traction Company of Indiana and the right of way of the C.C.C. & St. Louis Railway Company and described as follows, to-wit: Beginning at a stone at the Northeast corner of said West Half; thence South 01 degrees 40 minutes East 1222.5 feet; thence South 38 degrees 44 minutes West 73 feet which is the point of beginning; thence south 38 degrees 44 minutes West 82.5 feet; thence with a curve to the West of 2664.5 feet radius for a distance of 186.2 feet; thence Southeasterly at right angles to the right of way of the said C.C.C. & St. Louis Railway Company 133.25 feet; thence Northeasterly parallel with the said center line of said Railway Company 249.5 feet; thence Northwesterly 215 feet to the place of beginning.

A strip of land herein conveyed contains .32 of an acre more or less, and being a part of a 33 foot strip of land as was conveyed to Union Traction company of Indiana by E.H. Thompson by a deed dated January 10, 1900 and recorded in the Recorder's Office of Hancock County, in Deed Record 73 page 42 and also a part of a 20 foot strip of land as was conveyed to Union Traction Company of Indiana by Henry N. Thompson by a deed dated August 27, 1900 recorded in the Recorder's Office of Hancock County in Deed Record 74, page 359.

Containing in both descriptions 1.31 acres, more or less.

SECONDARY PLAT - MODERNIZED LAND DESCRIPTION:

A part of the Northeast Quarter of Section 26, Township 17 North, Range 05 East, Vernon Township, Town of McCordsville, Hancock County, Indiana and being part of the tracts of land as described in Instrument Numbers 9708964 and 070010933 as recorded in the Office of the Recorder of Hancock County, Indiana, and as shown on the plat of an Retracement Boundary Survey as certified by Nikolas M. Schmitt, P.S. No. LS21200004 (Fritz Engineering Services, LLC) project number FES 2308005 - Green Touch Project (all references to monuments and courses herein are as shown on said plat of survey) and more particularly described as follows:

Commencing from the Northeast corner of the Northwest Quarter of the Northeast Quarter of said Section 26; thence South 00 degrees 12 minutes 42 seconds West on and along the east line of said Quarter-Quarter Section with the basis of bearing being NAD83 Indiana State Plane East Zone, 1199.37 feet to the south line of the D&D Vail Trust tract of land as described in Instrument Number 202001289 as recorded in said Hancock County Recorders Office, said point being the Point of Beginning and being marked by a 5/8 inch diameter rebar with pink cap stamped "Fritz Eng. Boundary Firm #0152" (hereon referred to as Fritz capped rebar); thence North 89 degrees 11 minutes 02 seconds East on and along said south line 8.85 feet to the center of the of Stansbury Ditch (Stansbury and Schultz Regulated Drain), with the next five (5) courses being on and along the centerline of said Stansbury Ditch with the courses representing a meander line of said centerline; (1) thence South 38 degrees 40 minutes 12 seconds East 13.85 feet; (2) thence South 16 degrees 30 minutes 16 seconds East 25.17 feet; (3) thence South 24 degrees 27 minutes 17 seconds East 57.96 feet; (4) thence South 33 degrees 55 minutes 21 seconds East 121.40 feet; (5) thence South 32 degrees 23 minutes 00 seconds East 28.04 feet to the northern railroad right-of-way of the CSX Transportation Railroad (formerly C.C.C. & St. L. Railroad) as being marked by a mag nail with washer stamped "Fritz Eng. Boundary Firm #0152" (hereon referred to as Fritz mag nail); thence South 56 degrees 15 minutes 58 seconds West on and along said northern railroad right-of-way 244.86 feet to a Fritz mag nail; thence North 33 degrees 44 minutes 02 seconds West at right angles (perpendicular) to said northern railroad right-of-way 277.71 feet to the south section line of said Quarter-Quarter section (Northwest Quarter of the Northeast Quarter of Section 26), said point being marked by a Fritz mag nail; thence South 89 degrees 11 minutes 02 seconds West on and along said south section line 272.64 feet to the east line of the D&D Vail Trust tract of land as described in Instrument Number 20201288 as recorded in said Hancock County Recorders Office; thence North 00 degrees 17 minutes 35 seconds East on and along said east line 113.80 feet to said south line of said D&D Vail Trust tract of land as described in said Instrument Number 202001289 as recorded in said Hancock County Recorders Office, with said point being marked by a Fritz capped rebar; thence North 89 degrees 11 minutes 02 seconds East on and along said south line and parallel to the south section line of said Quarter-Quarter Section 498.53 feet to the Point of Beginning, containing 2.513 acres (109,466 square feet), more or less.



MONUMENTATION LEGEND

- | | |
|---------------|--|
| MON. SET C.R. | MONUMENT SET, CAPPED REBAR |
| MON. SET MAG | MONUMENT SET, MAG NAIL WITH STAMPED WASHER |
| CHISEL "X" | CHISEL "X" SCRIBED / CUT AS SET MONUMENT |

SET PROPERTY CORNER MONUMENTS TO BE:
24 IN. x 5/8 IN. DIA. REBAR WITH STAMPED PINK CAP SET FLUSH WITH GRADE OR WHERE CORNER IS ON HARDSCAPE, A MAG NAIL WITH STAMPED WASHER.

MONUMENT STAMPING: "FRITZ ENG. BOUNDARY FIRM # 0152"

REFERENCE MONUMENTS UTILIZED FOR OFFSETS
POINTS IN RELATIONSHIP TO P.L. CORNERS NOT ABLE TO BE SET IN FIELD. "##" INDICATES OFFSET DISTANCE IN FEET.

REFERENCE MONUMENT / OFFSET POINTS TO BE:
24 IN. x 5/8 IN. DIA. REBAR WITH STAMPED YELLOW CAP SET FLUSH WITH GRADE OR WHERE CORNER IS ON HARDSCAPE, A MAG NAIL WITH STAMPED WASHER.

MONUMENT STAMPING: "FRITZ ENG. REFERENCE POINT FIRM # 0152"

BOUNDARY SURVEY LEGEND

- | | | | |
|----|--|---------------------|----------------------|
| # | SURVEY POINT / MONUMENT NUMBER I.D. | # | KEYNOTE |
| + | SURVEY CONTROL | + | PARCEL I.D. |
| ● | RECOVERED MONUMENTS | ○ | GATE POST |
| ▲ | U.S.P.L.S.S. SECTION CORNER LOCATION | PPST | FENCE POST |
| ○ | ALIGNMENT POINT (RECOVERED OR CALC.) | 1 + P | "T" POST |
| ⊠ | R/W RECOVERED RIGHT-OF-WAY MONUMENT | | |
| ● | SET BOUNDARY CORNER MONUMENT | | |
| + | U.S.P.L.S.S. SECTION CORNER DELINEATION SYMBOL | +00' "#" | STATION OFFSET LABEL |
| ## | "#" INDICATES SECTION NUMBER | ("#" = ALIGN. NAME) | |

- | | | | |
|------|--|------|------------|
| --- | SURVEY PROPERTY LINE | | |
| --- | U.S.P.L.S.S. SECTION LINE | | |
| --- | ALIGNMENT | | |
| --- | APPARENT CENTERLINE | | |
| --- | EXISTING R/W OR LIMITED ACCESS R/W | | |
| --- | APPARENT R/W OR APPARENT R.E.R. (R.W.) | | |
| --- | APPARENT ADJACENT P.L. / LOT LINES | | |
| --- | APPARENT EASEMENT | | |
| --- | APPARENT REGULATED (LEGAL) DRAIN | | |
| --- | SURVEY LINE / APP. DEED LINE | | |
| 0 | X | | FENCES |
| ---- | WATERS EDGE | ---- | WOODS LINE |

- | | | | |
|-----|------------------------------|-----|------------------|
| --- | HOUSE / BUILDING | --- | ASPHALT PAVEMENT |
| --- | CONCRETE PAVEMENT / SIDEWALK | --- | MISC. MATERIAL |

ABBREVIATIONS

- | | | | |
|------------|-----------------------------------|-------------|---------------------------|
| P.L. | = PROPERTY / BOUNDARY LINE | L | = LENGTH |
| APP. | = APPARENT | R | = RADIUS |
| EX. | = EXISTING | T | = TANGENT |
| R/W or ROW | = RIGHT-OF-WAY | CL | = CENTERLINE |
| LA | = LIMITED ACCESS | ALIGN. | = ALIGNMENT |
| REG. | = REGULATED | B.A. | = BEG. OF ALIGNMENT |
| B.S.L. | = BUILDING SET-BACK | E.A. | = END OF ALIGNMENT |
| ESMT. | = EASEMENT | P.C. | = POINT OF CURVATURE |
| V.W. | = VARIABLE WIDTH | P.T. | = POINT OF TANGENCY |
| NO. | = NUMBER | P.I. | = POINT OF INTERSECTION |
| INSTR. | = INSTRUMENT | P.O.C. | = POINT ON CURVE |
| P.O.B. | = POINT OF BEGINNING | P.O.T. | = POINT ON TANGENT |
| L.C.R.S. | = LOCATION CONTROL ROUTE SURVEY | P.C.C. | = POINT OF COMPOUND CURVE |
| INDOT | = INDIANA DEPT. OF TRANSPORTATION | P.R.C. | = POINT OF REVERSE CURVE |
| CALC. | = CALCULATED | MID | = MIDPOINT |
| REC. | = RECORDED | CH | = CHORD |
| MEAS. | = MEASURED | B-B | = BACK TO BACK |
| DEED | = RECORDED DEED | L.F. | = LINEAR FEET |
| PLAT | = RECORDED PLAT | BLD. | = BUILDING |
| SURV. | = RECORDED SURVEY | HC | = HANDICAP SPACE |
| A.MAP | = AUDITOR / ARBITRARY SUB. MAP | FL | = FLOW LINE / DITCH LINE |
| TITLE | = TITLE COMMITMENT | ELEV. | = ELEVATION |
| SUB. | = SUBDIVISION PLAT | A.G. / B.G. | = ABOVE / BELOW GRADE |
| G.I.S. | = GEOGRAPHIC INFORMATION SYSTEM | DIA. | = DIAMETER |
| PLANS | = PUBLISHED OR RECEIVED PLANS | FND. | = FOUND |
| RT. / LT. | = RIGHT / LEFT | MON. | = MONUMENT |

PRIMARY PLAT INTERURBAN PLACE

SUBDIVIDER

G.T. REAL ESTATE LLC
6314 W. BROADWAY, MCCORDSVILLE, IN 46055

PROJECT ADDRESS:

7776 DEPOT STREET (TRACT 1) & 6312 RAILROAD STREET (TRACT 2)
MCCORDSVILLE, IN 46055

PREPARED BY: NICKOLAS M. SCHMITT
FRITZ ENGINEERING SERVICES, LLC

PROJECT NUMBER: 2308005
DATE: 12/27/2023




ANALYSIS BY: NMS
DRAFTED BY: NMS

CHECKED BY: NMS

PLAT STATUS
PRO-FORMA

SHEET NUMBER
1 OF 2





KEY NOTES:

- A1 CONCRETE PAVEMENT
- C13 CONCRETE 6 INCH "STRAIGHT" CURB
- C15 CONCRETE CHAIRBACK CURB AND GUTTER
- C16 CURB AT TOP OF SLOPE
- D1 LIGHT DUTY ASPHALT PAVEMENT
- D2 HEAVY DUTY ASPHALT PAVEMENT
- D3 PUBLIC RIGHT-OF-WAY GOVERNING MUNICIPALITY ASPHALT PAVEMENT
- E EXISTING CURB / PAVEMENT / SIDEWALK TO REMAIN
- F1 CONCRETE SIDEWALK
- F2 CONCRETE INTEGRAL / MONOLITHIC CURB AND WALK
- I INLET / CASTING CONCRETE COLLAR APRON
- K ROADWAY PAVEMENT REPAIR CUTS (FULL DEPTH AS REQUIRED) FOR UTILITY TRENCH CONSTRUCTION. PAVEMENT TYPE, LIMITS, AND SUB-GRADE SHALL MATCH THE GOVERNING MUNICIPALITY REPAIR CUT RIGHT-OF-WAY DETAILS. THE BACKFILL REQUIREMENTS FOR THE TRENCH SHALL MEET THE CORRESPONDING UTILITY REQUIREMENTS FOR THAT TYPE OF PIPE INSTALLATION. THE PAVEMENT SHALL MATCH EXISTING GRADES.
- L EXTERIOR LIGHTS. VERIFY FINAL LOCATION WITH PHOTOMETRIC PLAN.
- M MATCH INTO EXISTING
- S34 4 INCH SOLID WHITE PAVEMENT STRIPING (TYP.)
- S37 ADA BLUE PAVEMENT STRIPING AND MARKINGS
- S38 WHITE PAVEMENT CROSSWALK TRANSVERSE MARKING
- T1 CURB TAPER
- T2 FLUSH CURB FOR RAMP TRANSITION
- T3 CURB TURNOUT / CHUTE
- U DUMPSTER ENCLOSURE (SEE ARCHITECTURAL PLANS)
- X1 HANDICAP PARKING SIGN
- Y BICYCLE PARKING
- Z LANDSCAPE AREA
- AA SIDEWALK TRANSITION AT COMMERCIAL DRIVE (REF. INDOT DETAILS)
- AB CONCRETE PARKING BARRIER

FRITZ
ENGINEERING SERVICES

14020 MISSISSINNEWA DRIVE
CARMEL, INDIANA 46033
P: 317.324.8695 F: 317.324.8717
www.Fritz-Eng.com

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY

GENERAL NOTES / LEGEND:



Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.

PROJECT:

GREEN TOUCH SERVICES
MCCORDSVILLE

PROJECT LOCATION:
6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY

SECTION, TOWNSHIP, RANGE:
NE 1/4, S26, T17N, R5E

CLIENT:

MacDOUGALL PIERCE CONSTRUCTION
12720 FORD DRIVE
FISHERS, IN 46038


PLAN DATE:
3/8/2024

DESIGN: AF	CHECK: AF	DRAWN: KG
---------------	--------------	--------------

PROJECT NO:
2308005


SHEET NAME:
SITE PLAN

SHEET NO.:
C201



NOTES:

1. REF. C101 FOR ABBREVIATIONS AND ADDITIONAL LEGEND INFORMATION.



PRELIMINARY
NOT FOR
CONSTRUCTION

[illegible]

GENERAL NOTES / LEGEND:


"IT'S THE
LAW"
811
Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.

CLIENT:
**MacDOUGALL PIERCE
CONSTRUCTION**
12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:		
3/8/2024		
DESIGN: AF	CHECK: AF	DRAWN: KG
PROJECT NO.		
2308005		
SHEET NAME		
GRADING PLAN		
SHEET NO.		
C301		


© 2024 FRITZ ENGINEERING SERVICES, LLC

PRINTED BY: Ashton Fritz
DATE: 3/7/2024 9:41 AM
SHEET SIZE, SCALE: ANSI FULL BLEED D (34.00 X 22.00 INCHES), 1:1
FILE NAME: C:\3726\370008 - GREEN TOUCH MCCOYSDVILLE ELEM CMV (B) ANISO-301.DWG LAYOUT: C:\37





KEY NOTES:

- | | |
|-----|--|
| E1 | ELECTRIC - NEW TRANSFORMER, COORDINATE NEW SERVICE LINE WITH M.E.P. PLANS AND POWER UTILITY COMPANY. |
| E2 | ELECTRIC - PROPOSED SERVICE LINE. COORDINATE WITH ELECTRIC COMPANY AND FINALIZE BUILDING CONNECTION WITH ARCHITECTURAL / M.E.P. PLANS. |
| E3 | ELECTRIC - SECONDARY CONDUIT, COORDINATE WITH M.E.P. PLANS FOR SIZE AND CABLE REQUIRED. COORD. WITH POWER UTILITY COMPANY AS REQUIRED. |
| E4 | ELECTRIC - COORDINATE POWER DISTRIBUTION ONSITE WITH M.E.P. / SITE ELECTRICAL PLAN. |
| G1 | GAS - GAS SERVICE LINE, COORDINATE SIZE & LOCATION WITH M.E.P. PLANS AND GAS COMPANY. |
| G2 | GAS - GAS METER, COORD WITH M.E.P. PLANS & GAS COMPANY. |
| SS1 | SANITARY - 6 INCH DIAMETER SDR 26 PVC LATERAL @ 1.04% MINIMUM. LATERAL INSTALLATION SHALL INCLUDE FULL DEPTH GRANULAR BACKFILL WHERE LOCATED UNDER PAVED AREAS AND SHALL HAVE TRACER WIRE INSTALLED FROM THE BUILDING CLEANOUT TO THE MAIN CONNECTION IN ACCORDANCE WITH MCCORDSVILLE SANITARY STANDARDS. |
| SS2 | SANITARY - BUILDING CLEANOUT PER MCCORDSVILLE SANITARY STANDARDS, SEE PLAN FOR INVERTS. CLEANOUTS SHALL MATCH SIZE OF LATERAL PIPE UP TO A MAXIMUM 8 INCHES. CLEANOUT SHALL BE LOCATED 36 INCHES FROM BUILDING. |
| SS3 | SANITARY - CONNECT PROPOSED LATERAL TO EXISTING SANITARY LATERAL NEAR RIGHT-OF-WAY LINE. HORIZONTAL LOCATION PER SURVEY INTERPOLATION. LATERAL STUB CONNECTION INVERT ELEVATION CALCULATED AND NOT FIELD VERIFIED, AND THEREFORE INVERT SHALL BE CONSIDERED "PRELIMINARY" IN NATURE. CONTRACTOR TO VERIFY EXACT LOCATION, SIZE, MATERIAL, AND DEPTH OF EXISTING LATERAL PRIOR TO CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCIES. UPSTREAM EXISTING LATERAL TO BE ABANDONED SHALL BE REMOVED.

THE EXISTING INVERT OF THE EXISTING LATERAL AT THE PROPOSED CONNECTION POINT SHALL BE 845.0 OR LOWER. IF THE CONNECTION INVERT IS HIGHER THAN REQUIRED AS STATED, THE MINIMUM PROPOSED LATERAL PIPE SLOPE AND COVER MAY NOT BE ABLE TO BE MAINTAINED THROUGHOUT THE SITE UP TO THE BUILDING CONNECTION PER PLANS AND PER MCCORDSVILLE SANITARY STANDARDS. CONTACT ENGINEER IMMEDIATELY. |
| SS4 | SANITARY - CCTV INVESTIGATION REQUIRED FOR EXISTING LATERAL STUB / TIE-IN CONNECTION. CCTV INVESTIGATION FILE MUST BE AVAILABLE FOR THE LATERAL INSPECTION. COORDINATE WITH SEWER COMPANY. |
| 6XX | STORM - PROPOSED STRUCTURE.
REFERENCE STORM STRUCTURE TABLE  |
| RD1 | ROOF DRAINS - BUILDING DOWNSPOUT LOCATIONS, VERIFY WITH ARCHITECTURE PLAN. NO ROOF DRAIN CONNECTIONS PROPOSED FOR THIS PROJECT. DOWNSPOUTS TO DRAIN ONTO SPLASH PADS AT GRADE AS SPECIFIED BY THE OWNER. SEE ARCHITECTURE OR LANDSCAPE PLANS FOR SPLASH PAD TYPES. |
| RD1 | ROOF DRAINS - BUILDING CONNECTION AND CLEANOUT. REFERENCE M.E.P. PLANS FOR EXACT SIZE AND LOCATION OF ROOF DRAIN DOWNSPOUT. CLEANOUT TO BE LOCATED APPROX. ## FEET FROM THE BUILDING. SEE ROOF DRAIN / DOWNSPOUT DETAILS FOR FURTHER INFORMATION. |
| RD2 | ROOF DRAINS - COLLECTOR PIPE LINE. SEE PLANS FOR LENGTH.
SEE PLANS FOR MATERIAL, SIZE AND SLOPE.
OR
(# INCH DIAMETER HDPE N-12 AT 1.00% MINIMUM SLOPE) |
| UD1 | UNDERDRAIN - 6 INCH DIA. PERFORATED HDPE UNDERDRAIN AS SPECIFIED FOR DRY DETENTION DRAINAGE. SEE DETAILS FOR UNDERDRAIN PLACEMENT SPECIFICATIONS. CONNECT TO ADJACENT DRAINAGE STRUCTURES AS ILLUSTRATED. |
| W1 | WATER - PROPOSED 4 INCH TAPPING SLEEVE VALVE & BOX ON EXISTING 8 INCH WATER MAIN. COORDINATE TAP WITH CITIZENS (WATER COMPANY). |
| W2 | WATER - PROPOSED 4 INCH PVC C900 FIRE SERVICE LINE. |
| W3 | WATER - PROPOSED 1 INCH DOMESTIC SERVICE TAP ON NEW 4 INCH PRIVATE WATER SERVICE WITH ISOLATION VALVE AND 3/4" METER PIT PER CITIZENS STANDARDS. |
| W5 | WATER - 4 INCH DIAMETER PRIVATE FIRE CONNECTION LINE, PVC C900 OR APPROVED EQUAL, WITH FIRE DEPARTMENT CONNECTION APPURTENANCE. COORDINATE FINAL LOCATION WITH LOCAL FIRE DEPARTMENT. |
| | WATER - FIRE DEPARTMENT CONNECTION WITH 4 INCH FIRE WATERLINE PER LOCAL FIRE DEPARTMENT REQUIREMENTS AND CITIZENS WATER STANDARDS (WATER UTILITY COMPANY). |
| W6 | WATER - ISOLATION VALVE PER CITIZENS WATER STANDARDS. |
| W7 | WATER - POST INDICATOR VALVE. VERIFY TYPE AND FINAL LOCATION WITH GOVERNING WATER COMPANY AND LOCAL FIRE DEPARTMENT. |
| W8 | WATER - EXISTING WATER MAIN TO REMAIN. FIELD LOCATE EXACT LOCATION PRIOR TO CONSTRUCTION. PROTECT THROUGHOUT CONSTRUCTION. |
| W9 | WATER - EXISTING FIRE HYDRANT TO REMAIN. PROTECT THROUGHOUT CONSTRUCTION. |
| UX | UTILITY CROSSING, APPROXIMATE LOCATION SHOWN. CONTRACTOR SHALL FIELD VERIFY EXACT LOCATION OF ALL EXISTING UTILITIES WITHIN AREA OF WORK PRIOR TO CONSTRUCTION. ENGINEER SHALL BE NOTIFIED OF ANY POTENTIAL CONFLICTS FOUND. |



DATE: 3/8/2024
BY: AF
CHECK: AF
DRAWN: KG
PROJECT NO: 2308005
SHEET NAME: INITIAL EROSION CONTROL SWPPP
SHEET NO: C501



KEY NOTES:	
IP	INLET PROTECTION
CE	CONSTRUCTION ENTRANCE
PS	PERMANENT SEEDING
TS	TEMPORARY SEEDING
EB	EROSION CONTROL BLANKET WITH PERMANENT SEEDING
SP	SILT PERIMETER PROTECTION (SILT SOCK)
SF	SILT FENCE
CL	EROSION CONTROL LIMITS
CW	CONCRETE WASHOUT
SUB	PAVEMENT SUBBASE
LA	LANDSCAPE PLANTING AREA SEE SHEET L101 FOR PERMANENT E.C. MEASURE
RP	OUTLET RIP-RAP PROTECTION
CD	ROCK CHECK DAM

THE CONTRACTOR IS RESPONSIBLE FOR ALL INSTALLATION AND MAINTENANCE OF EROSION CONTROL AND STORM WATER POLLUTION PREVENTION FOR THE PROJECT AREA.

NAME: ROB WOODCOCK - MACDOUGAL PIERCE CONSTRUCTION
ADDRESS: 12720 FORD DRIVE, FISHERS, IN
PHONE: 317-596-6731
EMAIL: RWOODCOCK@MACDOUGALPIERCE.COM

LIST OF QUALIFICATIONS:
CONTRACTOR IS TO INFORM MCCORDSVILLE OF WHOM THIS STORMWATER POLLUTION PREVENTION INDIVIDUAL IS AT THE PRE-CONSTRUCTION MEETING, PRIOR TO ANY EARTH DISTURBING & CONSTRUCTION ACTIVITIES.

THE INDIANA STORM WATER QUALITY MANUAL AND MCCORDSVILLE STANDARDS AND DETAILS SHALL BE USED IN CONJUNCTION WITH THIS SET OF EROSION CONTROL PLANS.

EROSION CONTROL NOTES:

- All disturbed areas shall be restored to initial / pre-construction conditions and grades. All flow lines shall be re-established and vegetative cover restored. Contractor may be required to extend vegetative restoration period to warmer months to ensure seed germination.
- All erosion control practices shall be in accordance with the "Indiana Storm Water Quality Manual" and the SCS "Field Office Technical Guide".
- The governing municipality has the right to require additional erosion control measures in the field as conditions warrant.
- The storm water quality unit shown on these plans shall be the unit installed during the development of this property. No substitutions shall be permitted.
- There shall be no dirt, debris, or storage of materials in the street or alleyways.
- Public and private roadways, drives, and parking lots shall be kept cleared of accumulated sediment. Bulk clearing of accumulated sediment shall not include flushing the area with water. Projects subject to IDEM's CSGP shall remove sediment from public rights-of-way not exclusive of construction traffic at the end of each day per the CSGP requirements.
- Stabilization shall be initiated by the end of the seventh (7th) day the area was left idle. Stabilization must be completed within fourteen (14) days after initiation.
- Additional erosion and sediment control measures may be required by the inspector.
- Copies of the letter of intent and response from the governing municipality office for Construction Stormwater General Permit compliance shall be provided onsite, when required.
- All erosion control materials shall be approved by the governing municipality department prior to installation.
- All proposed erosion and sediment control shall be in conformance with the MCCORDSVILLE Stormwater Design and Specifications Manual and Requirements, latest editions. Discrepancies between the plans and the manual shall not alleviate the contractor from adhering to the requirements set forth in the manual.

EROSION CONTROL MAINTENANCE SCHEDULE		
EROSION CONTROL MEASURE	*MAINTENANCE	INSTALLATION SEQUENCE
STONE CONSTRUCTION ENTRANCE	AS NEEDED	PRIOR TO CLEARING AND GRADING
SILT PERIMETER PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
EXISTING INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TREE PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TEMPORARY SEEDING	WATER AS NEEDED	AFTER ROUGH GRADING
PERMANENT SEEDING	WATER AS NEEDED	AFTER FINISH GRADING
EROS CONTROL MATTING / BLANKETS	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING
RIP-RAP PROTECTION	AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING AND STORM SEWER CONSTRUCTION
INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
SEED, SOD & LANDSCAPE AROUND UNITS FINISHED	WATER AS NEEDED	AFTER FINISHED GRADING AROUND FINISHED UNITS
REMOVAL OF INLET PROTECTION	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF SILT PERIMETER	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED

*. SEE CHART, NOTES AND DETAILS FOR MAINTENANCE REQUIREMENTS

**FOR ADDITIONAL EROSION CONTROL INFORMATION AND NOTES, SEE SHEET C504 & C505.



14020 MISSISSINAWA DRIVE
CARMEL, INDIANA 46033
P: 317.324.8695 F: 317.324.8717
www.Fritz-Eng.com

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY

GENERAL NOTES / LEGEND:

"IT'S THE
LAW"
811

Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.

PROJECT:



**GREEN
TOUCH**
MCCORDSVILLE

PROJECT LOCATION:
6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY

SECTION, TOWNSHIP, RANGE:
NE 1/4, S26, T17N, R5E

CLIENT:

**MacDOUGALL PIERCE
CONSTRUCTION**

12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:
3/8/2024



DESIGN: AF CHECK: AF DRAWN: KG

PROJECT NO:
2308005

SHEET NAME:
**INITIAL EROSION
CONTROL SWPPP**

SHEET NO:
C501

DATE: 3/8/2024
BY: AF
PROJECT: 12720 FORD DRIVE, FISHERS, IN 46038
SHEET: C502 OF 502
SCALE: 1" = 20'



0 20' 40'
SCALE: 1" = 20'

KEY NOTES:

IP	INLET PROTECTION	
CE	CONSTRUCTION ENTRANCE	
PS	PERMANENT SEEDING	
TS	TEMPORARY SEEDING	
EB	EROSION CONTROL BLANKET WITH PERMANENT SEEDING	
SP	SILT PERIMETER PROTECTION (SILT SOCK)	
SF	SILT FENCE	
CL	EROSION CONTROL LIMITS	
CW	CONCRETE WASHOUT	
SUB	PAVEMENT SUBBASE	
LA	LANDSCAPE PLANTING AREA SEE SHEET L101 FOR PERMANENT E.C. MEASURE	
RP	OUTLET RIP-RAP PROTECTION	
CD	ROCK CHECK DAM	

THE CONTRACTOR IS RESPONSIBLE FOR ALL INSTALLATION AND MAINTENANCE OF EROSION CONTROL AND STORM WATER POLLUTION PREVENTION FOR THE PROJECT AREA.

NAME: ROB WOODCOCK - MACDOUGAL PIERCE CONSTRUCTION
ADDRESS: 12720 FORD DRIVE, FISHERS, IN
PHONE: 317-596-6731
EMAIL: RWOODCOCK@MACDOUGALPIERCE.COM

LIST OF QUALIFICATIONS:
CONTRACTOR IS TO INFORM MCCORDSVILLE OF WHOM THIS STORMWATER POLLUTION PREVENTION INDIVIDUAL IS AT THE PRE-CONSTRUCTION MEETING, PRIOR TO ANY EARTH DISTURBING & CONSTRUCTION ACTIVITIES.

THE INDIANA STORM WATER QUALITY MANUAL AND MCCORDSVILLE STANDARDS AND DETAILS SHALL BE USED IN CONJUNCTION WITH THIS SET OF EROSION CONTROL PLANS.

EROSION CONTROL NOTES:

- All disturbed areas shall be restored to initial / pre-construction conditions and grades. All flow lines shall be re-established and vegetative cover restored. Contractor may be required to extend vegetative restoration period to warmer months to ensure seed germination.
- All erosion control practices shall be in accordance with the "Indiana Storm Water Quality Manual" and the SCS "Field Office Technical Guide".
- The governing municipality has the right to require additional erosion control measures in the field as conditions warrant.
- The storm water quality unit shown on these plans shall be the unit installed during the development of this property. No substitutions shall be permitted.
- There shall be no dirt, debris, or storage of materials in the street or alleyways.
- Public and private roadways, drives, and parking lots shall be kept cleared of accumulated sediment. Bulk clearing of accumulated sediment shall not include flushing the area with water. Projects subject to IDEM's CSGP shall remove sediment from public rights-of-way not exclusive of construction traffic at the end of each day per the CSGP requirements.
- Stabilization shall be initiated by the end of the seventh (7th) day the area was left idle. Stabilization must be completed within fourteen (14) days after initiation.
- Additional erosion and sediment control measures may be required by the inspector.
- Copies of the letter of intent and response from the governing municipality office for Construction Stormwater General Permit compliance shall be provided onsite, when required.
- All erosion control materials shall be approved by the governing municipality department prior to installation.
- All proposed erosion and sediment control shall be in conformance with the MCCORDSVILLE Stormwater Design and Specifications Manual and Requirements, latest editions. Discrepancies between the plans and the manual shall not alleviate the contractor from adhering to the requirements set forth in the manual.

EROSION CONTROL MAINTENANCE SCHEDULE

EROSION CONTROL MEASURE	*MAINTENANCE	INSTALLATION SEQUENCE
STONE CONSTRUCTION ENTRANCE	AS NEEDED	PRIOR TO CLEARING AND GRADING
SILT PERIMETER PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
EXISTING INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TREE PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TEMPORARY SEEDING	WATER AS NEEDED	AFTER ROUGH GRADING
PERMANENT SEEDING	WATER AS NEEDED	AFTER FINISH GRADING
EROSION CONTROL MATTING / BLANKETS	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING
RIP-RAP PROTECTION	AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING AND STORM SEWER CONSTRUCTION
INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
SEED, SOD & LANDSCAPE AROUND UNITS FINISHED	WATER AS NEEDED	AFTER FINISHED GRADING AROUND FINISHED UNITS
REMOVAL OF INLET PROTECTION	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF SILT PERIMETER	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED

*. SEE CHART, NOTES AND DETAILS FOR MAINTENANCE REQUIREMENTS

**FOR ADDITIONAL EROSION CONTROL INFORMATION AND NOTES, SEE SHEET C504 & C505.

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY

GENERAL NOTES / LEGEND:





Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.


PROJECT LOCATION:
6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY
SECTION, TOWNSHIP, RANGE:
NE 1/4, S26, T17N, R5E

CLIENT:
MacDOUGALL PIERCE CONSTRUCTION
12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:
3/8/2024
DESIGN: AF CHECK: AF DRAWN: KG
PROJECT NO:
2308005
SHEET NAME:
MASS GRADING & CONSTRUCTION SWPPP
SHEET NO.
C502

[illegible]

GENERAL NOTES / LEGEND:



CLIENT: **MacDOUGALL PIERCE
CONSTRUCTION**
12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:			3/8/2024		
DESIGN: AF		CHECK: AF		DRAWN: KG	
PROJECT NO.			2308005		
SHEET NAME			POST CONSTRUCTION SWPPP		
SHEET NO.			C503		

EROSION CONTROL NOTES:

1. All disturbed areas shall be restored to initial / pre-construction conditions and grades. All flow lines shall be re-established and vegetative cover restored. Contractor may be required to extend vegetative restoration period to warmer months to ensure seed germination.
2. All erosion control practices shall be in accordance with the "Indiana Storm Water Quality Manual" and the SCS "Field Office Technical Guide".
3. The governing municipality has the right to require additional erosion control measures in the field as conditions warrant.
4. The storm water quality unit shown on these plans shall be the unit installed during the development of this property. No substitutions shall be permitted.
5. There shall be no dirt, debris, or storage of materials in the street or alleyways.
6. Public and private roads, drives, and parking lots shall be kept cleared of accumulated sediment. Bulk clearing of accumulated sediment shall not include flushing the area with water. Projects subject to IDEM's CSGP shall remove sediment from public rights-of-way not exclusive of construction traffic at the end of each day per the CSGP requirements.
7. Stabilization shall be initiated by the end of the seventh (7th) day the area was left idle. Stabilization must be completed within fourteen (14) days after initiation.
8. Additional erosion and sediment control measures may be required by the inspector.
9. Copies of the letter of intent and response from the governing municipality office for Construction Stormwater General Permit compliance shall be provided onsite, when required.
10. All erosion control materials shall be approved by the governing municipality department prior to installation.
11. All proposed erosion and sediment control shall be in conformance with the MCCORDSVILLE Stormwater Design and Specifications Manual and Requirements, latest editions. Discrepancies between the plans and the manual shall not alleviate the contractor from adhering to the requirements set forth in the manual.

EROSION CONTROL MAINTENANCE SCHEDULE		
EROSION CONTROL MEASURE	*MAINTENANCE	INSTALLATION SEQUENCE
STONE CONSTRUCTION ENTRANCE	AS NEEDED	PRIOR TO CLEARING AND GRADING
SILT PERIMETER PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
EXISTING INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TREE PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TEMPORARY SEEDING	WATER AS NEEDED	AFTER ROUGH GRADING
PERMANENT SEEDING	WATER AS NEEDED	AFTER FINISH GRADING
EROS CONTROL MATTING / BLANKETS	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING
RIP-RAP PROTECTION	AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING AND STORM SEWER CONSTRUCTION
INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
SEED, SOO & LANDSCAPE AROUND	WATER AS NEEDED	AFTER FINISHED GRADING AROUND FINISHED UNITS
UNITS FINISHED		
REMOVAL OF INLET PROTECTION	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF SILT PERIMETER	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED

* - SEE CHART, NOTES AND DETAILS FOR MAINTENANCE REQUIREMENTS


**FOR ADDITIONAL EROSION CONTROL INFORMATION AND NOTES, SEE SHEET C504 & C505.

EROSION CONTROL SEQUENCE & PROCEDURES

*THESE EROSION CONTROL MEASURES, SEQUENCES AND PROCEDURES SHALL APPLY TO ALL PHASES OF THE PROJECT, INCLUDING THE INITIAL / PRE-CONSTRUCTION PHASE, DURING CONSTRUCTION PHASE, AND POST CONSTRUCTION PHASE.

Contractor shall schedule a Pre-Construction Meeting with the TOWN OF MCCORDSVILLE Stormwater Management Department (317) 335-3604 / Local Governing Municipality Stormwater Management Department / County Surveyor's Office / County Soil and Water

- prior to any earth moving activities or construction.
- The following erosion control measures shall be in place prior to any land disturbing activities:
 - Create a stabilized construction entrance.
 - Install Temporary Inlet Protection Measures on existing storm inlets.
 - Install Temporary Silt Fence and/or Silt Sock Protection as shown on approved plans.
 - Install Temporary Construction Washout as required.
 - Install Temporary check dams and sediment basins as required.
- Contractor shall contact the TOWN OF MCCORDSVILLE / Governing Municipality / MS4 / County Soil and Water Department for an initial Erosion Control Inspection to obtain full sign off on the Improvement Location Permit prior to earthwork activities.
- The contractor shall control waste, garbage, debris, wastewater, and other substances on the site so they will not be transported from the site by the action of wind, storm water runoff, or other forces. Proper disposal or management of all wastes and unused building material appropriate to the nature of the waste or material is required.
- Public or private roadways shall be kept clear of accumulated sediment. All sediment that is cleared must be returned to the likely point of origin or other suitable location. Clearing of large amounts of sediment shall not include flushing the area with water.
- Minimize the exposure of bare earth by limiting the work area to that necessary to perform the work, and by proper scheduling of manpower and equipment.
- All erosion and sediment control measures shall be inspected, cleaned, and maintained following each storm event.
- Wherever possible, maintain existing vegetative cover. Use non-vegetative material including mulch, erosion blankets, or stone to control erosion from disturbed areas.
- A log shall be maintained of all inspections (weekly, and following storm events), maintenance and repair of erosion and sediment control measures. The log shall be maintained on site and be available upon request to the owners representatives and the operating authorities having jurisdiction over the site.
- Once land disturbing activities begin, the following practices shall be provided:
 - The Trained Individual responsible for the erosions control maintenance for the contractor shall make weekly site inspections and after every rainfall event of 0.5 inches and greater.
 - Positive drainage shall be maintained at all times. Contractor shall ensure the downstream drainage system and adjacent properties are not receiving sediment/debris laden runoff. If additional measures are necessary to protect adjacent properties or the downstream drainage system, the Contractor shall notify the Engineer and implement the necessary measures immediately.
 - Once earth disturbing activities begin, the adjacent roadways, adjacent drives and parking lots shall be continuously monitored for sediment tracking. If sediment is found, immediate action is required to clean the offsite areas and the current erosion control practices will need to be inspected and modified accordingly to prevent any further sediment from leaving the project site.
 - Once the new storm structures and / or pipes are in place, the appropriate type of inlet protection measures shall be placed.
 - As surface types change, perimeter silt protection may need to be modified or replaced with a different perimeter protection. Update and replace perimeter silt protection as needed and required per these plans and site conditions / restraints.
 - Continued monitoring of all exposed areas shall be performed in order to verify the surrounding areas are not becoming sediment laden from construction activities onsite.
 - As the construction occurs, disturbed areas shall be stabilized as soon as they are at finished grade or will be left bare for more than 15 days.
 - Provide final grade stabilization upon final grading of all areas including erosion control blanketing, seeding and sodding as appropriate.
 - Storm sewers that become silted due to construction activities shall be cleaned with a jet vacuum and the material properly disposed of.
 - As the existing swales and ditches are removed or graded away, the temporary check dams, filter dams, and sediment basins may be removed (unless noted otherwise on the plans) along with their retained debris, pollutants, and sediment. All material shall be disposed of off site at an approved location.
- After site preparation, demolition, clearing and mass earthwork phases are complete and prior to infrastructure, building, and fine grading construction begins:
 - The perimeter erosion control practices (silt fence, construction entrance, check filter dams, temp. sediment basins, etc.) shall be examined, cleaned, and reinstated if damaged. Some practices may need to be relocated or changed for the proposed site layout or per construction phases. (See Erosion Control Plans).
 - Relocate staging area if needed due to site configuration.
 - Install a Temporary Concrete Washout if not done already.
 - Once the new storm structures and / or pipes are in place, the appropriate type of inlet protection measures shall be placed.
 - Continued monitoring of all exposed areas shall be performed in order to verify the surrounding areas are not becoming sediment laden from construction activities onsite.
 - As the construction occurs, disturbed areas shall be stabilized as soon as they are at finished grade or will be left bare for more than 15 days.
 - Provide final grade stabilization upon final grading of all areas including erosion control blanketing, seeding and sodding as appropriate.
 - Storm sewers that become silted due to construction activities shall be cleaned with a jet vacuum and the material properly disposed of.
 - Temporary silt fence to be installed around pond and maintained until open areas contributing to direct sheet flow to pond have been stabilized. Only once these open areas are properly and permanently stabilized can this temporary silt fence be removed and disposed of properly.
 - Minimize erosion from exposed areas by providing and maintaining temporary or permanent stabilization measures. Erosion control measures to protect exposed areas shall be installed at the end of the day's work or within 24 hours of the completion of the earth disturbing activity, as applicable for the type of measure.
 - All disturbed areas shall be seeded and/or stabilized upon completion of the earth disturbing activity.
 - Rip-rap protection for final grades, detention ponds or storm sewers need established upon completion of final grading and storm sewer construction.
- All graded areas (lawns, banks, mounds, etc.) with slopes equal to or steeper than 6h:1v shall be stabilized with an erosion control blanket unless noted otherwise. All constructed swales channels shall be stabilized with an erosion control blanket to the top of the bank. Soil stockpiles shall be seeded and mulched to minimize erosion.
- All other lawn and planting areas shall be seeded and stabilized with an anchored, crimped or tackified mulch and seed mixture.
- Areas to be paved shall be stabilized with a temporary stone cover. The temporary stone stabilization shall be equivalent to the proposed stone sub-base material. Adequate sub-base depths shall be maintained during construction, verified and restored, if necessary, prior to final paving. Stone stabilization shall be installed per the paving specifications and details.
- Install pipe and grate inlet protection measures and pipe outlet protection as new pipes or pipe extensions are installed. Limit excavation to the work that can be performed that day. Trenches shall be seeded and mulched as part of the backfill operation.
- Install inlet protection measures to prevent debris and sediment from entering storm system. Check weekly and after each storm event for debris and sediment. Clear blockages as identified. Damaged or ineffective measures shall be replaced.
- Soil stockpiles shall have appropriate perimeter protection to prevent sedimentation of the surrounding acres. Any stock pile that will not be disturbed for 15 days or longer shall be seeded and protected with mulch or erosion control blanket.
- All disturbed areas where work will potentially cease for 15 days or longer shall be seeded and stabilized immediately upon completion of the activity.
- Erosion and sediment control measures shall be maintained until the site is 95% stabilized.
- Construction Phase BMP's shall remain in place and continue to be inspected until the entire site has reached the minimum vegetative cover, 70% established.
- Once construction is complete and prior to the contractor handing over the project to the owner, the contractor shall clean all debris, pollutants, and sediment from the storm sewers.
- Once construction is complete and prior to the contractor handing over the project to the owner, the contractor shall clean all debris, pollutants, and sediment from the detention pond and remove the outlet structure rock check dam. Contractor to stabilize wet detention ponds (if any) after clean out.
- Upon the site reaching the required minimum established vegetative cover, the IDEM CSGP Notice of Termination shall be submitted to the MS4 Department for approval prior to submitting it to IDEM if required for project.



2/20/2024
Page 1 of 3

Report—RUSLE2 Related Attributes

Soil properties and interpretations for erosion runoff calculations. The surface mineral horizon properties are displayed or the first mineral horizon below an organic surface horizon. Organic horizons are not displayed.

RUSLE2 Related Attributes—Hancock County, Indiana								
Map symbol and soil name	Pct. of map unit	Slope length (ft)	Hydrologic group	Kf	T factor	Representative value		
						% Sand	% Silt	% Clay
Br—Brookston silty clay loam, 0 to 2 percent slopes								
Brookston	95	200	B/D	.28	5	13.0	59.0	28.0
MpC3—Miami complex, 6 to 12 percent slopes, severely eroded								
Miami, severely eroded	55	98	C	.32	2	27.0	44.0	29.0
Miami, shallow, severely eroded	35	98	D	.37	1	27.0	44.0	29.0
YbV—Brookston silty clay loam-Urban land complex, 0 to 2 percent slopes								
Brookston	65	200	B/D	.28	5	13.0	59.0	28.0
YcuA—Crosby silt loam-Urban land complex, 0 to 2 percent slopes								
Crosby	60	249	C/D	.43	3	18.0	64.0	18.0
YmcC3—Miami-Urban land complex, 6 to 12 percent slopes, severely eroded								
Miami, severely eroded	45	98	C	.32	2	27.0	44.0	29.0
Miami, shallow, severely eroded	30	98	D	.37	1	27.0	44.0	29.0

Water Features—Hancock County, Indiana

Report—Water Features

Map unit symbol and soil name	Hydrologic group	Surface runoff	Most likely months	Water table			Ponding			Flooding	
				Upper limit	Lower limit	Kind	Surface depth	Duration	Frequency	Duration	Frequency
Br—Brookston silty clay loam, 0 to 2 percent slopes				ft	ft		ft				
Brookston	B/D	Negligible	Jan-May	0.0-1.0	6.0	Apparent	0.0-0.5	Long (7 to 30 days)	Frequent	—	None
			Jun	4.0-5.0	6.0	Apparent	—	—	—	—	None
			Jul-Oct	—	—	—	—	—	—	—	None
			Nov	4.0-5.0	6.0	Apparent	—	—	—	—	None
			Dec	0.0-1.0	6.0	Apparent	0.0-0.5	Long (7 to 30 days)	Frequent	—	None
MpC3—Miami complex, 6 to 12 percent slopes, severely eroded											
Miami, severely eroded	C	High	Jan-Apr	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
			May-Nov	—	—	—	—	—	None	—	None
			Dec	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
Miami, shallow, severely eroded	D	High	Jan-Apr	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
			May-Nov	—	—	—	—	—	None	—	None
			Dec	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
Map unit symbol and soil name	Hydrologic group	Surface runoff	Most likely months	Water table			Ponding			Flooding	
				Upper limit	Lower limit	Kind	Surface depth	Duration	Frequency	Duration	Frequency
				ft	ft		ft				
YbV—Brookston silty clay loam-Urban land complex, 0 to 2 percent slopes											
Brookston	B/D	Negligible	Jan-May	0.0-1.0	6.0	Apparent	0.0-0.5	Long (7 to 30 days)	Frequent	—	None
			Jun	4.0-5.0	6.0	Apparent	—	—	—	—	None
			Jul-Oct	—	—	—	—	—	—	—	None
			Nov	4.0-5.0	6.0	Apparent	—	—	—	—	None
			Dec	0.0-1.0	6.0	Apparent	0.0-0.5	Long (7 to 30 days)	Frequent	—	None
Urban land		Very high		—	—	—	—	—	—	—	
YcuA—Crosby silt loam-Urban land complex, 0 to 2 percent slopes											
Crosby	C/D	Medium	Jan-Mar	0.5-2.0	2.0-3.5	Perched	—	—	None	—	None
			Apr	0.5-3.0	2.0-3.5	Perched	—	—	None	—	None
			May	1.5-3.0	2.0-3.5	Perched	—	—	None	—	None
			Jun	1.5-3.5	2.0-3.5	Perched	—	—	None	—	None
			Jul-Sep	—	—	—	—	—	None	—	None
			Oct	1.5-3.5	2.0-3.5	Perched	—	—	None	—	None
			Nov	1.5-3.0	2.0-3.5	Perched	—	—	None	—	None
			Dec	0.5-3.0	2.0-3.5	Perched	—	—	None	—	None
Urban land		Very high		—	—	—	—	—	—	—	
Map unit symbol and soil name	Hydrologic group	Surface runoff	Most likely months	Water table			Ponding			Flooding	
				Upper limit	Lower limit	Kind	Surface depth	Duration	Frequency	Duration	Frequency
				ft	ft		ft				
YmcC3—Miami-Urban land complex, 6 to 12 percent slopes, severely eroded											
Miami, severely eroded	C	High	Jan-Apr	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
			May-Nov	—	—	—	—	—	None	—	None
			Dec	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
Miami, shallow, severely eroded	D	High	Jan-Apr	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
			May-Nov	—	—	—	—	—	None	—	None
			Dec	2.0-3.5	2.5-3.5	Perched	—	—	None	—	None
Urban land		Very high		—	—	—	—	—	—	—	

EROSION CONTROL MAINTENANCE SCHEDULE

EROSION CONTROL MEASURE	*MAINTENANCE	INSTALLATION SEQUENCE
STONE CONSTRUCTION ENTRANCE	AS NEEDED	PRIOR TO CLEARING AND GRADING
SILT PERIMETER PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
EXISTING INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TREE PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TEMPORARY SEEDING	WATER AS NEEDED	AFTER ROUGH GRADING
PERMANENT SEEDING	WATER AS NEEDED	AFTER FINISH GRADING
EROSION CONTROL MATTING / BLANKETS	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING
RIP-RAP PROTECTION	AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING AND STORM SEWER CONSTRUCTION
INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
SEED, SOD & LANDSCAPE AROUND	WATER AS NEEDED	AFTER FINISHED GRADING AROUND FINISHED UNITS
UNITS FINISHED		
REMOVAL OF INLET PROTECTION	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF SILT PERIMETER	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED

*. SEE CHART, NOTES AND DETAILS FOR MAINTENANCE REQUIREMENTS

THE CONTRACTOR IS RESPONSIBLE FOR ALL INSTALLATION AND MAINTENANCE OF EROSION CONTROL AND STORM WATER POLLUTION PREVENTION FOR THE PROJECT AREA.

NAME: ROB WOODCOCK - MACDOUGAL PIERCE CONSTRUCTION
ADDRESS: 12720 FORD DRIVE, FISHERS, IN
PHONE: 317-596-6731
EMAIL: RWOODCOCK@MACDOUGALPIERCE.COM

LIST OF QUALIFICATIONS:
CONTRACTOR IS TO INFORM MCCORDSVILLE OF WHOM THIS STORMWATER POLLUTION PREVENTION INDIVIDUAL IS AT THE PRE-CONSTRUCTION MEETING, PRIOR TO ANY EARTH DISTURBING & CONSTRUCTION ACTIVITIES.

THE INDIANA STORM WATER QUALITY MANUAL AND MCCORDSVILLE STANDARDS AND DETAILS SHALL BE USED IN CONJUNCTION WITH THIS SET OF EROSION CONTROL PLANS.




14020 MISSISSINAWA DRIVE
CARMEL, INDIANA 46033
P: 317.324.8695 F: 317.324.8717
www.Fritz-Eng.com

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND ISSUES	DATE	BY

GENERAL NOTES / LEGEND:



"IT'S THE
LAW"
811
Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG.

PROJECT:



6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY

SECTION, TOWNSHIP, RANGE:
NE 1/4, S26, T17N, R5E

CLIENT:

MacDOUGALL PIERCE
CONSTRUCTION

12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:
3/8/2024

DESIGN: AF CHECK: AF DRAWN: KG

PROJECT NO:
2308005

SHEET NAME:
SWPPP SEQUENCING
& SOILS INFORMATION

SHEET NO:
C504

DATE: 3/8/2024 10:42 AM
FILE NAME: C:\Users\jmac\OneDrive\Documents\2024\2308005\2308005 SWPPP SEQUENCING & SOILS INFORMATION.dwg

© 2024 FRITZ ENGINEERING SERVICES, LLC

CONSTRUCTION STORMWATER GENERAL PERMIT (CSGP) REPORT STORMWATER POLLUTION PREVENTION PLAN (SWP3 OR SWPPP)

SECTION A - CONSTRUCTION PLAN ELEMENTS

- A1** PLAN INDEX:
C501 - INITIAL CONTROLS SWPPP
C502 - MASS GRADING & CONSTRUCTION SWPPP
C503 - POST CONSTRUCTION SWPPP
C504 - SWPPP SEQUENCE AND SOIL INFORMATION
C505 - SWPPP - CSGP REPORT & SPILL PREVENTION
C506 - EROSION CONTROL DETAILS

A2 VICINITY MAP: SEE COVER SHEET C100

A3 PROJECT NARRATIVE: THE OVERALL PROJECT PROPERTY IS 2.4 ACRES IN SIZE. THE PROJECT CONSISTS OF THE PROJECT DISTURBANCE IS 1.5 ACRES. A PROPOSED 2-STORY BUSINESS USE BUILDING WILL BE CONSTRUCTED ALONG WITH AN ASPHALT PARKING LOT, STORMWATER DETENTION POND, AND ASSOCIATED INFRASTRUCTURE.

A4 SITE LOCATION COORDINATES:
LAT: 39°53'41" N
LONG: 85°55'26" W

A5 LEGAL DESCRIPTION: PART OF NE ¼ OF SECTION 26 - TOWNSHIP 17N - RANGE 5E, VERNON TOWNSHIP, HANCOCK COUNTY, INDIANA. FOR FULL LAND DESCRIPTION SEE SURVEY SHEETS LOCATED AT THE BEGINNING OF THIS PLAN SET.

A6 LOCATION OF ALL SITE IMPROVEMENTS: SEE SITE PLAN ON SHEET C201.

A7 HYDROLOGIC UNIT CODE (14 DIGIT) - 05120201100140 ("NAME" WATERSHED)

SEE FIRM MAP PANEL ON PLAN SHEET C101 FOR BOUNDARIES OF THE 100-YEAR FLOODPLAINS, FLOODWAY FRINGES, AND FLOODWAYS (IF ANY). FOR THIS PROJECT, SITE, THEIR ARE NO 100-YEAR FLOODPLAINS OR FLOODWAYS. THE PROJECT SITE IS LOCATED WITHIN THE FEMA COMMUNITY PANEL MAP NO. 18069C00180 WITH AN EFFECTIVE DATED OF 12/24/2007. REVIEW OF THE MAP INDICATES THE SITE IS LOCATED WITHIN THE FLOOD DESIGNATION "ZONE X" (UNSHADED), 'AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN". THE FEMA MAP IS INCLUDED IN ON SHEET C101.

A8 ADJACENT LAND USES:
NORTH: PUD ZONING
SOUTH: PUD ZONING
WEST: PUD ZONING
EAST: PUD ZONING

A9 IDENTIFICATION OF A U.S. EPA APPROVED OR ESTABLISHED TMDL, INCLUDING THE NAME OF THE TMDL AND THE POLLUTANT(S) FOR WHICH THERE IS A TMDL:
THE SITE IS LOCATED WITHIN THE "THORPE CREEK-GEIST RESERVOIR" WATERSHED AS LOCATED IN CENTRAL INDIANA. DRAINING APPROXIMATELY 22,170 ACRES IN HANCOCK COUNTY, INCLUDED IN THIS WATERSHED ARE 12 WATERBODIES, INCLUDING DRY BRANCH WHICH IS LOCATED JUST WEST OF THIS PROJECT PROPERTY AND WHERE ULTIMATELY THE STORMWATER FOR THIS PROJECT DISCHARGES. PER THE TMDL AND ASSESSMENT INFORMATION, THIS WATERCOURSE IS RATED "GOOD".

ALL INFORMATION OBTAINED FROM:
IDEM WEBSITE "https://www.in.gov/idem/nps/resources/total-maximum-daily-load-reports/"
AND / OR
THE FEDERAL EPA WEBSITE "https://mywaterway.epa.gov/"

A10 SPECIFIC POINTS WHERE STORMWATER DISCHARGE LEAVES SITE, OWNERSHIP/TYPE OF STORMWATER CONVEYANCE SYSTEM AND ITS ULTIMATE RECEIVING WATERS:

THE PROJECT AREAS DRAIN EASTERLY TOWARDS AN ONSITE DETENTION FACILITY. THE DETENTION BASIN WILL OUTLET TO STANSBURY CREEK ALONG THE EAST SIDE OF THE PROJECT SITE.

A11 IDENTIFICATION OF DISCHARGES TO A WATER ON THE CURRENT 303D LIST OF IMPAIRED WATERS AND THE POLLUTANT(S) FOR WHICH IT IS IMPAIRED:
THIS PROJECT DOES NOT DIRECTLY DISCHARGE INTO DRY RUN, WHICH IS LISTED AS "GOOD" PER THE EPA WEBSITE: "https://mywaterway.epa.gov/".

A12 SOIL MAP OF THE PREDOMINANT SOIL TYPES THAT INCLUDES SOIL PROPERTIES, CHARACTERISTICS, LIMITATIONS, AND HAZARDS ASSOCIATED WITH THE PROJECT SITE AND THE MEASURES THAT WILL BE INTEGRATED INTO THE PROJECT TO OVERCOME OR MINIMIZE ADVERSE SOIL CONDITIONS: SEE SOIL MAP AND SOIL DESCRIPTIONS ON SHEET C504.

A13 LOCATION AND NAME OF WETLANDS, LAKES AND WATER COURSES ON AND ADJACENT TO SITE: NONE

A14 NOTATION OF ANY STATE OR FEDERAL WATER QUALITY PERMITS:
401 WATER QUALITY CERTIFICATION (IDEM): NONE
SECTION 404 PERMIT (USACE): NONE
CONSTRUCTION IN A FLOODWAY (INDNR): NONE
GENERAL PERMIT RULE FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY (CSGP): TO BE APPLIED FOR

A15 IDENTIFICATION AND DELINEATION OF NATURAL BUFFERS AND EXISTING VEGETATIVE COVER, SUCH AS CROP OR CROP RESIDUE, GRASS, WEEDS, BRUSH, AND TREES:
EXISTING SITE CONDITIONS INCLUDE GRASS COVER ASSOCIATED WITH A COMMERCIAL OUTLOT. NO OTHER COVER TYPES.

A16 FOR EXISTING TOPOGRAPHY: SEE SURVEYS AND EXISTING CONDITIONS PLAN SHEET C102

A17 LOCATION(S) OF WHERE RUN-OFF ENTERS THE PROJECT SITE: ADJACENT ROADSIDE RUNOFF SHEET DRAINS ONTO THE PROJECT SITE, ACROSS THE PROJECT SITE AND INTO STANSBURY CREEK ALONG THE EAST SIDE OF THE SITE.

A18 LOCATION(S) OF WHERE RUN-OFF DISCHARGES FROM THE PROJECT SITE PRIOR TO CONSTRUCTION:

THE PROJECT AREA GENERALLY SHEET DRAINS FROM WEST TO EAST AND INTO STANSBURY CREEK ALONG THE EAST SIDE OF THE SITE.

A19 LOCATION OF ALL EXISTING STRUCTURES ON THE PROJECT SITE: SEE SURVEY SHEETS AND C102.

A20 EXISTING PERMANENT RETENTION OR DETENTION FACILITIES, INCLUDING MANMADE WETLANDS, DESIGNED FOR THE PURPOSE OF STORMWATER MANAGEMENT:

THE DISTURBED PROJECT AREAS DRAIN EASTERLY TO AN ONSITE DETENTION FACILITY. THE DETENTION BASIN WILL OUTLET TO STANSBURY CREEK ALONG THE EAST SIDE OF THE PROJECT SITE.

A21 LOCATIONS WHERE STORMWATER MAY BE DIRECTLY DISCHARGED INTO GROUND WATER, SUCH AS ABANDONED WELLS, SINKHOLES, OR KARST FEATURES: NONE FOR THIS PROJECT

A22 SIZE OF THE PROJECT PROPERTY AREA: TOTAL AREA = 2.4 ACRES

A23 TOTAL EXPECTED LAND DISTURBANCE: DISTURBED AREA = 1.5 ACRES

A24 PROPOSED FINAL TOPOGRAPHY: SEE GRADING PLAN SHEET C301.

A25 FOR DELINEATION OF ALL PROPOSED LAND-DISTURBING ACTIVITIES, INCLUDING KNOWN OFF-SITE ACTIVITIES THAT WILL PROVIDE SERVICES TO THE PROJECT SITE, SEE PLAN SHEETS C201, C301, C401, AND C501-C503.

A26 FOR LOCATION, SIZE, AND DIMENSIONS OF ALL STORMWATER DRAINAGE SYSTEMS, SUCH AS CULVERTS, STORM SEWERS, AND CONVEYANCE CHANNELS SEE PLAN SHEETS C102, AND C401

A27 LOCATIONS OF SPECIFIC POINTS WHERE STORMWATER AND NON-STORMWATER DISCHARGES WILL LEAVE THE PROJECT SITE: SEE PLAN SHEETS C102, C104 AND C401-C402.

THE DISTURBED PROJECT AREAS DRAIN EASTERLY TO AN ONSITE DETENTION FACILITY. THE DETENTION BASIN WILL OUTLET TO STANSBURY CREEK ALONG THE EAST SIDE OF THE PROJECT SITE.

A28 LOCATION OF ALL PROPOSED SITE IMPROVEMENTS, INCLUDING ROADS, UTILITIES, LOT DELINEATION AND IDENTIFICATION, PROPOSED STRUCTURES, AND COMMON AREAS: SEE SHEETS C301, C301, AND C401.

A29 LOCATION OF ALL ON-SITE SOIL STOCKPILES AND BORROW AREAS AND, WHEN KNOWN AT THE TIME OF SUBMITTAL, THE LOCATION OF ALL OFF-SITE BORROW, SOIL STOCKPILES, AND DISPOSAL AREAS: NONE ANTICIPATED AT THIS TIME.

A30 CONSTRUCTION SUPPORT ACTIVITIES THAT ARE EXPECTED TO BE PART OF THE PROJECT (E.G., STAGING AREAS, DISPOSAL SITES, ETC.): SEE SHEETS C501 & C502 AS APPLICABLE.

A31 LOCATION OF ANY IN-STREAM ACTIVITIES THAT ARE PLANNED FOR THE PROJECT INCLUDING, BUT NOT LIMITED TO STREAM CROSSINGS AND PUMP AROUND: N

SECTION B - EROSION AND SEDIMENT CONTROL/PROJECT SITE MANAGEMENT

B1 DESCRIPTION OF THE POTENTIAL POLLUTANT GENERATING SOURCES AND POLLUTANTS:
POTENTIAL POLLUTANTS FROM CONSTRUCTION ACTIVITY SUCH AS OIL, GREASE, ANTIFREEZE, GASOLINE AND DIESEL FUEL FROM CONSTRUCTION EQUIPMENT; SOIL EROSION FROM CONSTRUCTION ACTIVITIES; FERTILIZER AND PESTICIDES FROM LANDSCAPING.

B2 CONSTRUCTION ENTRANCE: SEE STORMWATER POLLUTION PREVENTION PLAN SHEET C501 & C502 FOR LOCATION AND SHEET C506 FOR CONSTRUCTION ENTRANCE DETAILS AND SPECIFICATIONS.

B3 SPECIFICATIONS FOR TEMPORARY AND PERMANENT STABILIZATION: SEE PLAN SHEETS C502-C503, ALONG WITH SHEET C506, FOR SPECIFIC INFORMATION, LAYOUTS, NOTES AND DETAILS. THE PERMANENT STABILIZATION IS PERMANENT SEEDED OVER ALL DISTURBED AREAS WITH SELECTED AREAS AS DENOTED ON SHEETS C503 WITH EROSION CONTROL BLANKETS. EROSION CONTROL BLANKET DETAILS ARE LOCATED ON SHEET C506.

B4 SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS:
AFTER CONSTRUCTION OF THE STORM SEWERS, IMMEDIATELY OUTLET RIP-RAP PROTECTION (SEE SHEET C503) WILL BE INSTALLED. A ROCK CHECK DAM WILL BE INSTALLED FOR THE SWALE AS SHOWN ON SHEET C502.

FOR RIP-RAP OUTLET PROTECTION DETAILS AND SPECIFICATIONS SHEET SHEET C503 / C506NONE FOR THIS PROJECT.

B5 SEDIMENT CONTROL PLAN FOR SHEET FLOW AREAS: SEE STORMWATER POLLUTION PREVENTION PLAN SHEETS C501 & C502. DURING CONSTRUCTION SEDIMENT AND POLLUTION CONTROL WILL BE HANDLED BY EROSION CONTROL SILT FENCES AND SILT SOCKS AS LOCATED AROUND THE PROJECT DISTURBED AREAS. FOR SILT FENCE AND SILT SOCK DETAILS AND SPECIFICATIONS SHEET SHEET C506.

AFTER CONSTRUCTION, PERMANENT SEEDING WITH EROSION CONTROL BLANKETS (AS REQUIRED) WILL BE INSTALLED FOR POST CONSTRUCTION SHEET FLOW SEDIMENT CONTROL. FOR PERMANENT SEEDING SCHEDULE SEE SHEET C506.

B6 RUNOFF CONTROL MEASURES: SEE STORMWATER POLLUTION PREVENTION PLAN SHEETS C501-C502. SEE STORMWATER POLLUTION PREVENTION PLAN SHEETS C502 AND C503. AS SOON AS THE STORM SEWER OUTLET PIPE WITH END SECTION IS INSTALLED, THE CONTRACTOR SHALL IMMEDIATELY INSTALL THE RIP-RAP OUTLET PROTECTION FOR THIS PROJECT. FOR RIP-RAP PROTECTION DETAILS SEE SHEET C506

B7 STORM WATER OUTLET PROTECTION SPECIFICATIONS:

-EXAMPLE-
THERE ARE NO DIRECT OUTLETS FOR THE STORM WATER CONVEYANCE SYSTEMS AS THEY DIRECTLY CONNECT INTO AN EXISTING STORM SEWER MASTER PLAN TRUNK LINE.

-EXAMPLE 2 -
SEE STORMWATER POLLUTION PREVENTION PLAN SHEETS C502-C503. THIS PROJECT HAS 1 OUTLET POINTS FOR THE ONSITE STORM SEWER SYSTEMS THAT DRAIN INTO THE ONSITE DETENTION FACILITY. AFTER CONSTRUCTION OF THE STORM SEWER(S), IMMEDIATELY OUTLET RIP-RAP PROTECTION (SEE SHEET C502 & C503) WILL BE INSTALLED. FOR RIP-RAP OUTLET PROTECTION DETAILS AND SPECIFICATIONS SEE SHEET SHEET(S) C506.

B8 GRADE STABILIZATION STRUCTURE LOCATIONS AND SPECIFICATIONS: THIS PROJECT DOES NOT REQUIRE ANY SITE SPECIFIC GRADE STABILIZATION STRUCTURES.

B9 DEWATERING APPLICATIONS AND MANAGEMENT METHODS (BASIN OUTLET MEASURES, FLOCCULANTS ETC.): SEE SHEETS C901 FOR DEWATERING INFORMATION.

B10 MEASURES UTILIZED FOR WORK WITHIN WATERBODIES (CROSSINGS, COFFER DAMS, ETC.): NONE FOR THIS PROJECT (NOT APPLICABLE).

B11 MONITORING AND MAINTENANCE GUIDELINES FOR POLLUTION PREVENTION MEASURES:

- SILT FENCE / SILT SOCK (PERIMETER PROTECTION MEASURES) MAINTENANCE REQUIREMENTS**
1. INSPECT THE SILT PERIMETER PROTECTION PERIODICALLY AND AFTER EACH STORM EVENT.
 2. IF FENCE FABRIC OR SILT SOCKS TEAR, STARTS TO DECOMPOSE OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY.
 3. REMOVE DEPOSITED SEDIMENT WHEN IT REACHES HALF THE HEIGHT OF THE FENCE OR SILT SOCK AT ITS LOWEST POINT OR IS CAUSING THE FABRIC TO BULGE.
 4. TAKE CARE TO AVOID UNDERMINING THE FENCE OR SILT SOCK DURING CLEAN OUT.
 5. AFTER EACH CONSTRUCTION PHASE, REMOVE THE SEDIMENT AND SILT PERIMETER PROTECTION AND SEDIMENT DEPOSITS, BRING THE DISTURBED AREA TO GRADE AND STABILIZE IT.

TEMPORARY GRAVEL/STONE CONSTRUCTION MAINTENANCE REQUIREMENTS

1. INSPECT ENTRANCE PAD AND SEDIMENT DISPOSAL AREA WEEKLY AND AFTER STORM EVENTS OR HEAVY USE.
2. RESHAPE AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
3. TOP-DRESS WITH CLEAN STONE AS NEEDED.
4. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO STREETS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED IF THE WATER IS CONVEYED INTO A SEDIMENT TRAP OR BASIN.
5. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.

TEMPORARY CONSTRUCTION ENTRANCE (IN LEAU OF GRAVEL / STONE ENTRANCE) MAINTENANCE REQUIREMENTS

1. INSPECT ENTRANCE DAILY AND STREET / PAVEMENT SWEEP CLEAN DAILY AT THE END OF EACH CONSTRUCTION WORK DAY.
2. RESHAPE AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
3. ADJACENT ROADWAY, DRIVES, PARKING LOTS, (HARDSCAPES) CLEAN THROUGHOUT THE WORK CYCLE.
4. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.

INLET PROTECTION MAINTENANCE REQUIREMENTS

1. AFTER EACH STORM EVENT REMOVE THE SEDIMENT AND REPLACE THE GEOTEXTILE FABRIC IF USED.
2. PERIODICALLY REMOVE SEDIMENT AND TRACKED-ON SOIL FROM THE STREET, WITHOUT FLUSHING, TO REDUCE THE THE SEDIMENT LOAD ON THE INLET PROTECTION.
3. INSPECT CASTING COVER PERIODICALLY FOR DAMAGE AND REPAIR. KEEP GRATES FREE OF DEBRIS.
4. AFTER THE CONSTRUCTION IS COMPLETED, REMOVE THE SEDIMENT DEPOSITS AND DISPOSE OF THEM PROPERLY. REMOVE THE INLET PROTECTION DEVICES AND DISPOSE OF THEM PROPERLY PER LOCAL AND STATE REQUIREMENTS.

CONCRETE WASHOUT MAINTENANCE REQUIREMENTS

1. WASHOUTS SHOULD BE INSPECTED DAILY AND AFTER EACH STORM EVENT TO CHECK FOR LEAKS OR DAMAGE.
2. WHEN THE WASHOUT CONTAINER IS FILLED TO OVER 75 PERCENT OF ITS CAPACITY, THE WASHWATER SHOULD BE VACUUMED OFF OR ALLOWED TO EVAPORATE TO AVOID OVERFLOWS. THEN WHEN THE REMAINING CEMENTITIOUS SOLIDS HAVE HARDENED, THEY SHOULD BE REMOVED AND RECYCLED.
3. DAMAGES TO THE WASHOUT / CONTAINER SHOULD BE REPAIRED IMMEDIATELY.
4. BEFORE HEAVY RAINS, THE WASHOUT CONTAINERS LIQUID LEVEL SHOULD BE LOWERED OR THE CONTAINER SHOULD BE COVERED TO AVOID AN OVERFLOW DURING THE RAIN STORM.
5. ALL WASHWATER, CONCRETE, DEBRIS, ETC. SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL LAWS AND REGULATIONS.

TEMPORARY SEDIMENT TRAP / ROCK CHECK DAMS MAINTENANCE REQUIREMENTS

1. INSPECT TEMPORARY SEDIMENT TRAPS AND ROCK CHECK DAMS AFTER EACH STORM EVENT AND IMMEDIATELY REPAIR ANY EROSION AND PUNCTURES.
2. REMOVE SEDIMENT WHEN IT HAS ACCUMULATED TO WITHIN 6" OF CASTING (IF APPLICABLE).
3. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, REMOVE THE STRUCTURE AND SEDIMENT. SMOOTH THE SITE TO BLEND WITH ADJOINING AREAS AND STABILIZE IT.

RIPRAP OUTLET MAINTENANCE REQUIREMENTS

1. INSPECT AFTER EACH STORM EVENT AND IMMEDIATELY REPAIR ANY EROSION. REPLACE RIP-RAP ROCK AS REQUIRED.
2. REMOVE SEDIMENT AND DEBRIS WHEN IT HAS ACCUMULATED TO WITHIN 3 INCHES OF ADJACENT STORM PIPE (IF APPLICABLE).

EROSION CONTROL BLANKET MAINTENANCE REQUIREMENTS

1. DURING VEGETATIVE ESTABLISHMENT, INSPECT AFTER EACH STORM EVENT FOR ANY EROSION BELOW THE BLANKET.
2. IF ANY AREA(S) SHOW EROSION, PULL BACK THAT PORTION OF THE BLANKET COVERING IT, RE-SEED THE AREA AND RELAY AND STRALE THE BLANKET.
3. AFTER VEGETATIVE ESTABLISHMENT CHECK THE TREATED AREA PERIODICALLY.

B12 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION RELATIVE TO LAND DISTURBING ACTIVITIES: SEE SHEET C504 FOR CONSTRUCTION SEQUENCING.

B13 EROSION & SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS: THERE ARE NO INDIVIDUAL BUILDING LOTS ASSOCIATED WITH THIS PROJECT.

B14 MATERIAL HANDLING AND SPILL PREVENTION PLAN: LOCATED ON THIS SHEET TO THE RIGHT.

B15 MATERIAL HANDLING AND STORAGE PROCEDURES ASSOCIATED WITH CONSTRUCTION ACTIVITY DESCRIBING THE MANAGEMENT AND DISPOSAL OF CONSTRUCTION PRODUCTS AND WASTE, INCLUDING CONCRETE AND CEMENTATION WASHOUT AREAS AND MANAGEMENT MEASURES. SEE "MATERIAL HANDLING AND SPILL PREVENTION PLAN" AS LOCATED ON THIS SHEET TO THE RIGHT.

SECTION C - STORMWATER POLLUTION PREVENTION PLAN - POST-CONSTRUCTION PHASE

DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED WITH THE PROPOSED LAND USE: SILT AND SEDIMENT FROM EXPOSED SOILS, LEAVES, MULCH, VEHICULAR SOURCES SUCH AS LEAKING FUEL, OR OIL, BRAKE FLUID, BRAKE DUST, GREASE, ANTIFREEZE, METALS, RUBBER FRAGMENTS, ROAD GRIT, SALTS AND SANDS, CONSTRUCTION TRASH AND DEBRIS, FERTILIZERS, CLEANING AGENTS, CHEMICALS, PAINT, ANIMAL WASTE, ELEVATED STORM RUNOFF TEMPERATURES, PESTICIDES AND PATHOGENS.

C2 DESCRIPTION OF PROPOSED POST CONSTRUCTION STORMWATER QUALITY MEASURES:

1. PERMANENT SEEDING AND LANDSCAPE PLANT MATERIAL.
2. ON GOING MAINTENANCE BY THE OWNER TO INSURE THAT SEDIMENT, TRASH AND POLLUTANTS DO NOT LEAVE THE SITE.
3. PROJECT AREA DRAINS INTO STORM SEWER TRUNK LINES THAT HAVE ONSITE WET DETENTION POND FACILITIES THAT WILL TREAT THE STORM WATER ASSOCIATED WITH THESE DISTURBANCE AREAS.

C3 LOCATION, DIMENSIONS, SPECIFICATIONS, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURES: SEE STORMWATER POLLUTION PREVENTION PLAN SHEETS C501-C503 FOR LOCATIONS AND SHEETS C506 FOR DETAILS AND SPECIFICATIONS.

C4 SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION:

1. INSPECT AND MAINTAIN ALL EROSION CONTROL MEASURES AS DETAILED IN THE STORMWATER POLLUTION PREVENTION MEASURES MAINTENANCE REQUIREMENTS BEGINNING IMMEDIATELY AFTER INSTALLATION AND CONTINUING UNTIL VEGETATION HAS BEEN SUFFICIENTLY ESTABLISHED AND ALL CONSTRUCTION ACTIVITY IS COMPLETE.
2. REMOVE ALL SILT FENCES, SILT SOCKS, INLET PROTECTION, CHECK DAMS, SEDIMENT TRAPS, ETC. ONLY AFTER SEEDING AND SUFFICIENT VEGETATIVE GROWTH HAS BEEN ESTABLISHED AND WATER QUALITY DEVICES HAVE BEEN IMPLEMENTED AND / OR INSTALLED (IF APPLICABLE TO THE PROJECT) IN EACH AREA TO A POINT WHERE SEDIMENT AND POLLUTANTS WILL NOT LEAVE THE SITE OR DRAIN INTO ANY ADJACENT WATERBODIES OR WATERCOURSES.
3. INSPECTION AND MAINTENANCE OF ALL AREAS IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ACCEPTED BY THE GOVERNING MS4 OFFICE. INSPECTION AND MAINTENANCE OF BMP'S SHALL FOLLOW TIME TABLES SET FORTH IN THE MAINTENANCE AND OPERATIONS MANUAL.

C5 DESCRIPTION OF MAINTENANCE GUIDELINES FOR POST CONSTRUCTION STORMWATER QUALITY MEASURE:
THE PROJECT SITE HAS BEEN DESIGNED TO MINIMIZE IMPERVIOUS SURFACES AND MAXIMIZE VEGETATIVE COVER. OWNER SHALL INSPECT VEGETATIVE COVER FOR HEALTH AND PROVIDE FERTILIZER AND/OR WATER AS NEEDED TO MAINTAIN AT LEAST 75% GRASS COVERAGE. IN LANDSCAPE BEDS TREES AND SHRUBS SHALL BE INSPECTED FOR HEALTH AND KEPT FREE OF TRASH. THE ONSITE DETENTION AND WATER QUALITY FACILITIES ARE MAINTAINED BY THE OWNER OF GREEN TOUCH SERVICES.

C6 ENTITY THAT WILL BE RESPONSIBLE FOR OPERATION AND MAINTENANCE OF THE POST-CONSTRUCTION SYSTEM FOR THIS PROJECT SITE:

OWNER CONTACT INFORMATION: GREEN TOUCH SERVICES, 6314 W BROADWAY, MCCORDSVILLE, IN 46055

MATERIAL HANDLING AND SPILL PREVENTION & RESPONSE PLAN (CSGP ITEM "B14" & "B15")

PURPOSE

The intention of this spill prevention, control and countermeasures (SPCC) is to establish the procedures and equipment required to prevent the discharge of oil and hazardous substances in quantities that violate applicable water quality standards, cause a sheen upon or discoloration of the surface of adjacent waterways / watercourses / waterbodies and navigable waters or adjoining shorelines, or cause sludge or emulsion to be deposited beneath the surface of the water or adjoining shorelines. The plan also establishes the activities required to mitigate such discharges (i.e., countermeasures) should they occur.

Definitions:

Pollutant: Means pollutant of any kind or in any form, including but not limited to sediment, paint, cleaning agents, concrete washout, pesticides, nutrients, trash, hydraulic fluids, fuel, oil, petroleum, fuel oil, sludge, oil refuse, and oil mixed with wastes other than dredged soil.

Discharge:

Includes but is not limited to, any spilling, leaking, pumping, pouring, emitting, emptying, or dumping.

Navigable waters:

Means all waters of the United States that are connected with a navigable stream, lake, or sea. [Note: This definition is usually interpreted to mean any wastewater (even normally dry wash or storm sewer) that eventually drains into a navigable stream].

Plan review and amendments:

This plan shall be reviewed and/or amended, if necessary, whenever there is a change in the design of the site, construction, operation, or maintenance which materially affects the sites' potential for the discharge of regulated material.

PREDICTION OF POTENTIAL SPILLS

1. Nearest navigable water: White River
2. Possible spill sources (during and post construction): Vehicular sources such as leaking fuel or oil, brake fluid, grease, antifreeze, construction trash and debris, biological agents found in trash and debris, fertilizers, household items including but not limited to cleaning agents, chemicals, paint, herbicides and pesticides.
3. Groundwater contamination: This facility maintains no above ground or under ground storage tanks. therefore, it is felt that there is little or no possibility of post construction groundwater contamination.

VEHICLE AND EQUIPMENT MAINTENANCE

DESCRIPTION AND PURPOSE

Prevent or reduce the contamination of stormwater resulting from vehicle and equipment maintenance by running a "dry and clean site". The best option would be to perform maintenance activities at an offsite facility. If this option is not available then work should be performed in designated areas only, while providing cover for materials stored outside, checking for leaks and spills, and containing and cleaning up spills immediately.

SUITABLE APPLICATIONS

These procedures are suitable on all construction projects where on site yard area is necessary for storage and maintenance of heavy equipment and vehicles.

LIMITATIONS

Onsite vehicle and equipment maintenance should only be used where it is impractical to send vehicles and equipment offsite for maintenance and repair. Sending vehicles/equipment offsite should be done in conjunction with a stabilized construction entrance / exit. Outdoor vehicle or equipment maintenance is a potentially significant source of stormwater pollution. Activities that can contaminate stormwater include engine repair and service, changing or replacement of fluids, and outdoor equipment storage and parking (engine fluid leaks).

IMPLEMENTATION

- If maintenance must occur onsite, use designated areas, located away from drainage courses. Dedicated maintenance areas should be protected from stormwater runoff and runoff, and should be located at least 50 feet from downstream drainage facilities and watercourses.
- Drip pans or absorbent pads should be used during vehicle and equipment maintenance work that involves fluids, unless the maintenance work is performed over an impermeable surface in a dedicated maintenance area.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- All fueling trucks and fueling areas are required to have spill kits and/or use other spill protection devices.
- Use absorbent materials on small spills. Remove the absorbent materials promptly and dispose of properly.
- Inspect onsite vehicles and equipment daily at startup for leaks, and repair immediately. Keep vehicles and equipment clean; do not allow excessive build-up of oil and grease.
- Segregate and recycle wastes, such as greases, used oil or oil filters, antifreeze, cleaning solutions, automotive batteries, hydraulic and transmission fluids. Provide secondary containment and covers for these materials if stored onsite.
- Train employees and subcontractors in proper maintenance and spill cleanup procedures.
- Drip pans or plastic sheeting should be placed under all vehicles and equipment placed on docks, barges, or other structures over water bodies when the vehicle or equipment is planned to be idle for more than 1 hour. Properly dispose of used oils, fluids, lubricants, and spill cleanup materials. Do not place used oil in a dumpster or pour into a storm drain or watercourse. Properly dispose of or recycle used batteries. Do not bury used tires. Repair leaks of fluids and oil immediately.
- Listed below is further information if you must perform vehicle or equipment maintenance onsite.

INSPECTION AND MAINTENANCE

- Inspect and verify that BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly to verify continued BMP implementation.
- Keep ample supplies of spill cleanup materials onsite. Maintain waste fluid containers in leak proof condition.
- Vehicles and equipment should be inspected on each day of use. Leaks should be repaired immediately or the problem vehicle(s) or equipment should be removed from the project site. Inspect equipment for damaged hoses and leaky gaskets routinely. Repair or replace as needed.

VEHICLE AND EQUIPMENT FUELING

DESCRIPTION AND PURPOSE

Vehicle equipment fueling procedures and practices are designed to prevent fuel spills and leaks, and reduce or eliminate contamination of stormwater. This can be accomplished by using offsite facilities, fueling in designated areas only, enclosing or covering stored fuel, implementing spill controls, and training employees and subcontractors in proper fueling procedures.

LIMITATIONS

Onsite vehicle and equipment fueling should only be used where it is impractical to send vehicles and equipment offsite for fueling. Sending vehicles and equipment offsite should be done in conjunction with a stabilized construction entrance / exit.

IMPLEMENTATION

- Use offsite fueling stations as much as possible. These businesses are better equipped to handle fuel and spills properly. Performing this work offsite can also be economical by eliminating the need for a separate fueling area at a site.
- Discourage "topping-off" of fuel tanks.
- Absorbent spill cleanup materials and spill kits should be available in fueling areas and on fueling trucks, and should be disposed of properly after use.
- Drip pans or absorbent pools should be used during vehicle and equipment fueling, unless the fueling is performed over an impermeable surface in a dedicated fueling area.
- Use absorbent materials on small spills. Do not hose down or bury the spill. Remove the absorbent materials promptly and dispose of properly.
- Avoid mobile fueling of mobile construction equipment around the site; rather, transport the equipment to designated fueling areas.
- Train employees and subcontractors in proper fueling and cleanup procedures.
- Dedicated fueling areas should be protected from stormwater runoff and runoff, and should be located at least 50 feet away from downstream drainage facilities and watercourses. Fueling must be performed on level-grade areas.
- Protect fueling areas with berms and dikes to prevent runoff, and to contain spills.
- Nozzles used in vehicle and equipment fueling should be equipped with an automatic shutoff to control drips. Fueling operations should not be left unattended.
- Federal, State, and Local requirements should be observed for any stationary above ground storage tanks.

INSPECTION AND MAINTENANCE

Vehicles and equipment should be inspected each day of use for leaks. Leaks should be repaired immediately or problem vehicles or equipment should be removed from the project site. Keep ample supplies of spill cleanup materials onsite. Immediately clean up spills and properly dispose of contaminated soil and cleanup materials.

SOLID WASTE MANAGEMENT

DESCRIPTION AND PURPOSE

Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training employees and subcontractors.

SUITABLE APPLICATIONS


- The BMP's are suitable for construction sites where the following wastes are generated or stored:
 - Solid waste generated from trees and shrubs removed during land clearing, demolition of existing structures (rubble), and building construction.
 - Packing materials including wood, paper, and plastic.
 - Scrap or surplus building materials including scrap metals, rubber, plastic, glass pieces and masonry products.
 - Domestic wastes including food containers such as beverage cans, coffee cups, paper bags, plastic wrappers, and cigarettes.
 - Construction wastes including brick, mortar, timber, steel and metal scraps, pipe and electrical cuttings, non-hazardous equipment parts, styrofoam and other materials sent transport and package construction materials.

IMPLEMENTATION

- The following steps will help keep a clean site and reduce stormwater pollution:
- Select designated waste collection areas onsite.
 - Inform trash-hauling contractors that you will accept only watertight dumpsters for onsite use.
 - Inspect dumpsters for leaks and repair any dumpster that is not watertight.
 - Provide an adequate number of containers with lids or covers that can be placed over the container to keep rain out or to prevent loss of wastes when it is windy.
 - Plan for additional containers and more frequent pickups during the demolition phase of construction or as needed.
 - Collect site trash daily, especially during rainy and windy conditions.
 - Remove this solid waste promptly since erosion and sediment control devices tend to collect litter.
 - Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acids, pesticides, additives, curing compounds) are not disposed of in dumpsters designated for construction debris.
 - Do not hose out dumpsters on the construction site. Leave dumpster cleaning to the trash hauling contractor.
 - Arrange for regular waste collection before containers overflow.
 - Clean up immediately if a container does spill.
 - Make sure that construction waste is collected, removed, and disposed of only at authorized disposal areas.
 - Inspect the stormwater management plan on a regular basis and have pumps professionally cleaned once a year. "Caution should be noted" all sumps are deep and potentially dangerous. Extreme care and safety measures along with OSHA guidelines should be followed.

COLLECTION, STORAGE, AND DISPOSAL

- Littering on the project site should be prohibited.
- To prevent clogging of the storm drainage system, litter and debris removal from drainage grates, trash rocks, and ditch lines should be a priority.
- Trash receptacles should be provided in the contractor's yard, field trailer areas, and at locations where workers congregate for lunch and break periods.
- Litter from work areas within the construction limits of the project site should be collected and placed in watertight dumpsters at least weekly, regardless of whether the litter was generated by the contractor, the public, or others. Collected litter and debris should not be placed in or next to drain inlets, stormwater drainage systems, or watercourses.
- Dumpsters of sufficient size and number should be provided to contain the solid waste generated by the project.
- Full dumpsters should be removed from the project site and the contents should be disposed of by the trash hauling contractor.
- Construction debris and waste should be removed from the site biweekly or more frequently as needed.



GENERAL NOTES / LEGEND:

"IT'S THE
LAW"
811




Know what's below.
Call before you dig.

2 WORKING DAYS BEFORE YOU DIG


CLIENT: **MacDOUGALL PIERCE
CONSTRUCTION**

12720 FORD DRIVE
FISHERS, IN 46038

© 2024 ERITZ ENGINEERING SERVICES LLC



EROSION CONTROL BLANKET
NOT TO SCALE



INSTALLATION:

1. THE BOTTOM 1' OF THE FENCE SHALL BE BURIED IN THE TRENCH ON THE UPSLOPE SIDE.
2. FENCE SHALL BE INSTALLED ABOVE LEVEL GRADES, NOT ACROSS FLOW CHANNELS.
3. IF OPTIONAL SUPPORT WIRE FENCE IS USED, POST SPACING MAY BE EXTENDED TO 8' O.C.

MAINTENANCE:

1. MAINTAIN SILENT FENCE PERIODICALLY (WEEKLY) AND AFTER EACH STORM EVENT.
2. IF FABRIC IS TORN OR DAMAGED OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY.
3. REMOVE OR TRIM EXCESS FABRIC WHEN IT REACHES HALF THE HEIGHT OF THE FENCE, OR IS CAUSING THE FABRIC TO BULGE.
4. TAKE CARE NOT TO UNDERMINE THE FENCE DURING SEDIMENT REMOVAL.
5. AFTER THE CONTRIBUTING AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND REMAINING PORTION OF THE TRENCH, BRING THE AREA BACK TO ORIGINAL GRADE.

SILT FENCE SECTION
NOT TO SCALE – PRACTICE 3.74

STABILIZED CONSTRUCTION ENTRANCE

A = KENTUCKY BLUEGRASS 40 LBS/ACRE; CREEPING RED FESCUE 40 LBS/ACRE; PLUS 2 TONS STRAW MULCH/ACRE, OR ADD ANNUAL RYEGRASS 20 LBS/ACRE

B = KENTUCKY BLUEGRASS 60 LBS/ACRE; CREEPING RED FESCUE 60 LBS/ACRE; PLUS 2 TONS STRAW MULCH/ACRE, OR ADD ANNUAL RYEGRASS 30 LBS/ACRE

C = SPRING OATS 3 BUSHEL/ACRE


D = WHEAT OR RYE 2 BUSHEL/ACRE

E = ANNUAL RYEGRASS 40 LBS/ACRE







F = SOD

G = STRAW MULCH 2 TONS/ACRE

SEASONAL SOIL SEEDING PROTECTION CHART



PRINTED BY: Ashton Fritz
DATE: 3/7/2024 9:42 AM
SHEET SIZE, SCALE: ANSI FULL BLEED D (34.00 X 22.00 INCHES), 1:1
FILE NAME: E:\2024\WORKING - GREEN TONER\COMMON\ILLUSTRATIONS\COMMON\ANSI-901.DWG; LAYOUT: COMMON EROSION CONTROL DETAIL S



GENERAL NOTES:



- All slopes are absolute rather than relative to the sidewalk or roadway grade. Slopes at least 0.50% shall be maintained and are preferred.
- Ramp or Blended Transition: A ramp or blended transition shall be used to lower or raise the sidewalk to connect with the street or highway.
- Turning Space: A turning space shall be provided at the top of a perpendicular ramp, bottom of a parallel ramp, or where the pedestrian travel requires a change in direction. A common turning space may be shared by adjacent ramps. The turning space shall have a minimum clear dimension of 4 ft x 4 ft (1.2 m x 1.2 m) and shall be perpendicular to the ramp. The turning space shall be a minimum of 2 ft (0.6 m) wide. The minimum clear dimension shall be 4 ft x 5 ft, with the 5-ft dimension in the direction of the ramp turning slope.
- Ramp Side: A raised side shall be used adjacent to a walkable surface. A raised curb may be used adjacent to a non-walkable surface. A raised curb shall have a minimum clear slope of 10.00% measured parallel to the sidewalk of the ramp.
- Return Curb: A return curb is placed perpendicular to the roadway curb. A return curb may be used adjacent to a non-walkable surface. A return curb shall not be used adjacent to a walkable surface. The return curb may be omitted where the non-walkable surface is flared and the curb adjacent the roadway is flared.
- Clear Space: A clear space shall be provided beyond the bottom grade break of a curb ramp wholly contained within the crosswalk and wholly outside the parallel vehicular travel space. The clear space shall have a minimum clear dimension of 4 ft x 4 ft.
- Detectable Warning Surface: A detectable warning surface shall consist of truncated domes and be placed at each street, highway, or railroad crossing. The detectable warning surface shall extend a minimum of 2 ft in the direction of pedestrian travel and be placed the entire width of a curb, blended transition, or turning space.
- Running Space: The running space of a curb, blended transition, or turning space shall be measured parallel to the direction of pedestrian travel.
 - A running space shall be provided for a curb ramp.
 - A ramp shall have a maximum running slope of 8.33%, but shall not require a ramp length to exceed 15 ft.
 - A blended transition shall have a maximum running slope of 5.00%.
 - A turning space shall have a maximum running slope of 2.00%.
- Width: Unless otherwise noted, minimum width of a ramp, blended transition, or turning space, excluding fixed ends or return curbs, shall be 4 ft.
- Grade Break: A grade break at the top and bottom of a ramp, blended transition, or turning space shall be perpendicular to the running space. Grade breaks shall be perpendicular to the running space. The running space shall be a minimum of 4 ft (1.2 m) wide. The running space shall be a minimum of 12 ft (3.7 m) wide where a discontinuity is greater than 1/4 in. the surface shall be beveled with a slope no steeper than 1V:25H.
- Cross Slope Exceptions: The cross slope of a ramp, blended transition, or turning space shall be measured perpendicular to the direction of pedestrian travel.
 - A maximum cross slope at a pedestrian street crossing without a posted grade or stop control shall be 5.00%.
 - A maximum cross slope at a pedestrian street crossing with a posted grade or stop control shall be 2.00%.
 - A maximum cross slope at a midblock crossing shall be the established grade of the adjacent roadway.
- Counter Slope: A counter slope is the cross slope of the gutter or street adjacent the running slope of the ramp, blended transition, or turning space. See Standard Drawing 604-CONC-04 for counter slope details.
- Objects such as a utility cover, walk frame, and grating shall be placed outside the curb ramp.
- Curb ramps shall be placed within the marked crosswalk area.
- Drainage inlets should be located uphill from a curb ramp to prevent ponding in the curb ramp travel.



INDIANA DEPARTMENT OF TRANSPORTATION	
CURB RAMP DRAWING INDEX AND GENERAL NOTES	
SEPTEMBER 2018	
STANDARD DRAWING NO.	E 604-SWCR-01

ELIZABETH W. PHILLIPS
 REG. SURVEYOR
 No.
 10200124
 STATE OF
 INDIANA
 PROFESSIONAL SURVEYOR

<i>/s/ Elizabeth W. Phillips</i> DESIGN STANDARDS ENGINEER	<i>03/20/18</i> DATE
<i>/s/ John Leckie</i> CHIEF ENGINEER	<i>04/25/18</i> DATE

[illegible]

[illegible]

GENERAL NOTES / LEGEND



Know what's below.
Call before you dig.
2 WORKING DAYS BEFORE YOU DIG

PROJECT



GREEN TOUCH CORDSVILLE

PROJECT LOCATION

6312 RAILROAD ST
MCCORDSVILLE, INDIANA 46055
HANCOCK COUNTY

SECTION, TOWNSHIP, RANGE

NE $\frac{1}{4}$, S26, T17N, R5E

CLIENT

**MacDOUGALL PIERCE
CONSTRUCTION**

12720 FORD DRIVE
FISHERS, IN 46038

PLAN DATE:

3/8/2024

DESIGN

CHECK:

DRAWN:

AF

2308005

SHEET NAME

INDOT CURB RAMP DETAILS

SHEET NO

C602

© 2024 ERITZ ENGINEERING SERVICES LLC

