

DEVELOPMENT PLAN FOR

SHOPS in VILLAGES at BROOKSIDE SEC 16 - BLOCK A

SWC CR N 600 W & CR W 900 N, McCORDSVILLE IN 46055



PROJECT LOCATION

PLAN SHEET INDEX	
C0.0	TITLE SHEET
C2.0	SITE PLAN
C3.0	GRADING & DRAINAGE PLAN
C3.1	STORM SEWER PLAN & PROFILES
C4.0	STORMWATER POLLUTION PREVENTION PLAN
C4.1	STORMWATER POLLUTION PREVENTION DETAILS
C4.2	STORMWATER POLLUTION PREVENTION NOTES
C5.0	UTILITY PLAN
C7.0-C7.1	GENERAL DETAILS
C9.0	SPECIFICATIONS
L1.0	LANDSCAPE PLAN
SL1.0	SITE LIGHTING PLAN (BY OTHERS)
TOPO	TOPOGRAPHIC SURVEY BY CROSSROAD ENGINEERS (03/11/2024)

REFERENCE STANDARDS/SPECIFICATIONS:
TOWN OF MCCORDSVILLE CONSTRUCTION STANDARDS & SPECIFICATIONS (10 SHEETS)
CITIZENS ENERGY GROUP WATER STANDARDS MANUALS

PROJECT DEVELOPER:
BDC REALTY GROUP, LLC
6274 S Fox Chase
Pendleton, Indiana 46064

ENGINEER:
CivilSite
GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Phone: (317) 810-1677
Email: bcross@civilsite.net

ARCHITECT:
INTEGRITY DESIGN, LLC
3128 Nichol Avenue
Anderson, Indiana 46011
Ph: (765) 608-3001

SURVEYOR:
Crossroad Engineers, P.C.
3417 Sherman Drive
Beech Grove, IN 46107
Contact: G.W. Charles, PE, PS
Phone: (317) 780-1555
Email: gwcharles@crossroadengineers.com

UTILITY CONTACTS

Telephone:
AT&T
240 North Meridian St., Room 280
Indianapolis, IN 46204
Brian Wente - (317) 610-5440;
(317) 525-4894 - cell
Bw1917@att.com

Drainage & Streets:
Town of McCordsville - Engineering
6280 W 800 N
McCordsville, IN 46055
(317) 335-3604

Electric:
Duke Energy
(800) 521-2232

Natural Gas:
Centerpoint Energy

Wastewater & Water:
Citizens Energy Group/CWA Authority, Inc.
2150 Dr. Martin Luther King Jr St
Indianapolis, IN 46202
Brad Hostetler - (317) 927-4351
bhostetler@citizensenergygroup.com

Streets:
INDOT-Greenfield District
32 South Broadway
Greenfield, IN 46140
Toll Free: 855-INDOT4U (463-6848)



VICINITY MAP
SCALE: 1" = 1000'
NORTH

LAND DESCRIPTION

BLOCK A IN THE VILLAGES OF BROOKSIDE SECTION 16 RECORDED
AS INSTRUMENT NO. 2022-12878, PLAT CABINET D, PAGE 210 IN THE
RECORDER'S OFFICE OF HANCOCK COUNTY, INDIANA.

DEVELOPMENT SUMMARY

PROPOSED USE: RETAIL-MEDIUM
BUILDING(S) GROSS SQUARE FOOTAGE: = 14,400± S.F.
TOTAL SITE AREA = 5.69± Ac.
OPEN SPACE AREA = 3.30± Ac. (58% of TOTAL LOT AREA)
IMPERVIOUS AREA COVERAGE = 2.39± Ac. (42%)
CURRENT ZONING = VILLAGES AT BROOKSIDE PUD-AMENDMENT

PARKING SPACES PROVIDED = 80
PARKING SPACES REQUIRED = 48 (1 SPACE / 300 GSF)

ANTICIPATED CONSTRUCTION START/END DATE:
AUGUST, 2024 / JUNE 2025

DRAINAGE TILE NOTE

ALL DRAINAGE TILES ENCOUNTERED ON PROJECT
SITE WILL BE PROVIDED A POSITIVE OUTLET.

STANDARDS


THE TOWN OF MCCORDSVILLE & INDOT STANDARDS SHALL
BE INCORPORATED BY REFERENCE INTO THESE PLANS FOR
CONSTRUCTION ACTIVITY THROUGHOUT THE SITE AND INDOT
RIGHT-OF-WAY

SPECIFICATIONS

NO ALTERNATE SPECIFICATIONS OR MATERIALS OR NEW MATERIALS
MAY BE USED WITHOUT THE EXPRESS WRITTEN APPROVAL FROM
THE TOWN OF PENDLETON PRIOR TO THE COMPLETION OF WORK.

INDIANA DEPARTMENT OF TRANSPORTATION LATEST
EDITION OF SPECIFICATIONS & STANDARDS TO BE USED
DURING CONSTRUCTION WITH THESE PLAN DOCUMENTS

REVISION RECORD				
REV	DATE	DESCRIPTION	DES BY	APP BY



CSG PROJECT NUMBER
BRG.006

DRAWING NUMBER
C0.0
SHEET 1 OF 24

DRAWING NUMBER
C2.0
SHEET 2 OF 24



DEVELOPER:
BDC REALTY GROUP, LLC
6274 SOUTH FOX CHASE
PENDLETON, INDIANA 46064
ATTN: DAVE CRAVENS
(763) 635-5559

ENGINEER:
CIVIL SITE GROUP, INC.
718 ADAMS STREET
CARMEL, INDIANA 46032
(317) 810-1677

SURVEYOR:
CROSSROAD ENGINEERS
3417 Sherman Drive
Beech Grove, IN 46107
ATTN: G.W. Charles, PE, PS
(317) 780-1555

BENCHMARK

SITE BENCHMARKS:
(LOCATIONS SHOWN ON SURVEY)

TBM #400 CUT "X" ON WEST ANCHOR BOLT OF
SIGNAL POLE, LOCATED IN SOUTHWEST QUAD OF "CR
900 N" AND "CR 600 W".

ELEV. = 850.90 (NAVD 88)

CASTING NOTE

STORM INLET CASTINGS TO REQUIRE A
"NO DUMPING" MESSAGE PER THE
TOWN OF MCCORDSVILLE STANDARDS.

TOPOGRAPHIC & BOUNDARY NOTE


ALL EXISTING HORIZONTAL AND VERTICAL INFORMATION HAS BEEN SHOWN
PER A TOPOGRAPHIC SURVEY DATED 03/11/2024 PREPARED BY CROSSROAD
ENGINEERG, P.C.; THEREFORE, CIVIL SITE GROUP, INC. CANNOT BE HELD
RESPONSIBLE IF ACTUAL HORIZONTAL AND VERTICAL DATA IS DIFFERENT
FROM THAT SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR
FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO COMMENCING
WITH CONSTRUCTION.

FLOOD NOTE

THIS LOT LIES ENTIRELY IN FLOOD HAZARD
ZONE "X" AS SCALED FROM THE FLOOD
INSURANCE RATE MAP (FIRM) FOR HANCOCK
COUNTY, INDIANA, COMMUNITY NUMBER
180468, MAP NUMBER 18059C0016D, PANEL
NUMBER 0016 D, DATED DECEMBER 4, 2007.
REFERENCE NFIP FIRM MAP #18059C0016D,
EFFECTIVE DATE: DECEMBER 4, 2007

STORM SEWER SYSTEM NOTE

ALL ON-SITE STORM SEWER INFRASTRUCTURE
TO BE CONSTRUCTED WITH THIS PROJECT SHALL
BE PRIVATELY OWNED AND MAINTAINED.



REVISION RECORD

REV	DATE	DESCRIPTION	DES BY	APP BY

PLAN NOTES:

- (R1) APPROX. 30± LF OF 10" PVC (SDR35 @ 0.1% MIN. SLOPE) ROOF
DRAIN LEADER WITH RISERS, ADAPTERS FOR CONNECTIONS, BENDS,
FITTINGS, & CLEANOUTS AT BENDS > 22.5' FOR ROOF CONNECTIONS;
REDUCE TO 6" TO BLDG. DOWNSPOUTS
- (R2) APPROX. 160± LF OF 8" PVC (SDR35 @ 0.75% MIN. SLOPE) ROOF
DRAIN LEADER WITH RISERS, ADAPTERS FOR CONNECTIONS, BENDS,
FITTINGS, & CLEANOUTS AT BENDS > 22.5' FOR ROOF CONNECTIONS;
REDUCE TO 6" TO BLDG. DOWNSPOUTS
- (FL) FLUSH WITH PAVEMENT

LEGEND:

- R/W — PROPERTY BOUNDARY OR R/W
(REFER TO ALTA/NSPS SURVEY)
- PROPOSED STORM SEWER
- PROPOSED INLET SUB-SURFACE DRAIN / ROOF DRAINS
- PROPOSED STORM STRUCTURE
- EX. UNDERGROUND STORM SEWER LINE
- PROPOSED SPOT ELEVATION
- PROPOSED TOP OF CURB ELEVATION
PROPOSED PYMT ELEVATION
- ME MATCH EXISTING GRADE
TC TOP OF CURB/STORM CASTING ELEVATION
INV STORM SEWER INVERT ELEVATION
- 849 — PROPOSED CONTOUR
— 850 — EXISTING CONTOUR
— >>> — PROPOSED DRAINAGE SWALE
- EXISTING SITE OVERFLOW ROUTING

GENERAL NOTES

CONTRACTOR TO KEEP EXISTING PAVEMENT SURROUNDING THE SITE
(CR N 600 W) "BROOM CLEAN" AND FREE OF SOIL OR AGGREGATE THAT
MIGHT BE BROUGHT OFF-SITE.

DEPENDING ON THE CONSTRUCTION SEASON, MOISTURE CONTENT
AND PROPERTIES OF THE SOILS ON SITE, CHEMICAL MODIFICATIONS
AND/OR LIME STABILIZATION MAY BE REQUIRED. SEE SHEET C9.0 FOR
SPECIFICATIONS.

ALL CONCRETE PIPE JOINTS SHALL BE CONTINUOUS O-RING RUBBER
GASKET CONFORMING TO ASTM C 443


CONTRACTOR SHALL SUBMIT PRECAST STORM SEWER STRUCTURE
SHOP DRAWINGS TO ENGINEER FOR REVIEW/APPROVAL PRIOR TO
MANUFACTURING.

GRADING NOTES

- ALL CONSTRUCTION METHODS AND MATERIALS MUST CONFORM TO CURRENT
STANDARDS AND SPECIFICATIONS OF THE FEDERAL, STATE, COUNTY, CITY
OR LOCAL REQUIREMENTS, WHICHEVER HAS JURISDICTION.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD PRIOR TO
STARTING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR
ALL FIELD DIMENSIONS. IF ANY DISCREPANCIES ARE FOUND IN THESE PLANS
FROM THE ACTUAL FIELD CONDITIONS, THE CONTRACTOR SHALL NOTIFY THE
ENGINEER IMMEDIATELY.
- THE EXCAVATING CONTRACTOR MUST TAKE PARTICULAR CARE WHEN
EXCAVATING IN AND AROUND EXISTING UTILITY LINES AND EQUIPMENT.
VERIFY COVER REQUIREMENTS BY UTILITY CONTRACTORS AND/OR UTILITY
COMPANIES SO AS NOT TO CAUSE DAMAGE.
- THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES 72 HOURS BEFORE
CONSTRUCTION IS TO START. TO VERIFY IF ANY UTILITIES ARE PRESENT ON
SITE, ALL VERIFICATIONS (LOCATION, SIZE AND DEPTH) SHALL BE MADE BY THE
APPROPRIATE UTILITY COMPANIES. WHEN EXCAVATING IS AROUND OR OVER
EXISTING UTILITIES, THE CONTRACTOR MUST NOTIFY THE UTILITY COMPANY
SO A REPRESENTATIVE OF THAT UTILITY COMPANY CAN BE PRESENT TO
INSTRUCT AND OBSERVE DURING CONSTRUCTION.
- TRENCHES FOR ALL STORM DRAIN LINES SHALL BE BACKFILLED COMPLETELY
WITH ENGINEERED GRANULAR MATERIAL IF WITHIN 5 FEET OF PAVEMENT.
- AFTER STRIPPING TOPSOIL MATERIAL, PROOFROLL WITH A MEDIUM WEIGHT
ROLLER TO DETERMINE LOCATIONS OF ANY POCKETS OF UNSUITABLE
MATERIAL. THE NECESSITY FOR SUBGRANS AND/OR REMOVAL OF ANY
UNUSABLE MATERIAL WITHIN THE PROPOSED PARKING AREAS WILL BE
DETERMINED AT THE TIME OF CONSTRUCTION.
- PROVIDE POSITIVE DRAINAGE WITHOUT PONDING, IN ALL AREAS, AFTER
INSTALLATION. CONTRACTOR TO TEST FOR, AND CORRECT, IF ANY, "BIRD
BATH" CONDITIONS.
- SEE APPROPRIATE DETAILS TO DETERMINE SUBGRADE ELEVATIONS BELOW
FINISH GRADE ELEVATIONS INDICATED.
- FLOW LINE ELEVATIONS GIVEN AT END OF CONCRETE END SECTIONS.
- SIDEWALK AGAINST BUILDING SHALL SLOPE AWAY FROM BUILDING AT
1.04% SLOPE MIN.

GRADING & UTILITY NOTE

CONTRACTOR TO VERIFY THE DEPTH AND LOCATION OF ALL EXISTING
UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROPOSED
DRIVEWAY CUTS MAY REQUIRE EXISTING UTILITY FACILITIES TO BE
LOWERED AND/OR RELOCATED IN ORDER TO MAINTAIN MINIMUM
STANDARDS OF COVER / VERTICAL SEPARATION, INCLUDING WATER,
GAS, POWER, AND TELECOM.



SHOPS in VILLAGES at BROOKSIDE BLOCK A

CR 600 W
McCordsville, IN 46055

GRADING & DRAINAGE PLAN


PROJECT NUMBER
BRG.006

DRAWING NUMBER
C3.0
SHEET 3 OF 24

BDC REALTY GROUP, LLC

6274 S FOX CHASE
PENDLETON, IN 46064

CivilSite
GROUP, INC.
CIVIL SITE GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Ph: (317) 810-1677



DWN BY: BSC
CHKD. BY: BSC
SCALE: 1" = 30'
DATE: 06/06/24



DEVELOPER:
BDC REALTY GROUP, LLC
6274 SOUTH FOX CHASE
PENDLETON, INDIANA 46064
ATTN: DAVE CRAVENS
(763) 635-5559

ENGINEER:
CIVIL SITE GROUP, INC.
718 ADAMS STREET
CARMEL, INDIANA 46032
(317) 810-1677

SURVEYOR:
CROSSROAD ENGINEERS
3417 Sherman Drive
Beech Grove, IN 46107
ATTN: G.W. Charles, PE, PS
(317) 780-1555

CASTING NOTE

STORM INLET CASTINGS TO REQUIRE A
"NO DUMPING" MESSAGE PER THE
TOWN OF MCCORDSVILLE STANDARDS.

BENCHMARK

SITE BENCHMARKS:
(LOCATIONS SHOWN ON SURVEY)


TBM #400 CUT "X" ON WEST ANCHOR BOLT OF
SIGNAL POLE, LOCATED IN SOUTHWEST QUAD OF "CR
900 N" AND "CR 600 W".

ELEV. = 850.90 (NAVD 88)

18" OF VERTICAL SEPARATION MUST
BE MAINTAINED FOR ALL UTILITY
CROSSINGS.

STORM SEWER PLAN

PROFILE SCALE: 1"=50'




STORM SEWER PROFILE

LEGEND

Existing Grade
New Grade
Granular Backfill

SCALE: HORZ.: 1"=50'
VERT.: 1"=5'



REVISION RECORD				
REV	DATE	DESCRIPTION	DES BY	APP BY

LEGEND:

- R/W — PROPERTY BOUNDARY OR R/W (REFER TO ALTA/NSPS SURVEY)
- PROPOSED STORM SEWER
- PROPOSED SUB-SURFACE ROOF DRAIN
- PROPOSED STORM STRUCTURE
- EX. UNDERGROUND STORM SEWER LINE
- PROPOSED SPOT ELEVATION
- PROPOSED TOP OF CURB ELEVATION
- PROPOSED PVMT ELEVATION
- ME MATCH EXISTING GRADE
- TC TOP OF CURB/STORM CASTING ELEVATION
- INV STORM SEWER INVERT ELEVATION
- 849 — PROPOSED CONTOUR
- 850 — EXISTING CONTOUR
- PROPOSED DRAINAGE SWALE

STORM SEWER SYSTEM NOTE

ALL ON-SITE STORM SEWER INFRASTRUCTURE
TO BE CONSTRUCTED WITH THIS PROJECT SHALL
BE PRIVATELY OWNED AND MAINTAINED.

TOPOGRAPHIC & BOUNDARY NOTE

ALL EXISTING HORIZONTAL AND VERTICAL INFORMATION HAS BEEN SHOWN
PER A TOPOGRAPHIC SURVEY DATED 03/11/2024 PREPARED BY CROSSROAD
ENGINEER, P.C.; THEREFORE, CIVIL SITE GROUP, INC. CANNOT BE HELD
RESPONSIBLE IF ACTUAL HORIZONTAL AND VERTICAL DATA IS DIFFERENT
FROM THAT SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR
FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO COMMENCING
WITH CONSTRUCTION.

SHOPS in VILLAGES at BROOKSIDE BLOCK A

CR 600 W
MCCORDSVILLE, IN 46055

STORM SEWER PLAN & PROFILE

PROJECT NUMBER
BRG.006

DRAWING NUMBER
C3.1
SHEET 4 OF 24

BDC REALTY GROUP, LLC

6274 S FOX CHASE
PENDLETON, IN 46064

CIVIL SITE GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Ph: (317) 810-1677



DWN BY: BSC
CHKD. BY: BSC
SCALE: 1" = 30'
DATE: 06/06/24




SOILS DESCRIPTIONS & LIMITATIONS

1. **Crosby Silt Loam (YcuA – 32.7% Site)** The Crosby series consists of very deep, somewhat poorly drained soils that are moderately deep to dense till on till plains. These soils formed in loamy till that can be capped with up to 22 inches of loess or silty material. Permeability is moderate or moderately slow in and above the argillic horizon and slow or very slow below the argillic horizon. Slope ranges from 0 to 6 percent. Subject soil does not present any foreseeable limitations to the proposed development.
2. **Brookston Silty Clay Loam (Ybva – 67.3% Site)** The Brookston series consists of very deep, poorly drained soils formed in up to 20 inches of silty material and the underlying loamy till in depressions on till plains and moraines. Permeability is moderate in the subsoil and moderately slow in the underlying material. Slope ranges from 0 to 3 percent. Subject soil does not present any foreseeable limitations to the proposed development. Given that this soil typically shows high moisture content and is a hydric soil, permeability may be moderate, soil chemical modifications (i.e. lime stabilization) may likely be required.

SWPP TRAINED INDIVIDUAL:

Self-inspections - A trained individual shall perform visual inspections of the project site. A trained individual is an individual who is trained and experienced in the principles of stormwater management, including erosion and sediment control as is demonstrated by completion of coursework, state registration, professional certification, or annual training that enable the individual to make judgments regarding stormwater management, treatment, and monitoring.

- 1) The frequency of self-inspections are:
- At least once every work week;
 - Within twenty-four (24) hours after qualifying precipitation event, which is precipitation accumulation equal to, or greater than, one-half (0.50) inch of rainfall within a 24-hour period. Inspections that were conducted twenty-four (24) hours prior to a qualifying precipitation event meet this requirement.
 - If there are multiple qualifying precipitation events occur during the week no more than three (3) inspections are required within that week.



30 0 15 30
(IN FEET)
1 inch = 30 ft.

REVISION RECORD			
REV	DATE	DESCRIPTION	DES BY APP BY

TOPOGRAPHIC & BOUNDARY NOTE

ALL EXISTING HORIZONTAL AND VERTICAL INFORMATION HAS BEEN SHOWN PER A TOPOGRAPHIC SURVEY DATED 03/11/2024 PREPARED BY CROSSROAD ENGINEERG, P.C.; THEREFORE, CIVIL SITE GROUP, INC. CANNOT BE HELD RESPONSIBLE IF ACTUAL HORIZONTAL AND VERTICAL DATA IS DIFFERENT FROM THAT SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO COMMENCING WITH CONSTRUCTION.

TOWN OF MCCORDSVILLE STANDARDS

CONTRACTOR TO CONSTRUCT ALL APPLICABLE SITE IMPROVEMENTS TO THE TOWN OF MCCORDSVILLE CURRENT STANDARDS PER THE ATTACHED STANDARD DETAIL SHEETS.

DEWATERING DISCHARGE

ALL DEWATERING PUMPING SHALL BE DISCHARGED INTO AN APPROVED FILTER BAG BEFORE RELEASING INTO THE EXISTING STORM SEWER SYSTEM AND/OR R/W SWALE.

GENERAL NOTES

- CONTRACTOR TO SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE TOWN OF MCCORDSVILLE AND/OR HANCOCK COUNTY SOIL & WATER CONSERVATION DISTRICT PRIOR TO COMMENCING WITH CONSTRUCTION.
- TEMPORARY TRAFFIC CONTROL DURING CONSTRUCTION TO CONFORM TO APPLICABLE LOCAL AND STATE STANDARDS.
- ALL CONSTRUCTION ACTIVITY ON THIS SITE TO BE PERFORMED IN COMPLIANCE WITH APPLICABLE O.S.H.A. STANDARDS FOR WORKER SAFETY.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL UTILITY LOCATIONS BEFORE CONSTRUCTION BEGINS.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING ELEVATIONS BEFORE CONSTRUCTION BEGINS.

ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED IN THE FIELD BY THE INSPECTOR

EROSION CONTROL NOTES

- ALL CONSTRUCTION METHODS AND MATERIALS MUST CONFORM TO CURRENT STANDARDS AND SPECIFICATIONS OF THE FEDERAL, STATE, COUNTY, CITY OR LOCAL REQUIREMENTS, WHICHEVER HAS JURISDICTION.
- LAND ALTERATION WHICH STRIPS THE LAND OF VEGETATION, INCLUDING REGRADING, SHALL BE DONE IN A WAY THAT WILL MINIMIZE EROSION.
- THIS PLAN SHALL NOT BE CONSIDERED ALL INCLUSIVE AS THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT SOIL SEDIMENT FROM LEAVING THE SITE. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION.
- SEDIMENT LADEN WATER SHALL BE DETAINED BY EROSION CONTROL PRACTICES AS NEEDED TO MINIMIZE SEDIMENTATION IN THE RECEIVING STREAM. NO STORM WATER SHALL BE DISCHARGED FROM THE SITE IN A MANNER THAT CAUSES EROSION AT THE POINT OF DISCHARGE.
- WASTES AND UNUSED BUILDING MATERIALS SHALL NOT BE ALLOWED TO BE CARRIED FROM THE SITE BY STORMWATER RUNOFF. PROPER DISPOSAL OF ALL WASTES AND UNUSED BUILDING MATERIALS IS REQUIRED.
- SEDIMENT BEING TRACED ONTO PUBLIC OR PRIVATE ROADWAYS SHALL BE MINIMIZED. CLEARING OF ACCUMULATED SEDIMENT SHALL NOT INCLUDE FLUSHING WITH WATER. CLEARED SEDIMENT SHALL BE RETURNED TO THE SITE FOR DISPOSAL.
- SOIL WHICH HAS ACCUMULATED NEXT TO EROSION CONTROL DEVICES SHALL BE COLLECTED AND REDISTRIBUTED ON SITE AFTER EACH RAINFALL EVENT, AND AT LEAST ONCE A WEEK.
- IF INSTALLATION OF STORM DRAINAGE SYSTEM SHOULD BE INTERRUPTED BY WEATHER OR NIGHTFALL, THE PIPE ENDS SHALL BE COVERED WITH FILTER FABRIC.
- ALL EXISTING STRUCTURES, FENCING, TREES AND ETC., WITHIN CONSTRUCTION AREA SHALL BE REMOVED AND DISPOSED OF OFF SITE. BURNING IS NOT ALLOWED ON-SITE.
- SCHEDULE OF EARTHWORK ACTIVITIES:
 - THE DURATION OF TIME WHICH AN AREA REMAINS EXPOSED SHALL BE KEPT TO A PRACTICAL MINIMUM. THE AREA SHALL BE STABILIZED SOON AS POSSIBLE. TEMPORARY VEGETATION OR MULCHING SHALL BE USED TO PROTECT EXPOSED AREAS IF PERMANENT VEGETATION CANNOT BE SEEDED WITHIN 14 DAYS OR ACTIVITY CEASES FOR MORE THAN 21 DAYS OR AS DIRECTED BY THE ENGINEER.
 - TOPSOIL REPLACEMENT SHALL TAKE PLACE FROM MARCH 1 TO OCTOBER 31. STOCKPILE TOPSOIL AT ALL OTHER TIME OF THE YEAR. PERMANENT AND FINAL VEGETATION AND STRUCTURAL EROSION CONTROL DEVICES SHALL BE INSTALLED WITHIN SEVEN (7) DAYS AFTER FINAL GRADING OR AS SOON AS POSSIBLE.

LEGEND:

- R/W
- PROPERTY BOUNDARY OR R/W (REFER TO ALTA/NSPS SURVEY)
- PROPOSED STORM SEWER
- PROPOSED SUB-SURFACE ROOF DRAIN
- PROPOSED STORM STRUCTURE
- EX. UNDERGROUND STORM SEWER LINE
- PROPOSED CONTOUR
- EXISTING CONTOUR
- PROPOSED DRAINAGE SWALE
- APPROX. CONSTRUCTION LIMITS
- Check Dam/Sediment Filter – Pond Outlet Protection & Existing Road Overlays (Rock Check Dam). SEE DETAIL 04/C4.1
- PROPOSED SILT FENCE—Typical in all areas where sediment could leave the site. SEE DETAIL 06/C4.1
- PERMANENT SEEDING WITH STRAW MULCH – TYPICAL AFTER FINAL GRADING IS COMPLETED.
- PROPOSED EROSION CONTROL BLANKET SEE DETAIL 05/C4.1
- TEMPORARY SEEDING WITH STRAW MULCH – TYPICAL WHERE CONSTRUCTION ACTIVITIES WILL REMAIN IDLE FOR A PERIOD OF 10 DAYS OR MORE.
- Point where stormwater will leave the site.
- Inlet Protection FlexStorm Baskets to be utilized in paved areas. SEE DETAIL ON SHEET C4.1
- PROPOSED TEMPORARY CONSTRUCTION ENTRANCE SEE DETAIL 03/C4.1

NOTE: INSTALL TEMPORARY SEEDING AFTER A SPECIFIC STAGE OF CONSTRUCTION HAS BEEN COMPLETED (TEMPORARY OR FINAL) WHERE AREAS WILL BE IDLE OF CONSTRUCTION ACTIVITIES FOR A PERIOD OF 10 DAYS OR MORE.

MULCHING NOTE

WHERE REQUIRED, CRIMPED/ANCHORED MULCH OR MULCH WITH A TACKING AGENT SHALL BE USED. THE APPLICATION RATE SHOULD MEET GUIDELINES PER PRACTICE 5.15 OF THE INDIANA HANDBOOK FOR EROSION CONTROL IN DEVELOPING AREAS.

STREET EROSION NOTE

THERE SHALL BE NO DIRT, DEBRIS, OR STORAGE OF MATERIALS IN THE SURROUNDING STREETS DURING THE CONSTRUCTION PROCESS.

EROSION CONTROL CONTACT

DAVE CRAVENS
BDC REALTY GROUP, LLC
6274 SOUTH FOX CHASE
PENDLETON, INDIANA 46064
(765) 635-5559



SOILS MAP
SCALE: 1" = 200'



CASTING NOTE


STORM INLET CASTINGS TO REQUIRE A "NO DUMPING" MESSAGE PER THE TOWN OF PENDLETON STANDARDS.

DEVELOPMENT SUMMARY

TOTAL SITE AREA = 5.69± ACRES
TOTAL DISTURBED AREA = 2.6± ACRES

FLOOD NOTE

THIS LOT LIES ENTIRELY IN FLOOD HAZARD ZONE "X" AS SCALED FROM THE FLOOD INSURANCE RATE MAP (FIRM) FOR HANCOCK COUNTY, INDIANA. COMMUNITY NUMBER 180468. MAP NUMBER 18059C0016D, PANEL NUMBER 0016 D, DATED DECEMBER 4, 2007. REFERENCE NFP FIRM MAP #18059C0016D, EFFECTIVE DATE: DECEMBER 4, 2007



BDC REALTY GROUP, LLC
6274 S FOX CHASE
PENDLETON, IN 46064

CIVIL SITE GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Ph: (317) 810-1677



DWN BY: BSC
CHKD. BY: BSC
SCALE: 1" = 30'
DATE: 06/06/24

SHOPS in VILLAGES at BROOKSIDE BLOCK A
CR 600 W
McCordsville, IN 46055

STORMWATER POLLUTION PREVENTION PLAN

PROJECT NUMBER
BRG.006

DRAWING NUMBER
C4.0
SHEET 5 OF 24

FERTILIZER NOTE

DO NOT USE PHOSPHOROUS CONTAINING FERTILIZERS UNLESS SOIL TESTS SHOW A PHOSPHOROUS DEFICIENCY.

SEEDBED PREPARATION

APPLY LIME TO RAISE THE pH TO THE LEVEL NEEDED FOR SPECIES BEING SEED. APPLY 23 POUNDS OF 12-12-12 ANALYSIS FERTILIZER (OR EQUIVALENT) PER 1000 SQ. FT. (APPROXIMATELY 1000 POUNDS PER ACRE) OR FERTILIZE ACCORDING TO TEST. APPLICATION OF 150 LBS. OF AMMONIUM NITRATE ON AREAS LOW IN ORGANIC MATTER AND FERTILITY WILL GREATLY ENHANCE VEGETATIVE GROWTH.

WORK THE FERTILIZER AND LIME INTO THE SOIL TO A DEPTH OF 2-3 INCHES WITH A HARROW, DISK OR RAKE OPERATED ACROSS THE SLOPE AS MUCH AS POSSIBLE.

SEEDING

SELECT A SEED MIXTURE BASED ON PROJECTED USE OF THE AREA (SEE PERMANENT SEED MIXTURE CHART). WHILE CONSIDERING BEST SEEDING DATES. IF PERMANENT SEEDING IS NOT PERMITTED USE TEMPORARY SEEDING UNTIL PERMANENT SEEDING CAN BE APPLIED. IF TOLERANCES ARE A PROBLEM, SUCH AS SALT TOLERANCE OF SEEDINGS ADJACENT TO STREETS AND HIGHWAYS, SEE SEED TOLERANCE CHART.

	SOIL CONDITION			SHADE TOLERANCE	CLOSE MOWING TO 2-3 1/2 INCHES	TRAMPING TOLERANCE	FERTILITY	WINTER HARDINESS	FLOODING TOLERANCE (DAYS)	MATURE HEIGHT (INCHES)	EMERGENCE TIME (DAYS)	SOIL TOLERANCE	
	WET	NORM	DRY									GEN.	SOIL SPRAY
CREeping RED FESCUE FESTUCA RUBRA	2	1	2	1	1	1	MED.	1	20-25	12-18	7-21		S
KENTUCKY BLUEGRASS POA PROTENSIS	2	1	2	1	1	1	MED.	1	20-35	12-18	10-20		MT
TALL FESCUE FESTUCA L. ARUNDINACEA	2	1	1	1	1	1	LOW	1	24-35	24-36	5-14	T	
PERENNIAL RYEGRASS LOLLUM PERENNE	2	1	2	-	1	2	MED. HIGH	2	15-20	12-18	5-10		MT
CROWN VETCH CORONILLA VARIA	-	1	1	2	-	-	LOW	1	5-10	24	14-21	T	
RED CLOVER TRIFOLIUM PROTENSE	-	1	-	2	-	-	MED.	1	7-10	18	5-10	S	S

RANKING:
1 GOOD
2 MEDIUM
- NOT TOLERANT

SALT TOLERANCE (TO BOTH SOIL SALTS & SPRAY)

T TOLERANCE
MT MEDIUM TOLERANCE
S SLIGHT TOLERANCE

SEED TOLERANCE

SPECIES	SEEDING RATE		SUITABLE pH	SITE SUITABILITY*		
	LBS/ACRE	LBS/1000 SQ. FT.		DROUGHTY	WELL DRAINED	WET
LEVEL AND SLOPING, OPEN AREAS						
1. TALL FESCUE	35	.8	5.5-8.3	2	1	2
2. TALL FESCUE	25	.6	5.5-8.3		1	
RED CLOVER	5	.12				
3. KENTUCKY BLUEGRASS	15	.4	5.8-7.5	2	1	
CREEPING RED FESCUE	15	.4				
STEEP BANKS AND CUTS						
4. TALL FESCUE	15	.4	5.8-7.5	2	1	2
KENTUCKY BLUEGRASS	25	.6				
TALL FESCUE	35	.8	5.5-8.3	2	1	
EMERALD CROWN VETCH**	10	.25				
LAWNS AND HIGH MAINTENANCE AREAS						
6. KENTUCKY BLUEGRASS	40	.9	5.8-7.5	2	1	
CREEPING RED FESCUE	40	.9				
PERENNIAL RYEGRASS (TURF TYPE)	170	4.0	5.0-7.5		1	
8. TALL FESCUE	170	4.0	5.5-8.3	2	1	2

* 1 - PREFERRED 2 - WILL TOLERATE ** INOCULATE WITH SPECIFIC INOCULANT.

SEED TOLERANCE CHART

SEEDING DETAIL

REVISION RECORD					
REV	DATE	DESCRIPTION	DES BY	APP BY	

TEMPORARY SEEDING DATES

	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
WHEAT OR RYE												
OATS												
ANNUAL RYEGRASS												

PERMANENT SEEDING DATES

	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
WHEAT OR RYE												
OATS												
ANNUAL RYEGRASS												

FERTILIZER NOTE

DO NOT USE PHOSPHOROUS CONTAINING FERTILIZERS UNLESS SOIL TESTS SHOW A PHOSPHOROUS DEFICIENCY.

IRRIGATION NEEDED DURING THIS PERIOD. TO CONTROL EROSION AT TIMES OTHER THAN IN THE SHADED AREAS. USE MULCH.






* LATE SUMMER SEEDING DATES MAY BE EXTENDED 5 DAYS IF MULCH IS APPLIED.

** INCREASE SEEDING APPLICATION BY 50%.








TEMPORARY SEEDINGS

TYPE OF SEED	1000 SQ. FT.	ACRE	REMARKS
WHEAT OR RYE	3.5 LBS.	2 BU.	COVER SEED 1" TO 1 1/2" DEEP
SPRING OATS	2.3 LBS.	3 BU.	COVER SEED 1" DEEP
ANNUAL RYEGRASS	1 LB.	40 LB.	COVER SEED 1/4" DEEP

* NOT NECESSARY WHERE MULCH IS APPLIED.



DAVE CRAVENS
BIO REALTY GROUP, LLC
6274 SOUTH FOX CHASE
PENDLETON, INDIANA 46064
(765) 635-5559



EROSION CONTROL MEASURE	MAINTENANCE	INSTALLATION SEQUENCE
STONE ENTRANCE	AS NEEDED	PRIOR TO CLEARING AND GRADING
SILT FENCE	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
EXISTING INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TREE PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	PRIOR TO CLEARING AND GRADING
TEMPORARY DIVERSIONS	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	ALONG WITH ROUGH GRADING
TEMPORARY SEEDING	WATER AS NEEDED	AFTER FINISH GRADING - AS SOON AS PRACTICAL UPON COMPLETION
PERMANENT SEEDING	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING - AS SOON AS PRACTICAL UPON COMPLETION
EROSION CONTROL MATTING	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER FINISH GRADING - AS SOON AS PRACTICAL UPON COMPLETION
ROCK CHECK DAM	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
INLET PROTECTION	WEEKLY, AFTER STORM EVENTS AND AS NEEDED	AFTER EACH INLET IS PLACED
REMOVAL OF TREE PROTECTION	N/A	AFTER PERMANENT SEEDING
REMOVAL OF STRAW BALES	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF INLET PROTECTION	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED
REMOVAL OF SILT FENCE	N/A	AFTER ALL AREAS DRAINING TO THESE AREAS ARE STABILIZED

EROSION CONTROL MEASURES MAINTENANCE REQUIREMENTS

EROSION CONTROL BLANKET (SURFACE APPLIED) MAINTENANCE REQUIREMENTS:

- DURING VEGETATIVE ESTABLISHMENT, INSPECT AFTER STORM EVENTS FOR ANY EROSION BELOW THE BLANKET.
- IF ANY AREA SHOWS EROSION, PULL BACK THAT PORTION OF THE BLANKET COVERING IT, ADD SOIL, RE-SEED THE AREA, AND RE-LAY AND STAPLE THE BLANKET.
- AFTER VEGETATIVE ESTABLISHMENT, CHECK THE TREATED AREA PERIODICALLY.

TEMPORARY GRAVEL CONSTRUCTION ENTRANCE MAINTENANCE REQUIREMENTS:

- INSPECT ENTRANCE PAD AND SEDIMENT DISPOSAL AREA WEEKLY AND AFTER STORM EVENTS OR HEAVY USE.
- RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
- TOP DRESS WITH CLEAN STONE AS NEEDED.
- IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED IF THE WATER IS CONVEYED INTO A SEDIMENT TRAP OR BASIN.
- REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.

ROCK CHECK DAM MAINTENANCE REQUIREMENTS:

- INSPECT ROCK CHECK DAMS AFTER EACH STORM EVENT AND PROMPTLY REMOVE ANY SEDIMENT DEPOSITS TO ENSURE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN, TAKING CARE NOT TO UNDERMINE THE ENTRENCHED BALES.
- INSPECT PERIODICALLY FOR DETERIORATION OR DAMAGE FROM CONSTRUCTION ACTIVITIES AND REPAIR IMMEDIATELY.
- AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE ALL ROCK CHECK DAMS AND SEDIMENT, BRING THE DISTURBED AREA TO GRADE, AND STABILIZE IT.

SILT FENCE MAINTENANCE REQUIREMENTS:

- INSPECT THE SILT FENCE PERIODICALLY AND AFTER EACH STORM EVENT.
- IF FENCE FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMEDIATELY.
- REMOVE DEPOSITED SEDIMENT WHEN IT REACHES HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT OR IS CAUSING THE FABRIC TO BULGE.
- TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEAN OUT.
- AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND SEDIMENT DEPOSITS, BRING THE DISTURBED AREA TO GRADE, AND STABILIZE.

BDC REALTY GROUP, LLC
6274 S FOX CHASE,
PENDLETON, IN 46064
CIVIL SITE GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Ph: (317) 810-1677

BRIAN S. CROSS
REGISTERED
PE 10910647
STATE OF INDIANA
PROFESSIONAL ENGINEER
DATE: 06/06/2024

DWN BY: BSC
CHKD. BY: BSC
SCALE: N/A
DATE: 06/06/24

SHOPS in VILLAGES at BROOKSIDE BLOCK A
CR 600 W
McCORDSVILLE, IN 46055
STORMWATER POLLUTION PREVENTION PLAN NOTES

PROJECT NUMBER
BRG.006
DRAWING NUMBER
C4.1
SHEET 6 OF 24

TOPOGRAPHIC & BOUNDARY NOTE

ALL EXISTING HORIZONTAL AND VERTICAL INFORMATION HAS BEEN SHOWN PER A TOPOGRAPHIC SURVEY DATED 03/11/2024 PREPARED BY CROSSROAD ENGINEERS, P.C.; THEREFORE, CIVIL SITE GROUP, INC. CANNOT BE HELD RESPONSIBLE IF ACTUAL HORIZONTAL AND VERTICAL DATA IS DIFFERENT FROM THAT SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF ALL EXISTING CONDITIONS PRIOR TO COMMENCING WITH CONSTRUCTION.

UTILITY CROSSINGS UNDER PAVEMENT

ALL UTILITY CROSSINGS UNDER PAVEMENT MUST BE JACK & BORE OR DIRECTIONAL DRILLED. OPEN CUTS SHALL NOT BE PERMITTED.

NOTE

UTILITY WORK WITHIN THE EXISTING RIGHT-OF-WAY OR WITHIN 5' OF EXISTING R/W PAVEMENT REQUIRES FLOWABLE FILL.

FLOOD NOTE

THIS LOT LIES ENTIRELY IN FLOOD HAZARD ZONE "X" AS SCALED FROM THE FLOOD INSURANCE RATE MAP (FIRM) FOR HANCOCK COUNTY, INDIANA, COMMUNITY NUMBER 180408, MAP NUMBER 1805000160, PANEL NUMBER 0016 D, DATED DECEMBER 4, 2007.

REFERENCE NFIP FIRM MAP #18059C0016D, EFFECTIVE DATE: DECEMBER 4, 2007

UTILITY VALVE NOTE

ALL UTILITY VALVES AFFECTED BY CONSTRUCTION SHALL BE ADJUSTED TO FINAL GRADE AS NEEDED TO BE FLUSH WITH FINISHED PAVEMENT, SIDEWALK OR LANDSCAPE AREA.

UTILITY LOCATE NOTE

INDIANA 811 FAILED TO LOCATE ALL EXISTING UTILITIES ON AND/OR SURROUNDING THE SUBJECT SITE; THEREFORE, CONTRACTOR IS RESPONSIBLE TO LOCATE AND FIELD VERIFY ANY EXISTING UTILITIES BEFORE COMMENCING WITH CONSTRUCTION. CIVIL SITE GROUP, INC. CANNOT BE HELD RESPONSIBLE IF THE PROPOSED IMPROVEMENTS INTERFERE WITH ANY EXISTING UTILITY INFORMATION NOT SHOWN ON THESE PLANS.

IRRIGATION NOTE

SITE IRRIGATION IS NOT SHOWN ON THESE PLANS. IF SITE IRRIGATION IS REQUIRED, CONTRACTOR SHALL WORK WITH THE LOCAL WATER UTILITY TO DETERMINE THE REQUIREMENTS & LOCATION FOR THE IRRIGATION METER & SITE IRRIGATION SYSTEM.



NOTE

REFER TO ARCHITECTURAL & FOUNDATION PLANS FOR ALL BUILDING DIMENSIONS.



GENERAL NOTES

- TEMPORARY TRAFFIC CONTROL DURING CONSTRUCTION TO CONFORM TO APPLICABLE LOCAL AND STATE STANDARDS.
- ALL CONSTRUCTION ACTIVITY ON THIS SITE TO BE PERFORMED IN COMPLIANCE WITH APPLICABLE O.S.H.A. STANDARDS FOR WORKER SAFETY.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL UTILITY LOCATIONS & DEPTHS BEFORE CONSTRUCTION BEGINS.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING ELEVATIONS BEFORE CONSTRUCTION BEGINS.



LEGEND:

- PROPERTY BOUNDARY
- RIGHT-OF-WAY
- PROPOSED STORM SEWER
- PROPOSED STORM STRUCTURE
- PROPOSED ELECTRIC SERVICE
- PROPOSED TELECOM SERVICE
- PROPOSED GAS SERVICE
- PROPOSED RPM - BLUE REFLECTOR
- PROPOSED PRIMARY 3Ø DUKE ENERGY ELECTRIC TRANSFORMER
- KICKER, PLUG, TEE, BEND FITTING
- GATE VALVE
- HYDRANT WITH HYDRANT VALVE
- 6" SAN. LATERAL CLEANOUT--CLEANOUTS INSTALLED IN PAVED AREAS MUST HAVE A HEAVY DUTY CASTING TO WITHSTAND TRAFFIC LOADING. REFER MCCORDSVILLE DETAIL SHEETS 8-10

PLAN NOTES:

- (A) LIGHT POLE FOUNDATION (REFER TO LIGHTING PLAN)
- (B) PEDESTRIAN BOLLARD LIGHT (REFER TO LIGHTING PLAN)
- (UX) UTILITY CROSSING
- (L1) 67± LF OF 6-INCH SDR35 PVC (ASTM D-3034) @ 1.04% MIN. WITH TRACER WIRE ATTACHED PER MCCORDSVILLE STDS. REFER MCCORDSVILLE DETAIL SHEETS 8 & 9
- (CC) CONCRETE CRADLE REQ'D. BETWEEN PIPES
- (18) 10 FOOT HORIZONTAL & 18-INCH VERTICAL SEPARATION REQ'D. BETWEEN SEWER (SANITARY OR STORM) & WATER SERVICE LINES
- (UT) PROPOSED 800A 3Ø 120/208V ELECTRIC TRANSFORMER
- (FH) WET TAP NEW HYDRANT BRANCH OFF EXISTING WATER MAIN PER CEG STDS. REFER TO CEG STD. PRACTICE B
- (M) 3/4-INCH METER PIT PER CEG STDS. REFER TO CEG STD. PRACTICE T
- (M1) 1-INCH METER PIT PER CEG STDS. REFER TO CEG STD. PRACTICE T
- (1) 1-INCH I.D. COMMON DOMESTIC WATER SERVICE LINE
- (2) 2-INCH I.D. COMMON DOMESTIC WATER SERVICE LINE REFER TO CEG STD. PRACTICE N
- (T) TELECOM SERVICE - 4-INCH PVC CONDUIT (QTY 2)

UTILITY NOTES

- IT SHALL BE THE RESPONSIBILITY OF EACH CONTRACTOR TO VERIFY ALL EXISTING UTILITIES AND CONDITIONS PERTAINING TO THEIR PHASE OF WORK. IT SHALL ALSO BE THE CONTRACTORS RESPONSIBILITY TO CONTACT THE OWNERS OF THE VARIOUS UTILITIES FOR PROPER STAKE LOCATIONS FOR EACH UTILITY BEFORE WORK IS STARTED. THE CONTRACTOR SHALL NOTIFY IN WRITING THE OWNER OR THE ENGINEER OF ANY CHANGES, OMISSIONS, OR ERRORS FOUND ON THESE PLANS OR IN THE FIELD BEFORE WORK IS STARTED OR RESUMED.
- STANDARD SPECIFICATIONS FOR THE LOCAL GOVERNING AGENCY SHALL APPLY FOR ALL SANITARY SEWERS, STORM SEWERS, AND WATER MAINS.
- ANY PART OF THE SANITARY OR STORM SEWER TRENCHES RUNNING UNDER PAVED AREAS TO BE BACKFILLED WITH GRANULAR MATERIAL.
- ALL WATER MAINS TO HAVE 60" MINIMUM COVER OVER TOP OF PIPE.
- STERILIZATION OF WATER MAIN SHALL BE IN ACCORDANCE WITH STATE BOARD OF HEALTH REQUIREMENTS. (APPLIES TO COMMERCIAL ONLY)
- CONTRACTOR RESPONSIBLE TO INSTALL ALL UNDERGROUND CONDUIT PER UTILITY COMPANY'S SPECIFICATIONS.
- CONTRACTOR RESPONSIBLE FOR RESTORATION TO ALL AREAS AFFECTED DURING CONSTRUCTION. REFER TO THE TOWN OF FISHERS STANDARDS FOR RESTORATION REQ'S.
- CONTRACTOR TO LOCATE ALL EXISTING UTILITIES AT ANY PROPOSED CROSSING AND PROVIDE EXISTING TOP-OF-PIPE ELEVATIONS WITHIN 10 DAYS OF NOTICE TO PROCEED. PROVIDE CONCRETE CRADLE AS REQUIRED FOR ANY VERTICAL SEPARATION LESS THAN 18 INCHES.

SEWER LATERAL BACKFILL

FULL DEPTH GRANULAR BACKFILL IS REQ'D. UNDER ALL PAVEMENT. REFER TO MCCORDSVILLE DETAILS SHEETS 9 & 10

SITE LIGHTING NOTE

SITE LIGHTING IS NOT SHOWN ON THESE PLANS. 2-1/2" CONDUITS (SITE LIGHTING & SECURITY) REQUIRED TO ALL PARKING LOT LIGHT POLE LOCATIONS. ALL CONDUIT RUNS SHALL BE TRENCHED INSTALLED WITH COMPACTED GRANULAR BACKFILL TO PAVEMENT SUBGRADE - FLOWED OR BAKED INSTALLATION OF CONDUITS ARE PROHIBITED

CITIZENS ENERGY NOTES:

Domestic Water / Fire Service:

- All work must be completed by a bonded Contractor according to Section 1.13 of the Water Standards.
- The water/fire service permit cannot be approved until the sanitary lateral permit has been approved.
- Please note that open cutting the asphalt path and the method of restoration is subject to the City's approval, not Citizens.

Service Line Requirements:

- Ensure that a minimum of a 10' horizontal separation and an 18" vertical separation between sewer lines (sanitary or storm) and the water service lines is maintained.
- A sewer and water crossing must be at a minimum of 45 degrees.

Domestic Service:

- Please note that copper or ductile iron pipe must be run from 5 feet outside of the building footer into the building to the meter setup.
- Please note that open cutting the asphalt path and the method of restoration is subject to the City's approval, not Citizens.


Fire Service:

Please submit for a hydrant flow request:

<https://www.citizensenergygroup.com/For-Partners/Contractors-Builders/Permits-and-Forms/Hydrant-Flow-Test>

Sanitary Sewer Lateral Service:

- Full depth granular backfill required under pavement. Refer to Fig 400.01 on Sheet C7.3.
- Ensure that a minimum of a 10' horizontal separation and an 18" vertical separation between sewer lines (sanitary or storm) and the water service lines is maintained
- Sewer lateral and utility crossings must be at a minimum of 45 degrees horizontal.
- Cleanouts installed in paved areas must have a heavy duty casting to withstand traffic loading. Refer to Fig 400.10 on Sheet C7.3.
- Tracer wire required to be attached to sewer laterals per Citizens Westfield Stds.



SHOPS in VILLAGES at BROOKSIDE BLOCK A

CR 600 W

MCCORDSVILLE, IN 46055

UTILITY PLAN

BDC REALTY GROUP, LLC

6274 S FOX CHASE

PENDLETON, IN 46064

CIVIL SITE GROUP, INC.

718 Adams Street, Suite E

Carmel, Indiana 46032

Ph: (317) 810-1677



DWN BY: BSC


CHKD. BY: BSC

SCALE: 1" = 30'

DATE: 06/06/24

PROJECT NUMBER
BRG.006

DRAWING NUMBER
C5.0
SHEET 8 OF 24



BDC REALTY GROUP, LLC
6274 S FOX CHASE
PENDLETON, IN 46064

CIVIL SITE GROUP, INC.
718 Adams Street, Suite E
Carmel, Indiana 46032
Ph: (317) 810-1677

BRIAN S. CROSS
REGISTERED
PE 10910647
STATE OF INDIANA
PROFESSIONAL ENGINEER
DATE: 06/06/2024





DWN BY:	BSC
CHKD. BY:	BSC
SCALE:	1" = 30'
DATE:	06/06/24

SHOPS in VILLAGES at BROOKSIDE BLOCK A
CR 600 W
McCordsville, IN 46055


GENERAL DETAILS

PROJECT NUMBER
BRG.006

DRAWING NUMBER
C7.0
SHEET 9 OF 24



DIMENSIONS (INCHES)		
A (MAX.)	B (I.D.)	C (MIN.)
18	48	25
21	48	28
24	48	31
27	60	34
30	60	38
33	60	41
36	60	44
42	60	50

BDC REALTY GROUP, LLC 6274 S FOX CHASE PENDLETON, IN 46064	CIVIL SITE GROUP, INC. 718 Adams Street, Suite E Carmel, Indiana 46032 Ph: (317) 810-1677	civilsite GROUP, INC.
 <i>Bryan S. Cross</i> DATE: 06/06/2024		
DWN BY: BSC CHKD. BY: BSC SCALE: N/A DATE: 06/06/24		
SHOPS in VILLAGES at BROOKSIDE BLOCK A CR 600 W MCCORDSVILLE, IN 46055	GENERAL DETAILS	
PROJECT NUMBER BRG.006		
DRAWING NUMBER C7.1		

				REVISION RECORD				
				REV	DATE	DESCRIPTION	DES BY	APP BY
EARTHWORK								
1. SCOPE OF WORK								
A. Extent: The work required under this section consists of all excavating, filling, rough grading and related items necessary to complete the work indicated on the drawings and described in the specifications. The Contractor shall notify in writing the owners and the Engineer of any changes, errors or omissions found on the plans or in the field before work is started or resumed.								
1. In general, the items of work to be performed under this section shall include: clearing and grubbing, removal of trees and stumps (where required), protection of trees to remain, stripping and storage of topsoil, fill compaction and rough grading of entire site.								
2. Excavated material that is suitable may be used for fills. All unsuitable material and all surplus excavated material not required shall be removed from the site. The location of dump and length of haul shall be the Contractor's responsibility.								
3. Provide and place any additional fill material from off the site as may be necessary to produce the grades required. Fill obtained from off site shall be of kind and quality as specified for fills herein and the source approved by the Owner.								
4. The Contractor shall accept the site as he finds it and shall remove all trees and debris from the site prior to starting excavation.								
B. Work not included: The following items of related work are specified and included in other sections of these specifications:								
1. Excavation, grading and backfilling for utility lines								
2. Storm drainage systems								
3. Sanitary sewer systems								
4. Streets and paving								
5. Water supply system								
2. BENCH MARKS								
Maintain carefully all bench marks, monuments and other reference points; if disturbed or destroyed, Contractor shall contact engineer. Replacement shall be at Contractor's expense.								
3. REMOVAL OF TREES								
A. Remove all trees and stumps from area to be occupied by road and surfaced areas. Removal of trees outside these areas shall only be done as noted on drawings or approved by the Owner.								
B. All brush, stumps, wood and other refuse from the trees shall be removed to disposal areas off of the site. Disposal by burning shall not be permitted unless proper permits are obtained (where applicable). These trees and stumps shall be removed by the owner and the Engineer if permitted.								
4. PROTECTION OF TREES								
A. General Protection: The Contractor shall be responsible for the protection of tops, trunks and roots of existing trees on the project site that are to remain. Existing trees subject to construction damage shall be boxed, fenced or otherwise protected before any work is started; do not stockpile within branch spread. Remove interfering branches without injury to trunks and cover scars with tree paint.								
5. HANDLING OF TOPSOIL								
A. Remove all organic material from the areas to be occupied by buildings, roads, walks and parking areas. Pile and store topsoil at a location where it will not interfere with construction operations. Topsoil shall be reasonably free from subsoil, debris, weeds, grass, stones, etc..								
B. After completion of site grading and subsurface utility installation, top soil shall be replaced in areas designated on the erosion control plan for seeding and/or sod. Any remaining topsoil shall be used for finished grading ground structures and landscaping areas.								
6. DISPOSITION OF UTILITIES:								
A. Rules and regulations governing the respective utilities shall be observed in executing all work under this section.								
B. If active utilities are encountered but not shown shown on the drawings, the Engineer shall be advised before work is continued.								
C. Inactive and abandoned utilities encountered in excavating and grading operations shall be reported to the Engineer. They shall be removed, plugged or capped as directed by the Utility Company or the Engineer.								
D. It shall be the responsibility of each contractor to verify all existing utilities and conditions pertaining to his phase of the work. It shall also be the contractors responsibility to contact the owners of the various utilities before work is started.								
7. SITE GRADING:								
A. Grades: Contractor shall perform all cutting, filling, compacting of fills and rough grading required to bring entire project area to grade as shown on the drawings.								
B. Rough Grading: the tolerance for paved areas shall not exceed 0.10 feet plus or minus above the established subgrade. All other areas shall not exceed 0.10 feet plus or minus the established grade. All banks and other breaks in grade shall be rounded at top and bottom.								
C. Compaction Requirements:								
1. All areas under building pads and paved areas shall be compacted to 95% standard proctor density.								
2. All other fill areas shall be compacted to 90% standard proctor density.								
3. All areas where cut is necessary to meet the condition of all sub-grade are required to be scarified 12 inches below sub-grade and meet the above compaction requirements.								
8. EARTH WORK BALANCE								
A. The Contractor shall confirm all earthwork quantities prior to start of construction. If an excess or shortage of earth is encountered, the Contractor shall confirm with the Owner and Engineer the requirements for stockpiling, removal or importing of earth.								
B. Minor adjustments to the grades may be required to earthwork balances when minor excess material or shortages are encountered. It is recognized by the parties hereto that the calculations of the Engineer in determining earthwork quantities shall be accomplished in accordance with the American Society of Civil Engineers Standards for such calculations. Further, that these calculations are subject to the interpretations of soil borings as the physical limits of the various soil types, the allowable variation in finish grade and compaction permitted the contractor, and that all of these parameters may cause either an excess or shortage of actual earthwork materials to complete the project. If such an actual minor excess or shortage of materials occurs, the contractor shall contact the Engineer to determine if adjustment can be made to correct the imbalance of earth.								
9. TESTING								
A. Contractor shall hire at Contractors expense an independent soil testing service to assure soil compaction with scope of testing to be approved by the Engineer. Copies of test results shall be submitted to the Engineer.								
SANITARY SEWER SYSTEMS								
1. SCOPE OF WORK								
A. The work under this section includes all sanitary sewers, manholes, cleanouts and related items including excavating and backfilling, necessary to complete the work shown in the drawings, starting five feet outside the building walls. The ends of sewers shall be tightly plugged or capped at the terminal points, adjacent to buildings, pending the connection of all other lines to the building drain as specified in the plumbing and architectural drawings. One set of "approved" plans shall be on the job site at all times.								
2. MATERIALS								
A. Polyvinyl Chloride Pipe (PVC)								
1. 6"-15" PVC pipe shall be SDR 35 and conform to ASTM D3034, with a minimum cell classification of 12454 or 12364. Greater than 15" PVC pipe shall conform to ASTM F679, with a minimum cell classification of 12454-C.								
2. All fittings and joints shall be compression type flexible gasketed joints, and manufactured and installed in accordance with the pipe manufacturer's specifications. No solvent cement joints shall be allowed.								
B. Ductile Iron Pipe								
1. Ductile iron (DI) pipe must meet ASTM A-746 or AWWA C151 with exterior asphaltic coating per AWWA C151 and interior asphaltic coating meeting AWWA C151 or polyethylene lining complying with ASTM D-1248 of nominal 40 mil thickness. Thickness design must be in accordance with AWWA C150.								
2. Joint on DI pipe must be the integral bell type gasketed joint meeting AWWA C111 mechanical joint (MJ) meeting AWWA C111, or ANSI 125 lb. flanged joint. Accessories for mechanical and flanged joints must be alloy steel. T-b-head bell and hex nut of Coarse Thread Series Class 2A (External) and Class 2B (Internal) per ANSI B1.1.								
C. Manholes								
1. Precast reinforced concrete manhole sections and steps and concrete adjusting rings shall conform to ASTM C-478 latest revision. Exterior of manhole shall be waterproofed with Bismatic material.								
2. Castings shall be of uniform quality, free from blow holes, porosity, hard spots, shrinkage distortion or other defects. They shall be smooth and well-cleaned by shot-blasting or by some other approved method. They shall be coated with asphalt paint which shall result in a smooth coating, tough and tenacious when cold, not tacky or brittle. They shall be gray iron meeting ASTM A-48 latest revision. Manhole covers for sanitary sewer shall be Neshen Type B-1077-A w/R-1712-B-SF frame w/Self-Sealing application.								
3. Joints - Manhole sections shall be joined with a nominal 1/2" size butyl rubber rubber base gasket material, conforming to AASHTO M-198 and Federal Specification 33S-5-210a. Joint conforms to ASTM C-443.								
4. Manholes shall include steps. Manhole steps shall be polypropylene coated steel reinforcing or an approved non-corrosive fiberglass material. The copolymer polypropylene shall meet the requirements of ASTM D-4101 with deformed 3/8" dia. or larger reinforcing steel conforming to ASTM A-615; Grade 60. Steps shall be a maximum of 18" from top, 24" from bottom and 16" spacing between.								
5. Manholes shall be bedded on a granular foundation. The granular foundation shall be compacted with vibratory tamps.								
3. APPLICATION								
A. Permits and Codes - The intent of this section of the specifications is that the contractor's bid on the work covered herein shall be based upon the drawings and specifications but that the work shall comply with all applicable codes and regulations as amended by any waivers. Contractor shall furnish all bonds necessary to get permits for cuts and connections to existing sewers.								
B. Local Standards - The term "local standards" as used herein means the standards of design and construction of the respective municipal department or utility company.								
C. Existing Improvements - Maintain in operating condition all active utilities, sewers and other drains encountered in the sewer installation. Repair to the satisfaction of the owner any damage to existing active improvements.								
D. Workmanship - To conform to all local, state and national codes and to be approved by all local and state agencies having jurisdiction.								
E. Trenching - Lay all pipe in open trenches, except when the local authority gives written permission for tunneling or jacking of pipe. Open the trench sufficiently ahead of pipe-laying to reveal any obstructions. The width of the trench shall be the inside pipe diameter plus 24 inches for 12 inches and larger pipe. Sheet and brace the trench as necessary to protect workmen and adjacent structures. All trenching to comply with Occupational Safety and Health Administration Standards. Keep trenches free from water while construction is in progress. Under no circumstances shall lay pipe or appurtenances in standing water. Conduct the discharge from trench dewatering to drains or natural drainage channels.								
F. Special Supports - Whenever, in the opinion of the Engineer, the soil at or below the pipe grade is unsuitable for supporting sewers and appurtenances specified in this section, such special support, in addition to those shown or specified, shall be provided as the Engineer may direct, and the contract will be adjusted.								
G. Backfilling - For a depth of at least 12 inches above the top of the pipe, backfill with 12" of #8 crushed stone or #8 fractured face aggregate. Compact this backfill thoroughly, taking care not to disturb the pipe. For the remaining trench depth, backfill with earth or granular material containing stones or rocks not larger than 4 inches. Backfill under and within 5' of walks, parking areas, driveways and streets shall be granular material only - thoroughly compacted, by approved methods.								
H. Flow Channels - The flow channels within manholes shall be an integral part of the precast base. The channels shall be shaped and formed for a clean transition with proper hydraulics to allow the smooth conveyance of flow through the manhole. The bench wall shall be formed to the crown of the inlet and outlet pipes to form a "U" shaped channel. The bench wall shall slope back from the crown at 1/2 inch per foot to the manhole wall. No brick, rock or sand fillers will be allowed.								
I. Infiltration - The contractor shall furnish necessary equipment to test sewers for infiltration. Infiltration rates shall not exceed the Local Standards. All sanitary sewer lines upon completion will be required to pass a low pressure air test, unless otherwise directed by the City Engineer. Soil test shall be conducted according to NCI Standard Method, and shall be witnessed by an inspector authorized by the City Engineer. Infiltration under test shall not exceed 100 gallons per inch of inside diameter of sewer pipe per mile of sewer in 24 hours and is inclusive of all appurtenances within the section being tested such as manholes, house connections, etc. Any portions not passing soil tests for acceptance shall be repaired or replaced, including re-excavation and backfill, at the Contractor's expense.								
J. Flushing Sewers - Flush all sanitary sewers except building sewer lines with high pressure water through each line. Remove all silt and trash from appurtenances just prior to acceptance of work.								
K. Plastic Sewer Pipe Installation - Plastic sewer pipe shall be installed in accordance with ASTM D2321 per latest revision, and no plastic pipe shall exceed an 11 point mandrel test deflection of 5%. All sewer mains shall be lamped at the time the mandrel test is conducted. All mains shall be true to alignment and grade.								
L. Storm Water Connections - No roof drains, footing drains and/or surface water shall be connected to the sanitary sewer systems, including temporary connections during construction.								
M. Waterline Crossing - Water and sewer line crossings and separations shall be in accordance with ten States Standards and local and state codes. Waterlines and sanitary sewers shall maintain a minimum of 10 foot horizontal separation and a minimum 18 inches vertical separation at all crossings. Otherwise, sanitary sewer within 10 feet of waterlines shall be constructed of water works grade Ductile Iron Pipe with mechanical joints and fittings. One length of sewer pipe crossing shall be centered at the waterline crossing so that no joint is closer than 10 feet to the waterline.								
N. Utilities - It shall be the responsibility of each contractor to verify all existing utilities and conditions pertaining to his phase of the work. It shall also be the contractors responsibility to contact the owners of the various utilities before work is started. The contractor shall notify in writing the owners and the engineer of any changes, errors or omissions found on the plans or in the field before work is started or resumed.								
O. Service Laterals - Individual building service lines shall be 6 inches in diameter and of material equal to that specified in 2A of this section. Service lines shall be connected to the main sewer by a wye at locations generally shown within these plans. Service lines shall be extended to a distance of 3 feet beyond the right-of-way line and within 5' of the existing ground surface. The ends shall be plugged and sealed with a water tight cap. Sewer service lines shall be marked with a 2"x4" painted green and extending from the lateral end to 3' above grade.								
P. New Sanitary Sewer Main Construction - Contractor shall record length and dimensions of each service line stub from nearest downstream manhole measure along the sanitary sewer main. The locations of manholes and service lines along with any other construction changes are to be incorporated on the original construction drawings as "as-built" locations and submitted to the Engineer as soon after completion of construction as possible, not to exceed 30 days.								
Q. Field Testing - All manholes must be vacuum tested after installation, repair or modification in accordance with ASTM C1244-93, Standard Test Method for Concrete Sewer Manholes by Negative Air Pressure (Vacuum) Test.								
R. Local Standards - The term "local standards" as used herein means the standards of design and construction of the respective municipal department or utility company.								
C. Existing Improvements - Maintain in operating condition all active utilities, sewers and other drains encountered in the sewer installation. Repair to the satisfaction of the owner any damage to existing active improvements.								
D. Workmanship - To conform to all local, state and national codes and to be approved by all local and state agencies having jurisdiction.								
STORM SEWER SYSTEMS								
1. SCOPE OF WORK								
The work under this section includes all storm sewers, storm water inlets, and related items, including excavating and backfilling, necessary to complete the work shown on the drawings. All work and materials shall meet local specifications.								
2. MATERIALS								
A. Storm Sewers								
1. Reinforced concrete sewer pipe shall conform to ASTM C-76 latest revision, with joints conforming to ASTM C-443 latest revision when storm pipe is located within public right-of-way.								
2. Aluminized type 2 corrugated steel pipe shall be manufactured in accordance with AASHTO M36 (type I) with 2 2/3" x 1/2" corrugations for 12" and 15" diameters; type II with 3/4" x 3/4" x 1 1/2" corrugations for 18" diameter and larger). The pipe shall be formed from an aluminized steel type 2 coil that conforms to AASHTO M274. The minimum gage thickness of the pipe shall be as follows:								
Diameter Gage								
12" - 36" 16								
36" - 48" 14								
54" - 84" 12								
3. High density polyethylene pipe shall perform in accordance with AASHTO M252 and M294 type specifications, latest revision, and shall have material specifications conforming to ASTM D1248 or D3350, latest revision.								
B. Manholes								
1. Precast reinforced concrete manhole sections and steps shall conform to ASTM C-478 latest revision.								
2. Casting shall be of uniform quality, free from blow holes, porosity, hard spots, shrinkage distortion or other defects. They shall be smooth and well cleaned by shot-blasting or by some other approved method. They shall be coated with asphalt paint which shall result in a smooth coating, tough and tenacious when cold, not tacky or brittle. They shall be gray iron meeting ASTM A-48 latest revision.								
3. Joints - Manhole sections shall be jointed with rubber type gaskets. The rubber type gaskets shall meet ASTM C-443 latest revision. When manhole and storm pipe are continuously in water.								
4. Shop Drawings - Contractor to submit storm sewer structure precast drawings to engineer for approval prior to installation.								
C. SUBDRAINS								
1. Perforated plastic pipe subdrains shall conform to ASTM F-405, AASHTO M-252 (4" to 10" pipe).								
3. APPLICATION								
A. Permits and Codes - The intent of this section of the specifications is that the contractor's bid on the work covered herein shall be based upon the drawings and specifications but that the work shall comply with all applicable codes and regulations as amended by any waivers. Contractor shall furnish all bonds necessary to get permits for cuts and connections to existing sewers. The contractor shall notify the local governing jurisdiction a minimum of 72 hours prior to the commencement of storm sewer construction.								
B. Local Standards - The term "Local Standards" as used herein means the standards of design and construction of the respective municipal department or utility company.								
C. Existing Improvements - Maintain in operating condition all active utilities, sewers and other drains encountered in the sewer installation. Repair to the satisfaction of the owner any damage to existing active improvements.								
D. Workmanship - To conform to all local, state and national codes and to be approved by all local and state agencies having jurisdiction.								
E. Trenching - Lay all pipe in open trenches, except when the local authority gives written permission for tunneling. Open the trench sufficient ahead of pipe laying to reveal any obstructions. The width of the trench shall be the inside pipe diameter plus 24 inches for 12 inches and larger pipe. Sheet and brace the trench as necessary to protect workmen and adjacent structures. All trenching to comply with Occupational Safety and Health Administration Standards. Keep trenches free from water while construction is in progress. Under no circumstances shall lay pipe or appurtenances in standing water. Conduct the discharge from trench dewatering to drains or natural drainage channels.								
F. Special Supports - Whenever in the opinion of the Engineer, the soil at or below the pipe grade is unsuitable for supporting sewers and appurtenances specified in this section, such special support, in addition to those shown or specified, shall be provided as the Engineer may direct, and the contract will be adjusted.								
G. Backfilling - For a depth of at least 12 inches above the top of the pipe, backfill with earth or granular material free from large stones, rock fragments, roots or sod. Tamp this backfill thoroughly, taking care not to disturb the pipe. For the remaining trench depth, backfill with earth or granular material containing stones or rocks not larger than 4 inches. Backfill under and within 5' of paved areas shall be granular material only and shall conform to local standards and be thoroughly compacted by approved methods.								
H. Manhole Inverts - Construct manhole flow channels of concrete sewer pipe or brick, smoothly finished and of semicircular section conforming to the inside diameter of the connecting sewers. Make changes in size or grade gradually and changes in direction by true curves. Provide such channels for all connecting sewers at each manhole.								
I. Subdrains - All subdrains shall be of the size shown on the plans and shall be constructed to the grades shown. All drains constructed off-site as part of the outlet drain will be located as shown.								
J. Utilities - It shall be the responsibility of each contractor to verify all existing utilities and conditions pertaining to his phase of the work. It shall also be the contractors responsibility to contact the owners of the various utilities before work is started. The contractor shall notify in writing the owners of any changes, errors or omissions found on these plans or in the field before work is started or resumed.								
STREETS AND PAVING								
1. SCOPE OF WORK								
A. The work required under this section includes all concrete and bituminous paving and related items necessary to complete the work indicated on drawings and described in the specifications, including but not limited to:								
All streets, parking areas in contract limits								
Curbs and gutters.								
Sidewalks and concrete slabs, exterior steps.								
2. MATERIALS								
A. Concrete - Concrete shall be ready-mixed concrete and shall be a mix of proportioned fine and coarse aggregates with Portland cement and water. Minimum cement content shall be 6 bags per cubic yard of concrete and maximum water content shall be 5.5 U.S. gallons per sack of cement, including moisture in the aggregate. Slump for normal weight concrete shall be a maximum of 4 inches and a minimum of 2 inches. The slump of machine place concrete shall be no less than 1-1/4 inches nor more than 3 inches. Standard test ASTM C-143 shall be used to measure slump. Compressive strength of concrete at 28 days shall be 4000 psi. All exterior concrete shall have air entrainment of 5% to 8% by volume per ASTM C-260. Retempering delivered concrete will not be allowed. Concrete shall be composed of:								
1. Portland cement - Conforming to ASTM C-150, Type IA or Type IIIA.								
2. Aggregates: Conforming to ASTM C-33								
3. Water - Shall be clear and free from injurious amounts of oils, acids, alkalis, organic materials or other deleterious substances.								
B. Welded Steel Wire Fabric - Where required for concrete reinforcement shall conform to ASTM A185.								
C. Premoulded Joint Filler - Shall be of non-extruding type meeting ASTM D-544 except that premoulded joint filler used in concrete work construction may be either non-extruding or resilient.								
D. Bituminous Pavement Materials - All materials proposed for the construction of bituminous pavements shall comply with the Indiana Department of Transportation specifications, per latest revision.								
E. Compacted Aggregate Subbase: Shall be crushed stone or gravel. Crushed gravel shall be a minimum of 35% crushed material. Chert shall be limited to a maximum of 8% of the total. Material shall be free from an excess of flat, elongated, thinly laminated, soft or disintegrated pieces; and shall be free from fragments coated with dirt. Compacted aggregate shall be graded as follows:								
SIEVE SIZE % PASSING								
1 1/2" 100								
3/4" 80-100								
3/4" 70-90								
1 1/2" 55-80								
3/4" 35-60								
1/2" 25-50								
3/8" 12-30								
#200 5-10								
3. APPLICATION								
A. Grading - Do any necessary grading in addition to that performed in accordance with Earthwork Section, to bring subgrades, after final compaction, to the required grades and sections for site improvement.								
B. Preparation of Subgrade - Remove spongy and otherwise unsuitable material and replace with stable material. No traffic will be allowed on prepared subgrade prior to paving.								
C. Compaction of Subgrade - The first 12 inches below the subgrade shall be compacted to at least 100% of the maximum dry density as determined by the provisions of AASHTO T-99. Water shall be prevented from standing on the compacted subgrade. A qualified geotechnical engineer shall be retained by contractor to observe and document a subgrade proof roll (Tri-Axle Truck loaded with aggregate). Contractor shall mediate all areas that fail proof roll and re-test as needed until passed by geotechnical engineer.								
D. Compacted Aggregate Subbase - The thickness shown on the drawings is the minimum thickness of the fully compacted subbase. Compaction shall be accomplished by rolling with a smooth wheeled roller weighing 8 to 10 tons. Compact to 95% standard proctor density (ASTM D698) Along curbs, headers and walls and at all placed not accessible to the roller, the aggregate material shall be tamped with mechanical tampers or with approved hand tampers.								
E. Bituminous Pavement - Hot asphalt concrete pavement shall be as specified in Section 400-410 of the Indiana Department of Transportation Specifications latest revisions. Paving will not be permitted during unfavorable weather or when the temperature is not in compliance with section 401.05 of the INDOT Specifications.								
F. Utility Structures - Check for correct elevation of all manhole covers, valve boxes and similar structures located within areas to be paved, and make, or have made, any necessary adjustments in such structures.								
G. Placing Concrete								
1. Subgrade - Place concrete only on a moist, compacted subgrade or base free from loose material. Place no concrete on a muddy or frozen subgrade.								
2. Forms - All forms shall be free from warp, tight enough to prevent leakage and substantial enough to maintain their shape and position without springing or settling when concrete is placed. Forms shall be clean and smooth and coated with form release before placement of concrete.								
3. Placing Concrete - Concrete shall be deposited so as to require as little rehandling as practicable. When concrete is to be placed at an atmospheric temperature of 35 degrees F. or less, paragraph 702.10 of the Indiana Department of Transportation Specifications latest revision shall be followed.								
H. Concrete Curb								
1. Expansion Joints - Shall be 1/2 inch thick premonoluted at ends of all returns and at a maximum spacing of 100 feet.								
2. Contraction Joints - Unless otherwise provided, contraction joints shall be sawed joints spaced 20 feet on center.								
3. Finish - Tamp and screed concrete as soon as placed, and fill any honey combed places. Finish square corners to 1/4" radius and other corners to radii shown.								
I. Concrete Walks and Exterior Steps								
1. Slopes - Provide 1/4 inch per foot cross slope. Make adjustments in slopes at walk intersections as necessary to provide proper drainage.								
2. Dimensions - Walks and steps shall be one course construction and of widths and details shown on the drawings.								
3. Finish - Screed concrete and trowel with a steel trowel to a hard dense surface after surface water has disappeared. Apply medium broom finish and scrub concrete with 1/2 foot spacing. Provide 1/2" expansion joints								



VILLAGES AT BROOKSIDE SECTION 16 SECONDARY PLAT

A PART OF THE NORTHEAST QUARTER (1/4) OF SECTION 23, TOWNSHIP 17 NORTH,
RANGE 5 EAST, VERNON TOWNSHIP, HANCOCK COUNTY, MCCORDSVILLE, INDIANA
DEDICATED RIGHT-OF-WAY IN THIS SUBDIVISION CONSISTS OF 0.443 ACRES

OWNER
KS REAL ESTATE HOLDINGS, LLC
2700 WEST MAIN STREET
GREENFIELD, IN 46140
PHONE: (317) 468-2515
CONTACT: KEITH WHITE
EMAIL: keith.white@prideip.com

OWNER
VERNON TOWNSHIP BUILDING CORPORATION
602 VITALITY DRIVE
FORTVILLE, IN 46040
PHONE: (317) 485-7327
CONTACT: FLORENCE MAY
EMAIL: trustee@vernontownship.us

LEGEND

- PROPERTY LINE
- PROP. LOT LINE
- PROP. RIGHT-OF-WAY
- SECTION LINE
- PROP. SETBACK LINE
- PROP. EASEMENT LINE
- ADJACENT LOT LINE
- EX. EASEMENT LINE

- TEMP. BENCHMARK
- RW FYS FRONT YARD SETBACK
- PIPE WITH CAP "GWCHARLES LS0800117" SET FLUSH
- MONUMENT FOUND
- PERMANENT OUTSIDE BOUNDARY CORNER SET 1"X36" PIPE [1.0#/1R] WITH CAP "GWCHARLES LS0800117" IN CONCRETE
- PERMANENT PROPERTY LOT CORNER SET 1"X36" PIPE [1.0#/1R] WITH CAP "GWCHARLES LS0800117"

BOUNDARY LINE TABLE

BL1	N72°37'49"E 104.85'
BL2	N89°15'25"E 667.31'
BL3	S87°46'42"E 193.34'
BL4	N89°15'25"E 389.59'
BL5	S17°40'28"E 22.31'
BL6	S00°07'23"W 229.66'
BL7	S03°27'12"E 262.98'
BL8	S00°07'23"W 522.91'

INGRESS/EGRESS EASEMENT TABLE

Line #	Direction	Length
IE1	N89°15'25"E	67.69'
IE2	N00°07'23"E	55.54'
IE3	S89°52'37"E	67.18'
IE4	N00°07'23"E	75.00'
IE5	S89°52'37"E	50.50'
IE6	N00°07'23"E	140.51'
IE7	N89°52'37"W	74.50'
IE8	S00°07'23"W	64.52'
IE9	N89°52'37"W	12.00'
IE10	S00°07'23"W	115.98'
IE11	N89°52'37"W	71.18'
IE12	S00°07'23"W	89.65'

PEDESTRIAN EASEMENT TABLE

Line #	Direction	Length
PE1	S89°14'42"W	10.00'
PE2	N00°07'23"E	492.88'
PE3	N05°34'44"W	146.22'
PE4	N00°07'23"E	60.05'
PE5	N04°59'38"W	43.50'
PE6	N00°00'00"E	237.03'
PE7	N54°30'41"W	38.31'
PE8	S89°07'46"W	324.55'
PE9	N00°07'23"E	5.00'
PE10	N89°07'46"E	334.54'

EXISTING EASEMENT TABLE

ITEM 1	EASEMENT IN FAVOR OF: INDIANAPOLIS WATER COMPANY; TYPE OF EASEMENT: UNDERGROUND WATER MAIN; RECORDED: SEPTEMBER 24, 1997; INSTRUMENT NO. 9700779.
ITEM 2	EASEMENT IN FAVOR OF: TOWN OF MCCORDSVILLE; TYPE OF EASEMENT: SANITARY SEWER; RECORDED: OCTOBER 22, 1999; INSTRUMENT NO. 9914251.
ITEM 3	EASEMENT IN FAVOR OF: TOWN OF MCCORDSVILLE; TYPE OF EASEMENT: SANITARY SEWER; RECORDED: OCTOBER 24, 2000; INSTRUMENT NO. 2011358.
ITEM 4	EASEMENT IN FAVOR OF: HANCOCK RURAL TELEPHONE CORPORATION D/B/A HANCOCK TELECOM AND HANCOCK COUNTY RURAL ELECTRIC MEMBERSHIP CORPORATION D/B/A CENTRAL INDIANA POWER; TYPE OF EASEMENT: TELECOMMUNICATIONS AND ELECTRIC TRANSMISSION FACILITIES; RECORDED: MARCH 28, 2001; INSTRUMENT NO. 0103594.
ITEM 5	EASEMENT IN FAVOR OF: HANCOCK RURAL TELEPHONE CORPORATION D/B/A HANCOCK TELECOM AND HANCOCK COUNTY RURAL ELECTRIC MEMBERSHIP CORPORATION D/B/A CENTRAL INDIANA POWER; TYPE OF EASEMENT: TELECOMMUNICATIONS AND ELECTRIC TRANSMISSION FACILITIES; RECORDED: MARCH 28, 2001; INSTRUMENT NO. 0103595.
ITEM 6	ACCESS, DRAINAGE AND SEWER EASEMENT AGREEMENT, BY AND BETWEEN PKCW OLIO 86 PARTNERS, LLC AND GRAND COMMUNITIES, LTD., RECORDED JANUARY 18, 2011, AS INSTRUMENT NUMBER 110000683.
ITEM 7	EASEMENT IN FAVOR OF: TOWN OF MCCORDSVILLE; TYPE OF EASEMENT: SEWER MAINS; RECORDED: FEBRUARY 4, 2011; INSTRUMENT NO. 110001282.


RIGHT OF WAY DEDICATION TABLE		
Line #	Direction	Length
R1	S89°14'42"W	14.51'
R2	N00°07'23"E	493.18'
R3	N04°06'25"W	249.57'
R4	N00°00'00"E	241.74'
R5	N54°30'41"W	70.18'
R6	N87°07'02"W	174.67'

TOTAL DEDICATED RIGHT-OF-WAY
0.443 ACRES

DULY ENTERED
FOR TAXATION


SEP 26 2022

Debra A. Carnes
Auditor of Hancock County



VILLAGES AT BROOKSIDE
SECTION 16
SECONDARY PLAT

PROJECT NO.	DRAWN	KLF	CHECKED	GJI
DATE SEPTEMBER 1, 2022	DESIGNED	CDM	APPROVED	GWC



SHEET 1 OF 2

SURVEYOR
CROSSROAD ENGINEERS, PC
115 N 17TH AVENUE
BEECH GROVE, IN 46107
PHONE: (317) 780-1555
CONTACT: GEORGE W. CHARLES
EMAIL: GWCHARLES@CROSSROADENGINEERS.COM

VILLAGES AT BROOKSIDE SECTION 16 SECONDARY PLAT

A PART OF THE NORTHEAST QUARTER (1/4) OF SECTION 23, TOWNSHIP 17 NORTH,
RANGE 5 EAST, VERNON TOWNSHIP, HANCOCK COUNTY, MCCORDSVILLE, INDIANA

DEDICATION CERTIFICATE

WE THE UNDERSIGNED, KS REAL ESTATE HOLDINGS, LLC, OWNER OF REAL ESTATE SHOWN AND DESCRIBED HEREIN, DO HEREBY LAY OFF, PLAT AND SUBDIVIDE SAID REAL ESTATE IN ACCORDANCE WITH THE WITHIN PLAT.

THE SUBDIVISION SHALL BE KNOWN AND DESIGNATED AS VILLAGES AT BROOKSIDE SECTION 16, CONTAINING TWO LOTS AND TWO BLOCKS, AND IS AN ADDITION TO THE TOWN OF MCCORDSVILLE. ALL STREETS AND ALLEYS SHOWN AND NOT HERETOFORE DEDICATED, ARE HEREBY DEDICATED TO THE PUBLIC.

BUILDING SETBACK LINES ARE HEREBY ESTABLISHED AS SHOWN ON THIS PLAT, BETWEEN WHICH LINES AND THE PROPERTY LINES OF THE STREET THERE SHALL BE ERECTED OR MAINTAINED NO BUILDING OR STRUCTURE.

THERE ARE STRIPS OF GROUND VARIOUS FEET IN WIDTH AS SHOWN ON THIS PLAT AND MARKED "EASEMENT", RESERVED FOR THE USE OF PUBLIC UTILITIES FOR THE INSTALLATION OF STORM SEWER, WATER AND SEWER MAINS, POLES, DUCTS, LINES AND WIRES, AND SIGNS SUBJECT AT ALL TIMES TO THE PROPER AUTHORITIES AND TO THE EASEMENT HEREIN RESERVED. NO PERMANENT OR OTHER STRUCTURES ARE TO BE ERECTED OR MAINTAINED UPON SAID STRIPS OF LAND, BUT OWNERS OF LOTS IN THIS SUBDIVISION SHALL TAKE THEIR TITLES SUBJECT TO THE RIGHTS OF THE PUBLIC UTILITIES.

THE MAINTENANCE OF THE STORM DRAINAGE SYSTEM FOR EACH LOT SHALL BE THE RESPONSIBILITY OF THE RESPECTIVE LOT OWNER AND SHALL INCLUDE BUT SHALL NOT BE LIMITED TO THE MAINTENANCE OF ALL INLETS, OPEN DITCHES, PIPES, SWALES, MANHOLES AND DETENTION PONDS. THE COST AND EXPENSE OF SUCH MAINTENANCE SHALL BE THE LOT OWNER'S RESPONSIBILITY.

THERE ARE STRIPS OF GROUND AS SHOWN ON THE PLAT LABELED INGRESS/EGRESS EASEMENT. THESE STRIPS ARE RESERVED FOR ACCESS, INGRESS AND EGRESS UPON, OVER AND ACROSS THE PRIVATELY OWNED AND MAINTAINED ROADWAYS AS SHOWN. NO PERMANENT OR OTHER STRUCTURE OF ANY KIND IS TO BE ERECTED OR MAINTAINED UPON SAID STRIPS OF GROUND.

THE FOREGOING COVENANTS, OR RESTRICTION, ARE TO RUN WITH THE LAND AND SHALL BE BINDING ON ALL PARTIES AND ALL PERSONS CLAIMING UNDER THEM (A 25-YEAR PERIOD IS SUGGESTED), AT WHICH TIME SAID COVENANTS, OR RESTRICTIONS, SHALL BE AUTOMATICALLY EXTENDED FOR SUCCESSIVE PERIODS OF 10 YEARS UNLESS CHANGED BY VOTE OF A MAJORITY OF THE THEN OWNERS OF THE BUILDINGS COVERED BY THESE COVENANTS, OR RESTRICTIONS, IN WHOLE OR IN PART. INVALIDATION OF ANY ONE OF THE FOREGOING COVENANTS OR RESTRICTIONS, BY JUDGMENT OR COURT ORDER, SHALL IN NO WAY AFFECT ANY OF THE OTHER COVENANTS OR RESTRICTIONS, WHICH SHALL REMAIN IN FULL FORCE AND EFFECT.

INVALIDATION OF ANY OF THE FOREGOING COVENANTS AND RESTRICTIONS BY JUDGMENT OR COURT ORDER SHALL IN NO WAY AFFECT REMAINING PORTIONS NOT SO AFFECTED.

THE RIGHT TO ENFORCE THESE PROVISIONS BY INJUNCTION, TOGETHER WITH THE RIGHT TO CAUSE THE REMOVAL, BY DUE PROCESS OF LAW, OF ANY STRUCTURE OR PART THEREOF ERECTED OR MAINTAINED IN VIOLATION HEREOF, IS HEREBY DEDICATED TO THE PUBLIC, AND RESERVED TO THE SEVERAL OWNERS OF THE SEVERAL LOTS IN THIS SUBDIVISION AND TO THEIR HEIRS AND ASSIGNS.

I affirm under the penalty for perjury that I have taken reasonable care to redact each Social Security number in this document unless required by law IC 36-2-11-15(d)

Daniel Koleszar

Daniel Koleszar

KS REAL ESTATE HOLDINGS, LLC

DATED:

9/24/2022

BY:

Keith White

KEITH WHITE, MANAGING MEMBER


STATE OF INDIANA)

) SS:

COUNTY OF Hancock

BEFORE ME, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE, PERSONALLY APPEARED KEITH WHITE, WHO BEING FIRST DULY SWORN BY ME UPON HIS OATH, STATED THAT HE IS THE DULY APPOINTED MANAGING MEMBER OF KS REAL ESTATE HOLDINGS, LLC, AN INDIANA LIMITED LIABILITY COMPANY, THAT HE IS DULY AUTHORIZED TO EXECUTE THE FOREGOING ON ITS BEHALF AND HE ACKNOWLEDGED EXECUTION OF THE FOREGOING.

WITNESS MY HAND AND NOTARIAL SEAL THIS 26th DAY OF September, 2022.



NOTARY PUBLIC:

Sherril Lynn Lutes

PRINTED: Sherril Lynn Lutes

MY COMMISSION EXPIRES: November 20, 2023

MY COUNTY OF RESIDENCE: Madison

VERNON TOWNSHIP BUILDING CORPORATION

DATED:

09/26/2022

BY:

Florence L. May

FLORENCE L. MAY - TRUSTEE

STATE OF INDIANA)

) SS:

COUNTY OF Hancock

BEFORE ME, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE, PERSONALLY APPEARED KEITH WHITE, WHO BEING FIRST DULY SWORN BY ME UPON HIS OATH, STATED THAT SHE IS THE DULY APPOINTED MANAGING MEMBER OF KS REAL ESTATE HOLDINGS, LLC, AN INDIANA LIMITED LIABILITY COMPANY, THAT HE IS DULY AUTHORIZED TO EXECUTE THE FOREGOING ON ITS BEHALF AND HE ACKNOWLEDGED EXECUTION OF THE FOREGOING.

WITNESS MY HAND AND NOTARIAL SEAL THIS 26th DAY OF September, 2022.



NOTARY PUBLIC:

Stephanie Crider

PRINTED: Stephanie Crider

MY COMMISSION EXPIRES: October 22, 2029

MY COUNTY OF RESIDENCE: Hancock

CERTIFICATE OF APPROVAL

MCCORDSVILLE ADVISORY PLAN COMMISSION

THIS IS TO CERTIFY THAT THIS PLAT HAS BEEN APPROVED BY THE MCCORDSVILLE ADVISORY PLAN COMMISSION THE 4TH DAY OF APRIL, 2021, UNDER THE AUTHORITY PROVIDED BY:

SIGNED

Devin L. Stetler

PRINTED

DEDICATION STATEMENT

THE RIGHT-OF-WAYS AS SHOWN WITHIN THIS PLAT ARE HEREBY DEDICATED TO THE PUBLIC FOR USE AS A PUBLIC STREET. THE SUBORDINATE USE OF SUCH RIGHT-OF-WAYS AS UTILITY AND DRAINAGE EASEMENTS AS PROVIDED HEREIN IS ALSO GRANTED.

ACCEPTANCE OF DEDICATION:

THOMAS R. STRAYER, MCCORDSVILLE TOWN COUNCIL PRESIDENT

SURVEYOR'S CERTIFICATE

I, GEORGE W. CHARLES II, HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR, LICENSED IN COMPLIANCE WITH THE LAWS OF THE STATE OF INDIANA. THAT THIS PLAT WAS PREPARED FROM A SURVEY PERFORMED BY MYSELF, DATE OF OCTOBER 8, 2019; LAST REVISED FEBRUARY 19, 2021 WITH INSTR. NO. 202211186. THE PROPERTY IS SUBJECT TO ANY OVERLAPS, GAPS, OR OTHER INCONSISTENCIES THAT SAID SURVEY MIGHT REVEAL.



GEORGE W. CHARLES II
INDIANA LAND SURVEYOR
No. LS 20800117
DATED: JUNE 11, 2020



DRAINAGE COVENANT

THIS SUBDIVISION IS SUBJECT TO ALL DRAINAGE SYSTEM DESIGN AND CONSTRUCTION STANDARDS OF THE MCCORDSVILLE SUBDIVISION CONTROL ORDINANCE, ALL OTHER APPLICABLE ADOPTED STANDARDS OF THE TOWN OF MCCORDSVILLE, AND THE REQUIREMENTS OF THE TOWN ENGINEER THAT PROVIDE FOR THE REPAIR AND MAINTENANCE OF THE SYSTEM.

DULY ENTERED
FOR TAXATION

SEP 26 2022

Debra A. Carnes
Auditor of Hancock County



PLAT DESCRIPTION

THIS DESCRIPTION WAS PREPARED BY GEORGE W. CHARLES II, LS20800117 FOR PURPOSE OF PLATTING. PART OF THE NORTHEAST QUARTER OF SECTION 23, TOWNSHIP 17 NORTH, RANGE 5 EAST, VERNON, TOWNSHIP, HANCOCK COUNTY, INDIANA, DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHEAST CORNER OF SAID NORTHEAST QUARTER; THENCE SOUTH 00 DEGREES 07 MINUTES 23 SECONDS WEST ALONG THE EAST LINE OF SAID NORTHEAST QUARTER A DISTANCE OF 1081.62 FEET; THENCE SOUTH 89 DEGREES 14 MINUTES 42 SECONDS WEST A DISTANCE OF 52.50 FEET TO THE PLACE OF BEGINNING; THENCE CONTINUING SOUTH 89 DEGREES 14 MINUTES 42 SECONDS WEST A DISTANCE OF 1373.38 FEET; THENCE NORTH 00 DEGREES 07 MINUTES 23 SECONDS EAST A DISTANCE OF 1016.91 FEET TO THE SOUTH BOUNDARY OF COUNTY ROAD 900 NORTH PER INSTRUMENT NUMBER 201904454, AS RECORDED IN THE HANCOCK COUNTY RECORDER'S OFFICE; THENCE ALONG SAID SOUTH BOUNDARY THE FOLLOWING FOUR COURSES: 1) NORTH 72 DEGREES 37 MINUTES 49 SECONDS EAST A DISTANCE OF 104.85 FEET; 2) NORTH 89 DEGREES 15 MINUTES 25 SECONDS EAST A DISTANCE OF 799.39 FEET; 3) SOUTH 85 DEGREES 01 MINUTE 57 SECONDS EAST A DISTANCE OF 100.50 FEET; 4) NORTH 89 DEGREES 15 MINUTES 25 SECONDS EAST A DISTANCE OF 350.59 FEET TO THE WEST BOUNDARY OF COUNTY ROAD 600 WEST PER INSTRUMENT NUMBER 2008303, AS RECORDED IN SAID RECORDER'S OFFICE; THENCE ALONG SAID WEST BOUNDARY THE FOLLOWING FOUR COURSES: 1) SOUTH 17 DEGREES 40 MINUTES 28 SECONDS EAST A DISTANCE OF 22.31 FEET; 2) SOUTH 00 DEGREES 07 MINUTES 23 SECONDS WEST A DISTANCE OF 229.66 FEET; 3) SOUTH 03 DEGREES 27 MINUTES 12 SECONDS EAST A DISTANCE OF 262.98 FEET; 4) SOUTH 00 DEGREES 07 MINUTES 23 SECONDS WEST A DISTANCE OF 522.91 FEET TO THE PLACE OF BEGINNING.

CONTAINING 32.722 ACRES, MORE OR LESS.

FLOODPLAIN INFORMATION

BY GRAPHIC PLOTTING ONLY, THIS TRACT OF LAND DESCRIBED HEREON LIES WITHIN ZONE "X" (AREAS OUTSIDE THE 500-YEAR FLOODPLAIN) AND IS NOT IN A SPECIAL FLOOD HAZARD AREA AS PLOTTED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP FOR HANCOCK COUNTY, INDIANA, COMMUNITY PANEL NO. 18059C00160, WHICH BEARS AN EFFECTIVE DATE OF DECEMBER 4, 2007.

BENCHMARK INFORMATION

ORIGINATING BENCHMARK

DESIGNATION - X 245
PID - KA0177
STATE/COUNTY - IN/MARION
USGS QUAD - BEECH GROVE (1980)

VERT. ORDER - FIRST CLASS II

DESCRIBED BY COAST AND GEODETIC SURVEY 1947

4.6 MI SE FROM INDIANAPOLIS
ABOUT 4.65 MILES SOUTHEAST ALONG THE NEW YORK CENTRAL RAILROAD FROM THE UNION STATION AT INDIANAPOLIS, AT 35-FOOT CONCRETE BRIDGE NO. 462 OVER LICK CREEK, SET IN THE TOP OF THE NORTHEAST WING WALL, 8 RAILS SOUTHEAST OF MILE POST 105, 4 RAILS NORTHWEST OF A LIGHT SIGNAL, 8.0 FEET NORTHEAST OF THE NORTHEAST RAIL AND 2.5 FEET BELOW THE TRACK.

ELEV. = 799.56 (NAVD 88)

TBM #400

CUT "X" ON WEST ANCHOR BOLT OF SIGNAL POLE, LOCATED IN SOUTHWEST QUAD OF "CR 900 N" AND "CR 600 W".

ELEV. = 850.90

DISCLAIMER WITH PRIVATE ROADS

"THE OWNER/DEVELOPER EXPRESSLY COVENANTS AND WARRANTS ON BEHALF OF ITSELF AND ALL FUTURE OWNERS OF LOTS WITHIN THIS SUBDIVISION THAT BECAUSE THE STREETS ARE PRIVATE THAT ALL MAINTENANCE, REPAIRS, AND REPLACEMENT NOW AND FOREVER SHALL BE UNDERTAKEN AT THE EXPENSE OF THE LOT OWNERS IN ACCORDANCE WITH THE TERMS AND CONDITIONS SET FORTH IN THE OWNERS ASSOCIATION BYLAWS AND ARTICLES. NO GOVERNMENTAL ENTITY HAS ANY DUTY OR RESPONSIBILITY TO MAINTAIN, REPAIR OR REPLACE ANY PRIVATE STREETS."

Document prepared by: Daniel Koleszar

Daniel Koleszar



VILLAGES AT BROOKSIDE SECTION 16 SECONDARY PLAT

PROJECT NO.	DRAWN	KLF	CHECKED	GJI
DATE SEPTEMBER 1, 2022	DESIGNED	CDM	APPROVED	GWG



SHEET 2 of 2


DIRECTORY PATH : R:\Active\BOC Realty\Villages At Brookside - Block A\Design\CAD\Deliverables
DATE/USER : 3/11/2024 4:20 PM / KJgg



TOPOGRAPHICAL NOTES

1. THIS IS NOT A BOUNDARY SURVEY.
2. UTILITIES ARE GRAPHICAL REPRESENTATION PER SURVEY AND MAPPING.
3. EXISTING INFORMATION ON LOT 1, BLOCK A REFLECTS DESIGN INFORMATION PER PLANS DATED FEBRUARY 19, 2021 WITH A LATEST REVISION DATE OF MAY 14, 2021. ACTUAL IN PLACE ELEVATIONS WILL NEED TO BE CONFIRMED BY CONTRACTOR.

EXISTING UTILITY SIZE AND MATERIAL INFORMATION SHOWN ON THESE PLANS ARE PER THE BEST GRAPHICAL AND VISIBLE INFORMATION AVAILABLE. CONFLICTS MAY EXIST AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL SIZING AND MATERIAL INFORMATION PROVIDED. IF ACTUAL CONDITIONS DIFFER FROM THAT INFORMATION SHOWN ON THE PLANS, THE CONTRACTOR SHALL, PRIOR TO THE INSTALLATION OF ANY PROPOSED INFRASTRUCTURE, NOTIFY THE DESIGN ENGINEER IMMEDIATELY.



TOPOGRAPHICAL SURVEY

BLOCK A

JOB No.	DRAWN	KLF	CHECKED	GWC
DATE	MARCH 11, 2024	DESIGNED	APPR.	GWC

SHEET

SHEET

McCordsville, Indiana

Town Standards

Directions for Use

- 1.) The entire set of full size drawings shall be attached to the construction drawings and shall be considered part thereto. A partial set may be used for small projects when whole sections are not applicable. Approval of use of a partial set will be made by the Town Engineer at the time of approval of the construction drawings.
- 2.) Details prepared by outside sources shall not be included in the construction drawings when the said drawings cover work which is covered by McCordsville Standards.
- 3.) Individual McCordsville Standards that do not apply may be crossed out by the design engineer through placement of a single large X over the detail. Minor reference notations may be placed adjacent to individual standard titles for coordination. However, the standards themselves shall not be modified in any way.
- 4.) Details prepared by outside sources covering work which is not covered by the McCordsville Standards are the sole responsibility of the design engineer and shall be placed on sheets other than the McCordsville Standards.


General Notes


- 1.) Contractor shall verify the exact location of all existing utilities at least 48 hours prior to any construction or excavation. All utilities shall be adequately supported to minimize damage. The contractor shall be responsible for repairing damaged utilities to the satisfaction of the Town of McCordsville and the owner of the utility.
- 2.) All benchmarks and elevations shall be from NAD 1983 (Conus) Datum. All coordinates shall conform with the Hancock County GIS standard.
- 3.) Wherever proprietary equipment is specified, all proposals for substitution shall be submitted in writing to the Town Engineer and shall be subject to the findings of the Town Engineer and may be appealed to the Public Works Committee.
- 4.) Whenever trench opening encroaches within 5 feet of an existing or proposed street or sidewalk, "B"-Borrow compacted in accordance with the most recent INDOT standard specifications shall be required. Approved backfill may be used under proposed sidewalks provided sidewalks are constructed six months after backfilling of the trench.
- 5.) Installation of or provisions for installation of all underground utilities (including service laterals) to be placed under pavement areas shall be established prior to the construction of pavements including lime stabilization.


Revision Log


Sheet No.	Sheet Description	Issued	Revised	Revised	Revised	Revised
SHEET 1	DIRECTIONS FOR USE, GENERAL NOTES & REVISION LOG	06/14/05	05/02/2023			
SHEET 2	RIGHT-OF-WAY SECTIONS & PAVEMENT SPECIFICATIONS	06/14/05	05/02/2023			
SHEET 3	RIGHT-OF-WAY DETAILS	06/14/05	05/02/2023			
SHEET 4	UTILITY LOCATION GUIDELINES	06/14/05	05/02/2023			
SHEET 5	DRIVE WAYS, SIDEWALKS, AND HANDICAP RAMPS	06/14/05	05/02/2023			
SHEET 6	STORM SEWER STRUCTURE DETAILS	06/14/05	05/02/2023			
SHEET 7	STORM SEWER BEDDING DETAILS AND GENERAL NOTES	06/14/05	05/02/2023			
SHEET 8	SANITARY SEWER SPECIFICATIONS	06/14/05				
SHEET 9	SANITARY SEWER DETAILS	06/14/05				
SHEET 10	SANITARY SEWER LIFT STATION STANDARDS & GUIDELINES	06/14/05	05/02/2023			

Town of McCordsville


THOMAS STRAYER TOWN COUNCIL PRESIDENT


GRANT ADAMS PUBLIC WORKS CHAIRMAN




TONYA GALBRAITH TOWN MANAGER


RONALD D. CRIDER PUBLIC WORKS COMMISSIONER

HOLEY MOLEY SAYS
"DIG SAFELY"



"IT'S THE LAW"
CALL 2 WORKING DAYS BEFORE YOU DIG
1-800-382-5544
CALL TOLL FREE
PER INDIANA STATE LAW IC8-1-26,
IT IS AGAINST THE LAW TO EXCAVATE
WITHOUT NOTIFYING THE UNDERGROUND
LOCATION SERVICE TWO (2) WORKING DAYS
BEFORE COMMENCING WORK.

REVISIONS				RECOMMEND FOR APPROVAL  <u>7/12/05</u> DESIGN ENGINEER DATE	TOWN OF McCORDSVILLE	SHEET 1 OF 10
REV. NO.	DESCRIPTION	DATE			DIRECTIONS FOR USE, GENERAL NOTES & REVISION LOG	
1	Various changes in red	4/18/2023				

LIME STABILIZATION

DESCRIPTION: This work shall consist of upgrading of mostly fine grained soils by uniformly mixing small amounts of lime (~~3 to 6%~~ **4.5%**) by weight to provide a working platform for the road subbase.

MATERIALS: Material shall meet the requirements of the Section 913 of the INDOT Standard Specification
Cement (3% by weight) may be used as an alternative.
LIME:

- a)High calcium or dolomite Hydrated Lime (Ca(OH)2 +Mg(OH)2) shall have a minimum of 90% total available calcium hydroxide content and the hydrates must contain no more than 5 % carbon dioxide content if sampled at the lime plant, or no more than 7 % if sampled at the job site.
- b)High calcium hydrated lime shall have a minimum available calcium hydroxide Ca(OH)2 content of 90%. The method used for determination of available lime shall conform to AASHTO T219-72 or ASTM C25.
- c)Maximum Mechanical Moisture content shall be 4%.
- d)Gradation: All hydrated lime shall conform to the following gradation requirement. At least 85% passing a #200 sieve (0.075 mm). Determination of particle size shall conform to the provision for wet sieving on ASTM C110.
- e) ~~Quicklime or Kiln dust shall not be used.~~
~~Other lime products such as quicklime - high calcium (CaO) or Dolomite (CaO- MgO) may be substituted with written approval by the Town Engineer. By product lime (kiln dust) shall not be used.~~

WATER: Water used for lime modification shall be in accordance with all applicable requirements of 913 and 913.01 of the INDOT Specifications, except that the minimum acceptable pH is 6.5.

STORAGE AND HANDLING

- a)Hydrated lime shall be stored and handled in closed weatherproof containers until immediately before distribution on the subgrade. Hydrated lime in bags shall be stored in weather protected conditions with adequate protection from ground dampness, and the facility shall be approved by the Town Engineer prior to commencement of any lime work.
- b)Each shipment shall be accompanied by a bill of loading and by a certificate of compliance stating conformance to the applicable specification requirements. The certificate of compliance shall be submitted to the Town Engineer prior to the proof roll on the subgrade.
- c)The Contractor shall take appropriate preventive and protective (safety) measure that shall be exercised by those working with this material. All safety measures shall comply with applicable OSHA requirements.

MIXTURE COMPOSITION:

- a)Mix Design: Lime will be proportioned within a range of 3 to 6 percent of soil (oven - dry basis). The required proportion of lime will be recommended by the Contractor and approved by the Town Engineer prior to construction using samples of soil and lime. The Town Engineer reserves the right to make such adjustments of lime proportioning as are considered necessary during the progress of the work within the range specified.
- b)Source or type of lime shall not be changed during the progress of the work without permission of the Town Engineer. However, the Town Engineer may choose to use different types of lime on different portions of the project, but shall not be mixed.

CONSTRUCTION REQUIREMENTS:

- a)Temperature and Weather Limitations: No lime modification shall be performed at a soil temperature less than 45 degrees Fahrenheit (7 degrees C) and the air temperature rising, of subgrade soil when it is measured 4" (100 mm) below the surface. Lime shall not be mixed with frozen soils or with soil containing frost.
- b)Preparation of Existing Roadway: All deleterious material, such as stumps, roots, turf, etc. and aggregate larger than 3" (75 mm) shall be removed. Any soft organic soils shall be removed as directed by the Town Engineer.
- c)Spreading of Lime: The roadbed shall be scarified or disked prior to distribution of the lime. The machine shall be of such design that a visible indication is given at all times that the machine is cutting to the required depth; The lime shall than be distributed uniformly over the surface by means of cyclone, screw-type, or pressure manifold type distributor. The Town Engineer may reject any procedure which does not provide even distribution of lime.

Lime shall not be applied when wind conditions are such that blowing lime becomes objectionable to adjacent property owners or creates a hazard to traffic on adjacent roadways.

The spreading of lime shall be limited to the amount which can be incorporated after mixing. In no case shall compaction be started later than three (3) days after mixing into the soil. In the event that rain intervenes causing cessation of work and exposure of the lime to washing or blowing, the Town Engineer may require additional lime to be spread.

- d)Mixing: The lime, soil and water (if necessary) shall be thoroughly blended by rotary speed mixers or a disc harrow. The mixing shall continue until a homogeneous layer of the required thicknesses has been obtained and clods are broken down so that 100 %, exclusive of rock particle, will pass a one-inch (25 mm) sieve and at least 60% will pass a 4 sieve (4.75 mm). The loose thickness of a single lime modified layer shall not exceed eight (8) inches (200 mm) if a disc harrow is used and fourteen (14) inches (355 mm) if a rotary speed mixer is used.
- e)Compaction: Compaction of the mixture shall begin as soon as is practicable mixing unless approved by the Town Engineer. If compaction is to be delayed, the surface of the lime modified soil shall be crown-graded and sealed by either blade dragging or light rolling immediately after mixing.


Compaction shall be continued until the Contractor has shown that the lime modified layer has a density not less than 100 percent within the special subgrade treatment zone and/or 95 percent below special subgrade treatment zone, of the maximum dry density.

The standard dry density of the lime treated soil shall be obtained by AASHTO 99. The field in-place dry density will be obtained by the Contractor in accordance with AASHTO T 191.


Aeration by means of further mixing, or the addition of water and further mixing, may be required by the Town Engineer to achieve the required compaction.

- f) Finishing: When compaction of the lime modified soil is nearing completion, the surface shall be shaped to the required line, grades and cross section, and compaction continued until uniform and adequate compaction if obtained.

The Town Engineer reserves the right to determine the actual thickness of the completed and cured layer by coring or other means at the owner's expense, and any deficient areas shall be acceptably corrected.



- NOTES
- 1.) 6" DENSE GRADED AGGREGATE (#53) SHALL BE 6" WIDER THAN ASPHALT
- 2.) PROVIDE A 2" SOFT SHOULDER AT 1/4" PER FOOT ALONG BOTH SIDES OF MULTI-USE PATH
- 3.) CONTACT THE TOWN ENGINEER WITH A MINIMUM 48 HOURS NOTICE TO SCHEDULE PROOF ROLL ON SUBGRADE



- NOTES:
1. HMA SHALL BE PRODUCED FROM AN INDOT CERTIFIED HMA PLANT, IN ACCORDANCE WITH INDIANA TEST METHOD (ITM) 583.
2. THE CONTRACTOR SHALL PROVIDE A COPY OF THE CERTIFICATION TO THE TOWN ENGINEER AT OR BEFORE THE INSTALLATION OF THE HMA.
3. PG BINDER MATERIAL (LIQUID) SHALL BE PG 64-22 FOR TYPE A AND TYPE B MIXES.
4. RECYCLED MATERIALS, UP TO 25%, MAY BE USED BASE. IF OVER 15% RECYCLED MATERIAL IS USED, PG BINDER 58-28 SHALL BE USED RATHER THAN PG 64-22

- LOCAL ROAD**
- d = 12"
- 1.5" ~~1.5"~~ HMA, TYPE A, 9.5 MM SURFACE
- 2.5" ~~2.5"~~ HMA, TYPE A, 19.0 MM INTERMEDIATE
- 3 4" COMPACTED AGGREGATE BASE #53
4" COMPACTED AGGREGATE BASE #2

- LOCAL COLLECTOR ARTERIAL ROAD**
- d = 15"
- 1.5" ~~1.5"~~ HMA, TYPE A, 9.5 MM SURFACE
- 2.5" ~~2.5"~~ HMA, TYPE A, 19.0 MM INTERMEDIATE
- 3 3" HMA, TYPE A, 25.0 MM BASE
- 4 4" COMPACTED AGGREGATE BASE #53
4" COMPACTED AGGREGATE BASE #2

- COLLECTOR ROAD**
- d = 18"
- 1.5" ~~1.5"~~ HMA, TYPE B, 9.5 MM SURFACE
- 2.5" ~~2.5"~~ HMA, TYPE B, 19.0 MM INTERMEDIATE
- 3 6" HMA, TYPE B, 25.0 MM BASE
- 4 4" COMPACTED AGGREGATE BASE #53
4" COMPACTED AGGREGATE BASE #2

PAVEMENT CONSTRUCTION

SCALE: NONE

PAVEMENT CONSTRUCTION

- 1.) Subgrade shall be lime stabilized per the lime stabilization specification on this sheet.
- 2.) Adequacy of existing subgrades shall be determined solely by the town based on a contractor performed proof roll with a fully loaded tri-axle dump truck. A proof roll shall be performed on all street subgrade prior to placing stone, under drains and installing curb. A second proof roll shall be performed on the stone prior to placing the asphalt base. The adequacy of the stone and subgrade shall be determined solely by the town.
- 3.) Place tack coat in accordance with the most recent INDOT standard specifications for asphalt pavement sections.
- 4.) Local ~~Arterial~~ **Collector** Road is defined as a low capacity and low speed roads within subdivisions whose function is to become a collector street for local subdivision traffic and move traffic from within the community to other locations in the community and to the existing county roads. Whether a street is defined as a Local Arterial Road is at the sole discretion of the Public Works Commissioner.
- 5.) Installation of or provisions for installation of all underground utilities (including service lines and laterals) shall be placed prior to the construction of pavement including lime stabilization.


6.) Paving of base and/or intermediate shall occur when temperatures are 32 degrees and rising. Surface paving of 1.5" or greater shall be when temperatures are 40 degrees and rising. Surface paving of 1" or less shall be when temperatures are 45 degrees and rising.

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	Various changes in red	4/18/2023



RECOMMEND FOR APPROVAL		7/12/05 DATE
APPROVED		7/12/05 DATE
APPROVED		7/12/05 DATE

TOWN OF McCORDSVILLE	SHEET 2 OF 10
TOWN STANDARDS RIGHT-OF-WAY SECTIONS & PAVEMENT SPECIFICATIONS	



UNDERDRAIN DETAIL
SCALE: NONE

STREET SIGN STANDARDS

All traffic and road name signs in and as a result of a major subdivision or a minor subdivision with newly constructed streets, shall be supplied and installed by the developer. The placement of the signs shall be as shown on the traffic sign plan that is to be submitted with the construction drawings. The traffic sign plan shall show the type of sign, size of sign, location of sign with dimensions and the streets to scale. A five (5) year maintenance bond shall be posted on the signs. The installer or developer shall notify the Town Engineer in writing when the signs are installed, so they can be inspected. Also include the date and time of installation of each sign. The plat shall not be recorded until the signs have been accepted.

TRAFFIC SIGNS

- 1.) Traffic signs shall be designed and installed to conform with the applicable requirements of the Indiana Manual of Uniform Traffic Control Devices, latest edition.
- 2.) No spliced sheeting unless acceptable by the Indiana Department of Transportation standard specifications, latest edition.
- 3.) Reflective sheeting for traffic signs shall be encapsulated lens (high intensity).
- 4.) Posts used for traffic signs shall be 3 lb. galvanized channel posts.
- 5.) Traffic sign height shall comply with the Indiana Manual of Uniform Traffic Control Devices, latest edition.
- 6.) Posts shall be installed with no less than three (3) feet of post in the ground.
- 6.) Backing material will be made of sheet aluminum.
- 7.) Bolts for mounting shall be 5/16" galvanized, stainless steel or plated carriage bolts.
- 8.) The number of posts for mounting and the minimum thickness or gage of sheet shall be as shown for the appropriate sign width:

WIDTH(inches)	NO. OF POSTS	THICKNESS (inches) ALUMINUM SHEET
Up to 24"	1	0.080
25" to 30"	1	0.080
31" to 60"	2	0.100
61" and over	2	0.125


STREET NAME SIGNS

- 1.) Intersections shall have one (1) road name sign for each street.
- 2.) All road name signs shall be made of an aluminum extruded blade.
- 4.) Reflective sheeting for road name signs shall be inclosed lens (high intensity), green in color.
- 5.) Letters and numerals for the road name signs shall be high intensity reflective sheeting, series B letters, and white in color.
- 3.) Posts used for road name signs shall be 2 lb. galvanized channel posts.
- 6.) Minimum height to bottom of sign for road name signs shall be seven (7) feet.
- 7.) Posts shall be installed with no less than three (3) feet of post in the ground.
- 8.) Material for posts shall be galvanized steel.
- 7.) Bolts for mounting shall be 5/16" galvanized, stainless steel or plated carriage bolts.




ROAD NAME SIGN DETAIL
SCALE: NONE


1. THE EXISTING PAVEMENT IS TO BE SAW CUT TO PROVIDE A CLEAN JOINT.
2. TRENCH SPOIL IS TO BE REMOVED FROM THE WORK SITE AND DISPOSED OF OUT OF THE RIGHT-OF-WAY AT A PREDESIGNATED APPROVED AREA.
3. FLOWABLE FILL IS TO BE POURED INTO THE TRENCH TO SERVE AS BACKFILL, TO THE DIMENSIONS AND SPECIFICATIONS LISTED IN THIS DETAIL.
4. THE ASPHALT PATCH IS TO CONSIST OF A MINIMUM OF 5 (FIVE) INCHES OF #8 HAC BITUMINOUS BINDER AND 1 (ONE) INCH OF #11 HAC BITUMINOUS SURFACE. IF THE EXISTING PAVEMENT IS THICKER THAN 6 (SIX) INCHES, ADDITIONAL BINDER IS TO BE USED TO MATCH THE EXISTING PAVEMENT THICKNESS. IN NO CASE IS LESS THAT 6 (SIX) INCHES OF ASPHALT TO BE USED.
5. THE EXISTING PAVEMENT IS TO BE TACK COATED PRIOR TO THE LAYING OF NEW ASPHALT. TACK COAT IS TO BE APPLIED AS SPECIFIED IN THE LATEST INDOT SPECIFICATIONS, SECTIONS 409 AND 902.
6. THE NEW SURFACE IS TO BE SLOPED AT THE SAME RATE AS THE EXISTING SURFACE.
7. A 2 (TWO) INCH WIDE BAND OF CRACK SEALANT IS TO BE APPLIED ALONG THE JOINT BETWEEN THE EXISTING AND NEW ASPHALT SURFACE. SEALANT IS TO BE APPLIED IN ACCORDANCE WITH INDOT SPECIFICATIONS, SECTION 305.
8. THE FLOWABLE FILL MIX IS TO CONTAIN, FOR EVERY CUBIC YARD OF BATCH MATERIAL, NO MORE THAN 50 LBS OF PORTLAND CEMENT, NO MORE THAN 500 LBS OF WATER.
9. THE COMPRESSIVE STRENGTH OF THE FLOWABLE FILL IS NOT TO EXCEED 100 PSI AT 28 DAYS.



ROAD CUT PATCH DETAIL
NOT TO SCALE




TYPICAL PAVEMENT TIE-IN
SCALE: NONE




(TYPE I)

2' CONCRETE ROLL
CURB & GUTTER
SCALE: NONE



(TYPE II)

2' COMBINED CONCRETE
CURB AND GUTTER
SCALE: NONE



CONCRETE CURB (BARRIER)
SCALE: NONE

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	Various changes in red	4/18/2023




RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
	DESIGN ENGINEER	DATE
APPROVED	<i>Ronald D. C. [Signature]</i>	7/12/05
	PUBLIC WORKS COMMISSIONER	DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
	TOWN COUNCIL PRESIDENT	DATE

TOWN OF McCORDSVILLE


**TOWN STANDARDS
RIGHT-OF-WAY DETAILS**

**SHEET
3
OF
10**



TYPICAL LOT UTILITY LOCATION
NOT TO SCALE

GENERAL NOTES:
1.) The location of proposed utilities as indicated hereon are based upon the orderly development of the land. Strict adherence to the indicated location is required. Requests to change the location of the proposed utilities shall be submitted in writing to the Public Works Commissioner. Utilities not meeting these requirements shall be removed and replaced as directed by the Public Works Commissioner at the owner's expense.




TYPICAL LOCAL ROAD UTILITY LOCATION
NOT TO SCALE


REVISIONS			<div>MARK J. WITSMAN REGISTERED No. 10100264 STATE OF INDIANA PROFESSIONAL ENGINEER</div>	RECOMMEND FOR APPROVAL		<div>TOWN OF McCORDSVILLE</div> <div>TOWN STANDARDS UTILITY LOCATION GUIDELINES</div>	<div>SHEET 4 OF 10</div>
REV. NO.	DESCRIPTION	DATE		DESIGN ENGINEER	DATE		
1	Various changes in red	4/18/2023		PUBLIC WORKS COMMISSIONER	DATE		
				TOWN COUNCIL PRESIDENT	DATE		

RESIDENTIAL DRIVES

- 1.) THE MAXIMUM ALGEBRAIC DIFFERENCE IN GRADE FOR ANY 10 FOOT INTERVAL SHALL NOT EXCEED 8% FOR CREST VERTICAL CURVES. NOR 10% FOR SAG VERTICAL CURVES.
- 2.) ALL LOTS SHALL DRAIN TO ADJACENT STREETS EXCEPT WITH THE PRIOR APPROVAL OF THE PUBLIC WORKS COMMISSIONER.
- 3.) CONCRETE DRIVES REQUIRE CONTROL JOINTS EVERY 10 FEET EACH WAY.




SECTION "A-A"




- 1. CROSS HATCHED AREAS SHALL BE EITHER 6" PLAIN CONCRETE OR 1" SURFACE ON 2" BITUMINOUS BASE ON 4" #53 COMPACTED AGGREGATE BASE, EXTENDING TO THE SIDEWALK OR R/W LINE WHICHEVER IS NEAREST TO THE ROADWAY.
- 2. SUBGRADE UNDER ALL SIDEWALKS AND DRIVES SHALL BE IN ACCORDANCE WITH SECTION 207.02 OF CURRENT INDOT STANDARD SPECIFICATIONS.
- 3. SIDEWALKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPROPRIATE STANDARD AND SHALL BE CONTINUOUS ACROSS THE DRIVEWAY. SIDEWALK SECTION ACROSS DRIVEWAY SHALL BE SAME THICKNESS AS DRIVEWAY WITH A 6-INCH MINIMUM.

RESIDENTIAL DRIVEWAY DETAIL


SCALE: NONE



SECTION "A-A"



SECTION "C-C"



HANDICAP RAMP CONSTRUCTION





SCALE: NONE


HANDICAP RAMP CONSTRUCTION

- 1.) All handicap ramps shall meet the requirements of the American Disabilities Act, the most recent INDOT standard specifications, and the Town of McCordsville's most recent standards. Curb modifications required for handicap ramps shall be provided at time of initial construction.
- 2.) Minimum width of curb ramp shall be 5 feet not including flares. Maximum slope of ramps and flares shall be 12:1.
- 3.) Handicap ramps are to be located as shown on the plans or as directed by the Public Works Commissioner.
- 4.) Ramps shall be provided at the centerline of radius at all corners of every street intersection where there is an existing or proposed sidewalk and curb. Ramps shall also be provided at walk locations at mid-block in vicinity of hospitals, medical centers, or athletic stadiums. The use of details contrary to those shown hereon shall require the prior written approval of the Public Works Commissioner.
- 5.) ~~Surface texture of the ramp shall be ramp grooves located 2" on center and 0.3" deep.~~
- 6.) Care shall be taken to assure a uniform grade on all ramps with no breaks in grade.
- 7.) Drainage structures shall not be placed in line with the ramps except where existing drainage structures are being utilized in the new construction. Location of the ramps shall take precedence over location of drainage structures.
- 8.) The normal gutter line profile shall not be maintained through the area of the ramp. Drainage inlets should be located uphill from the curb ramps to prevent puddles at the path of travel.
- 9.) Expansion joint for the ramp shall be a maximum 1/2" wide. The top of the joint filler for all ramp types shall be flush with adjacent concrete.
- 10.) Crosswalk and stop line marking, if used, shall be so located as to stop traffic short of ramp crossing.

SIDEWALK CONSTRUCTION

- 1.) Sidewalks shall be constructed of plain concrete four (4) inches thick except where crossing driveways where the sidewalk shall be a minimum of six (6) inches thick.
- 2.) Sidewalks shall be constructed on 2" of crushed stone or sand.
- 3.) Control joints shall be placed every 5 feet on center.
- 4.) Expansion joints shall be placed every 40 feet on center.
- 5.) Broom finish across the direction of travel and include a 1" steel trowel finish along both sides of the sidewalk and along either side of all expansion and control joints.

REVISIONS				RECOMMEND FOR APPROVAL		7/12/05 DATE	TOWN OF MCCORDSVILLE	SHEET 5 OF 10
REV. NO.	DESCRIPTION	DATE						
1	Various changes in red	4/18/2023						
				APPROVED		7/12/05 DATE	TOWN STANDARDS DRIVE WAY AND HANDICAP RAMP DETAILS	
				APPROVED		7/12/05 DATE		




- NOTES:
- 1.) MANHOLE CONFORMS TO A.S.T.M. C-478.
 - 2.) TONGUE AND GROOVE JOINT WITH MASTIC, BUTYL ROPE OR GASKETED PER ASTM C-443 AS REQUIRED.

MANHOLE TYPE	MANHOLE DIAMETER "F"	MAXIMUM PIPE SIZE	
		PIPE ENTERING / PIPE EXITING AT 0°-45° BEND	PIPE ENTERING / PIPE EXITING AT 45°-90° BEND
J	60"	36"	33"
K	72"	48"	36"
L	96"	54"	48"
M	102"	72"	66"
N	108"	84"	72"


STORM MANHOLES TYPE "J - K - L - M & N"

NOT TO SCALE



CATCH BASIN

NOT TO SCALE




- NOTE:
- 1.) MANHOLE CONFORMS TO A.S.T.M. C-478.


MAXIMUM PIPE SIZE	
PIPE ENTERING / PIPE EXITING AT 0°-45° BEND	PIPE ENTERING / PIPE EXITING AT 45°-90° BEND
24"	21"

STORM MANHOLES TYPE "C"

NOT TO SCALE



NOTE: ALL CASTINGS SHALL BE STAMPED "DUMP NO WASTE"



BEEHIVE GRATE CASTING WITH FRAME - NEENAH R-2560-E2

NOT TO SCALE

MANHOLE NOTES:

1.) Type "J, K, L, M & N" manholes as detailed hereon require a certain minimum depth. In cases where the depth of the storm sewer is not sufficient to meet the minimum depth as by the detail, "F" diameter manhole section may be used required by the detail, "F" diameter manhole section may be used throughout the depth of the manhole.

2.) Manholes shall conform to ASTM C-478. Joints shall conform to ASTM C-443. The use of cast-in-place concrete structures shall require the prior written approval of the Town Engineer. Regardless of the type of casting used, the casting shall be centered over the manhole steps.

3.) Manhole steps shall be made from a steel reinforcing rod encapsulated in a copolymer polypropylene resin. The manhole steps shall equal or exceed OSHA requirements manhole steps, PS1-PF as manufactured by M.A. Industries, Inc. Peachtree City, Georgia, or approved equal.

STORM SEWER TELEVISION:

1.) All storm lines 12" in diameter and greater upon completion and 3 months prior to the expiration of the maintenance bond shall be televised. Smaller lines may be required to be televised by the Town Engineer at his discretion if it is necessary to ensure proper installation and/or operation. The storm sewer shall also be jetted clean if necessary in the judgment of the Town's representative after observing the televising.

CASTING NOTES:

1.) Castings which drain combined curb and gutter, Type II curbing shall be Neenah R-3286-8V or Neenah R-3287-10V or as approved by the Town Engineer. Manholes shall not be used to drain combined curb and gutter, Type II curbing.

2.) Castings which drain roll curb and gutter, Type I curbing shall be Neenah R-3501-TR, or Neenah R-3501-TL or as approved by the Town Engineer. Manholes shall not be used to drain roll curb and gutter, Type I curbing.



3.) Castings for inlets which drain open pavement areas without curbing shall be Neenah R-3402-E or as approved by the Town Engineer.

4.) Castings for manholes which drain open pavement areas without curbing shall be Neenah R-2501 or as approved by the Town Engineer.

5.) Castings for use on inlets or manholes which drain swales or dry bottom detention basins shall be Neenah R-2560 or as approved by the Town Engineer.

6.) Castings for manholes which do not collect surface water shall be Neenah R-1772-A or as approved by the Town Engineer.

7.) All castings shall be stamped "DUMP NO WASTE".



NOTE: ALL CASTINGS SHALL BE STAMPED "DUMP NO WASTE"

R-3501-T(L&R) NEENAH CURB INLET FRAME, GRATE & CURB BOX DETAIL



NOT TO SCALE

CATALOG NO.	D	Wt. Lbs.
R-1772	25"	250
R-1772-A	25"	265

HEAVY DUTY

FURNISHED WITH PLATEN LID, SIMILAR TO R-1706-1

NOTE: ALL CASTINGS SHALL BE STAMPED "DUMP NO WASTE"



STORM MANHOLE R-1772-A WITH CONCEALED PICK HOLES

NOT TO SCALE

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	Various changes in red	4/18/2023




RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. C. Witsman</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE


TOWN OF McCORDSVILLE

TOWN STANDARDS STORM SEWER STRUCTURE DETAILS

SHEET
6
OF
10






NOT TO SCALE



NOT TO SCALE

NOTES: 1. MANUFACTURE OF END SECTION IS IN ACCORDANCE WITH THE
APPLICABLE PORTIONS OF A.S.T.M. SPECIFICATION C76.



RECOMMEND FOR APPROVAL	 DESIGN ENGINEER	7/12/05 DATE
APPROVED	 PUBLIC WORKS COMMISSIONER	7/12/05 DATE
APPROVED	 TOWN COUNCIL PRESIDENT	7/12/05 DATE

TOWN STANDARDS STORM SEWER BEDDING DETAILS AND GENERAL NOTES

SHEET
7
OF
10

GENERAL NOTES

- 1.) Sanitary sewer pipe of other material not meeting Town of McCordsville Standards shall require the prior written approval of the Town Engineer.
- 2.) The Contractor shall submit information to the Town Engineer showing conformance with these specifications upon request.
- 3.) Forty-eight (48) hours notice shall be given to the Town Engineer prior to the start of sewer construction and prior to any testing.
- 4.) The contractor shall be responsible for verifying that all state highways, city, and county permits have been obtained by the developer prior to start of construction.
- 5.) Backfill around all structures and all cuts under paved areas with B-barrow as defined by current INDOT specifications. Trenches opening within 5-feet of paved roadways shall be backfilled with B-barrow as defined by current INDOT specifications. Backfill under sidewalks shall be B-barrow; unless the walks are constructed a minimum of 6 months after backfill has been in place. The Town of McCordsville may require an analysis of the B-barrow to confirm its compliance with INDOT specifications at the contractor's expense.
- 6.) Water and sewer line crossings and separations shall be in accordance with 327 IAC 3-6-9.
- 7.) Trench shall be opened sufficiently ahead of pipe laying to reveal obstruction, and shall be properly protected and/or barricaded when left unattended.
- 8.) No water shall be permitted to flow into the sanitary sewer system during construction. The contractor shall utilize a pump to keep the water level below the pipe. Pump discharge shall be directed to a storm outlet in accordance with local, state and federal laws and regulations. Any pipe entering existing sewers shall be plugged with screw type mechanical, braced plug and tied in place until such time as all tests on the sewers have been completed and the lines have passed all punch lists.
- 9.) The contractor shall use a laser and target wherever possible to insure proper construction at the planned grade.
- 10.) The contractor shall provide measurements of the slope of the sewer for each manhole section as construction progresses. Such measurements shall be certified by a registered land surveyor or engineer and be available on-site for observation by the Town Engineer. No more than three manhole sections can be constructed in advance of such measurements.
- 11.) The contractor shall be required to furnish the developer's engineer with a set of prints, marked in red pencil, showing actual sewer location and invert, to include lateral location, depth and length. Such asbuilt prints must be received by the developer's engineer before the final contract payment can be authorized. The sanitary sewer laterals and stubs termination shall be indicated on the surface with a 2"x4" wood board or other appropriate marker set immediately above the said termination point.
- 12.) Record drawings shall be provided to the Town Engineer for review and approval. Once approved, two copies and electronic images of the approved record drawings will be provided. The electronic images will be in an acceptable format approved by the Town Engineer. A site plan in state plane coordinates compatible with the Hancock County GIS system will also be provided with the electronic files showing the property lines, easements, streets and right-of-ways and as-built locations of the sanitary sewer, storm sewer and water lines.

SANITARY SEWER PIPE

- 1.) Sanitary sewer pipe between 6 and 15 inches in diameter shall be SDR 35 PVC in accordance with ASTM D3034 and ASTM 2321. Sanitary sewer pipe buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic in accordance with ASTM D1784.
- 2.) Sanitary sewer pipe greater than 15 inches in diameter shall be either:
- a. PVC SDR 35 in accordance with ASTM D3034 and ASTM 2321. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic as defined in ASTM D1784. Sanitary sewer pipe buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034.
- b. Profile sewer in accordance with ASTM F949. The pipe and fittings shall have a minimum cell classification of 12454 in accordance with ASTM D1784. The joints shall be push-on bell and spigot type using elastomeric ring gaskets conforming to ASTM D3212 and ASTM F477. The pipe shall have a minimum stiffness of 46 PSI when measured in accordance with ASTM D2412. Profile sewer pipe is not permitted at depths 15 feet or greater.
- 3.) PVC sewer fittings shall be SDR 26 in accordance with ASTM D3034. Fittings in sizes through 8-inches shall be molded in one piece with elastomeric joints and minimum socket depths as specified in sections 6.2 and 7.3.2. Fittings 10-inches and larger shall be molded or fabricated in accordance with section 7.11 with manufacturers standard pipe bells and gaskets. Gaskets for elastomeric joints shall be molded with a minimum cross-sectional area of 0.20 square inches and conform to ASTM F-477 specification.
- 4.) The minimum slope for sewer acceptance by the Town of McCordsville are:
- | Size of pipe | Minimum constructed slope |
|--------------|---------------------------|
| 8-inch | 0.40% |
| 10-inch | 0.28% |
| 12-inch | 0.22% |
| 15-inch | 0.15% |
| 18-inch | 0.12% |
| 21-inch | 0.10% |
| 24-inch | 0.08% |
- In the event the contractor does not meet the minimum slopes, the sewer section and any other affected sewer sections shall be reconstructed to meet such minimum slopes.

SANITARY SEWER LATERALS OUTSIDE OF THE RIGHT OF WAY/EASEMENT

- 1.) Only approved contractors may install sewer laterals. Contractors must provide proof of liability insurance and a reference list for consideration to be added to the approved list.
- 2.) If working within an existing right-of-way, the contractor must obtain a right-of-way permit from the appropriate local jurisdiction.
- 3.) Contractors are responsible for obtaining all appropriate permits prior to construction. No deviations from the approved plot plan are permitted unless instructed by the Office of Public Works. Immediately notify the office of Public Works of any conflicts or discrepancies noted on the approved plot plan. It is the sole responsibility of the owner to ensure all contractors and subcontractors comply with the approved plot plan. A copy of the approved plot plan is to be provided to the Inspector at the time of inspection.
- 4.) The portion of the lateral installed from the right-of-way/easement to the building shall be inspected by the Office of Public Works prior to being backfilled.
- 5.) Lateral inspections shall be scheduled forty-eight (48) hours in advance with the Office of Public Works.
- 6.) A 6" diameter pipe Type I clean out shall be installed 3' away from building. A threaded plug shall be used to ensure the pipe is 100% watertight. For laterals greater than 100 LF as measured along the pipe, clean outs shall be installed at the right-of-way or property line or at 100 feet increments to provide access every 100 feet.
- 7.) Clean outs are not to be installed in sidewalks, driveways, or any other paved or unpaved traffic areas or pedestrian paths.
- 8.) All clean outs except within 3 feet of the building are to be Type II cleanouts.
- 9.) The connection of the building plumbing to the lateral shall be made with a fernco coupling within three (3) feet of the building before the cleanout except when the building has a basement. If the connection is made at the basement and there is not an adjacent slab or craw space, then a glued joint connection shall be made.
- 10.) The connection point shall not be made under porches or foundations.
- 11.) The fernco coupling shall be sealed watertight using steel band clamps. The piping on either side of the connection point shall be aligned and have no offsets or angles.

SANITARY SEWER LATERALS - GENERAL NOTES

- 1.) Laterals are to be constructed to the right-of-way/easement line and plugged tight with a braced plastic disc or cap capable of withstanding a low pressure air test without leakage. Only after the sanitary sewer has been tested and accepted by the Town Engineer is further installation of the laterals outside the right-of-way/easement permitted.
- 2.) Normal lateral slope is 1/4" per foot. Minimum lateral slope is 1/8" per foot. Any areas found not to comply with the minimum slope shall be removed and reinstalled.
- 3.) Lateral pipe shall be a minimum of 6" diameter and shall be SDR 35 PVC in accordance with ASTM D3034 and ASTM 2321. Laterals with any portion buried 15 feet or greater shall be SDR 26 PVC in accordance with ASTM D3034 to the terminus point either the right-of-way or easement line. PVC pipe shall have grooved bell and gasket. The pipe shall be made of PVC plastic conforming to ASTM D1784. Size and conformance shall be clearly labeled on pipe for inspection.
- 4.) All PVC sewer fittings shall be SDR 26 in accordance with ASTM D3034. Fittings shall be molded in one piece with elastomeric joints and minimum socket depths as specified in sections 6.2 and 7.3.2. Gaskets for elastomeric joints shall be molded with a minimum cross-sectional area of 0.20 square inches and conform to ASTM F-477 specification.
- 5.) All sewer laterals shall be bedded the same as the main line sewer. A minimum D/4 or 6-inches of compacted #8 stone under the pipe, 6-inches on either side of the pipe, and 12" above the pipe are required.
- 6.) Laterals are not to be installed under driveways.
- 7.) Full depth granular backfill is required for the lateral trench in areas within five (5) feet of drive ways, sidewalks or other traffic areas.
- 8.) Laterals are to be traced along the top of the pipe with a minimum size of 14 gauge wire from the wye to the clean out within three (3) feet of the building and extended above grade. The contractor will install the tracer wire utilizing a method does not require any splices in the tracer wire. The tracer wire will be mounted to the top of the pipe in at least three locations along each stick of pipe. Any splices that become necessary during construction will be sealed water tight.
- 9.) Laterals will be separated from water mains and water service lines by ten (10) feet when measured horizontally from the outside edge of the lateral to the outside edge of any existing or proposed water mains or water service lines except when crossing water mains or water service lines which shall be separated by eighteen (18) inches when measured vertically. Crossings must be at a minimum angle of 45 degrees.

SANITARY MANHOLES AND CASTINGS

- 1.) All sanitary manholes shall be precast concrete manholes in accordance with ASTM C-478 and section 720. O-rings shall conform to C-443. Kent seal or approved equal shall also be applied to all joints and between riser rings and castings. Manhole step spacing shall be no more than 16-inches.
- 2.) The casting elevations are set by plan. However, the castings are to be adjusted in the field by the Town's representative should a discrepancy occur between plan grade and existing grade. A new manhole ring and cover shall be installed to establish grade. Maximum height of adjusting rings from the top of the cone to the bottom of the casting shall be 12-inches.
- 3.) Butyl rubber coating shall be applied around each manhole joint from 6-inches above to 6-inches below each joint. The appropriate primer shall be applied prior to applying the double row of kent seal. Each manhole joint will then be wrapped four times with minimum 15 inch wide 80 gage (0.8 mil) polyethylene plastic stretch wrap. Inside joints to be filled with non-shrink grout or precoat plug material.
- 4.) The manhole chimneys, including all riser rings shall be sealed the same as the manhole joints. The butyl rubber and plastic stretch wrap shall extend over the flange of the casting.
- 5.) Manhole castings shall be East Jordan casting 1022-2 or approved equal with a heavy duty self-sealing lid stamped "SANITARY SEWER." Waterproof castings shall be East Jordan casting 1022-2 WT with a heavy duty lid stamped "SANITARY SEWER" or approved equal.

TESTING

- 1.) Manholes shall be air tested for leakage in accordance with ASTM C1244-93, standard test method for concrete sewer manholes by the negative air pressure (vacuum) test.
- a. Installation and operation of vacuum equipment and indicating devices must be in accordance with manufacturer's recommendations and performance specifications which have been provided by the manufacturer and accepted by the engineer.
- b. With the vacuum tester set in place:
1. Using a plate testing device, connect the vacuum pump to the outlet port with the valve open.
2. Draw a vacuum of ten (10) inches of hg. And close the valve.
- c. Accepted standards for leakage will be established from the elapsed time for a negative pressure change from ten (10) inches to nine (9) inches of mercury. The maximum allowable leakage rate for a four (4) foot diameter manhole must be in accordance with the following:
- Minimum elapsed time for a manhole depth pressure change of 1 inch hg
- | | |
|-----------------------|------------|
| 10 feet or less | 60 seconds |
| >10 feet but <15 feet | 75 seconds |
| >15 feet | 90 seconds |

For manholes five (5) feet in diameter, add an additional fifteen (15) seconds and for manholes six (6) feet in diameter, add an additional thirty (30) seconds to the time requirements for four (4) foot diameter manholes.

- d. If manhole joint sealants are pulled out during the vacuum test, the manhole must be disassembled and the joint sealants replaced.
- e. Manholes will be subject to visual inspection with all visual leaks being repaired.
- 2.) All sanitary sewer lines upon completion will be required to pass a low pressure air test. The test shall be conducted according to ASTM 1417-92, and witnessed by a representative of the Town of McCordsville. The testing shall be in accordance with Table 1. Add 0.5 psig for each foot of water above the sewer line being tested.
- 3.) Deflection tests shall be performed on all flexible" pipe after the final backfill has been in place at least 30 days. No pipe shall exceed a vertical deflection of 5% deflection test results. ("the following are considered non-flexible pipes: concrete pipe, ductile iron pipe, and cast iron pipe). The deflection test shall be performed with a nine-point mandrel. Proving rings shall be available.
- 4.) All sanitary sewer lines upon completion and six months prior to the expiration of the maintenance bond will be televised. The sanitary sewer lines will also be cleaned if necessary in the judgment of the Town's representative after observing the televising tapes.
- 5.) All testing shall be observed by a representative of the Town of McCordsville.

OIL/GREASE TRAP REQUIREMENTS




- 1.) All new commercial of industrial entities, which either generate and/or waste oil, grease or their by-products, shall construct a 1,000 gallon (minimum) grease trap. The design engineer shall submit detailed calculations for size justification of the trap. Calculations shall be accompanied with references, specifically denoted origin of sizing calculation method.
- 2.) Toilets, urinals and other similar fixtures shall not waste through the grease interceptor. All other waste shall enter through the grease interceptor, through the inlet pipe only.
- 3.) The grease interceptor and grease trap shall be sized such that it is easily accessible at all times for inspection/sampling and cleaning. The grease trap shall have a minimum of two (2) compartments with fittings designed for grease interception.
- 4.) The oil/ grease trap shall be located outside the building and at a distance far enough to allow soluble grease/oil to become insoluble.

SPECIFICATION TIME REQUIRED FOR A 0.5 PSIG PRESSURE DROP
FOR SIZE AND LENGTH OF PIPE INDICATED FOR Q=0.0015

1 Pipe Diameter (in.)	2 Minimum Time (sec)	3 Length For Minimum Time (ft)	4 Time for Longer Length (sec)	Specification Time for Length (L) Shown (min:sec)							
				100 ft	150 ft	200 ft	250 ft	300 ft	350 ft	400 ft	450 ft
8	3:47	298	0.760 L	3:47	3:47	3:47	3:47	3:48	4:26	5:04	5:42
10	4:43	239	1.187 L	4:43	4:43	4:43	4:56	5:56	6:55	7:54	8:54
12	5:40	199	1.709 L	5:40	5:40	5:42	7:07	8:32	9:58	11:23	12:49
15	7:05	159	2.671 L	7:05	7:05	8:54	11:07	13:21	15:34	17:48	20:02
18	8:30	133	3.846 L	8:30	9:37	12:49	16:02	19:14	22:26	25:38	28:51
21	9:55	114	5.235 L	9:55	13:05	17:27	21:49	26:11	30:32	34:54	39:16
24	11:23	100	6.846 L	11:23	17:07	22:49	28:31	34:14	39:56	45:38	51:21

REVISIONS		
REV. NO.	DESCRIPTION	DATE














RECOMMEND FOR APPROVAL	 DESIGN ENGINEER	7/12/05 DATE
APPROVED	 PUBLIC WORKS COMMISSIONER	7/12/05 DATE
APPROVED	 TOWN COUNCIL PRESIDENT	7/12/05 DATE

TOWN OF McCORDSVILLE

TOWN STANDARDS
SANITARY SEWER
SPECIFICATIONS

SHEET
8
OF
10




SERVICE CONNECTION FOR SHALLOW SEWERS
LESS THAN 15' DEEP

SERVICE CONNECTION FOR DEEP SEWERS (2 ALTERNATIVES)
15' DEEP AND OVER

NOTE:
1. ALL WORK SHALL BE IN ACCORDANCE WITH THE I.N.D.O.T. STANDARD SPECIFICATIONS. WHERE NO PROCEDURES FOR A PARTICULAR PORTION OF THE WORK ARE GIVEN, THE RECOMMENDATIONS OF THE HORIZONTAL EARTH BORING AND PIPE JACKING MANUAL OR THE AMERICAN RAILWAY ENGINEERING ASSOCIATION SHALL BE FOLLOWED.

REVISIONS		
REV. NO.	DESCRIPTION	DATE



RECOMMEND FOR APPROVAL	<i>Mark J. Witsman</i>	7/12/05
DESIGN ENGINEER		DATE
APPROVED	<i>Ronald D. Cramer</i>	7/12/05
PUBLIC WORKS COMMISSIONER		DATE
APPROVED	<i>Mark J. Witsman</i>	7/12/05
TOWN COUNCIL PRESIDENT		DATE

TOWN OF McCORDSVILLE

TOWN STANDARDS



SANITARY SEWER DETAILS

SHEET

9

OF

10



MATERIALS SCHEDULE				
INFLUENT SEWER I.D.	"A"	"B"	"C"	"D"
8"-10"Ø	19"	5"	13"	10"
10"-14"Ø	23"	5"	18"	10"
14"-18"Ø	27"	5"	23"	10"
18"-22"Ø	31"	5"	28"	10"
22"-26"Ø	35"	5"	37"	10"

- GENERAL NOTES
- Actual lift station dimensions, control settings, & pump selection to be indicated by the design engineer's certification sheet.
 - Pumps "A" and "B" shall be identical, centrifugal, submersible, solids handling, non-clog design capable of handling 3" sphere solids, fibrous material, sludge, and material found in typical raw sewage. Fit replaceable bronze wear ring to volute. Pumps shall be **Flygt**, Hydromatic or approved equal. Manufacturer shall warrant the pumps for five years after installation. **Barnes**.

All mating surfaces intended to be watertight shall be machined and fitted with nitrile rubber o-rings with sealing complete when metal-to-metal contact is made, resulting in controlled compression of o-rings without specific torque limit. Fasteners shall be 316 S.S.

Mechanical shaft seal system running in an oil reservoir shall have separate, constantly lubricated lapped seal faces. The lower seal unit between media and oil reservoir shall consist of one stationary seat and one rotating ring held in place by its own spring. The rotating seat ring and the stationary seat ring shall be made of Tungsten-Carbide. The lower seal shall be removable without disassembling the seal chamber. The upper seal between seal chamber and motor shall be of the same design with its own spring. Seals shall be maintenance free, but shall be easily inspectable.

The lift station control panel shall be stainless steel construction, NEMA 4X rating mounted on an aluminum pedestal. The control cabinet shall house the following controls and indication: Warning lights for each pump, Indicator lights, Common alarm, H-O-A switches, Silence button, Pump alternator, Warning reset buttons, Relays, Heater, Surge protection, Phase monitoring, Hour meters, and a GFI 110 volt, single phase convenience outlet. Lower seal failure alarm shall be engaged by seal failure sensor provided in the seal chamber, which senses water intrusion through lower seal. A mini-float in the motor chamber which signals pump shutdown and alarm upon water intrusion through upper seal may be acceptable when approved by Town of McCordsville.

Over temperature alarm and pump shutdown shall be engaged by heat sensor attached to the motor windings. Motor winding and stator lead insulation shall be class F with maximum temperature capability of 155 degree C. Housing shall be filled with High-Dielectric Oil. Air filled housing may be acceptable when approved by Town of McCordsville. Pump and motor shall be designed to operate partially or fully submerged in pumped media without the use of cooling jackets.

Rail system shall enable the easy removal of the pump without the need for a person to enter the wet well. A non-corrosive FRP I-beam or schedule 40 stainless steel guide rails shall be provided for each pump. The guide rail shall be supported at the bottom by the discharge elbow, aligned perfectly plumb and securely affixed to access frame. One intermediate guide rail support is required for each 9' of guide rail length.

- Check valve shall use packing material to seal the integral shaft or hinge pin. O-ring side plugs and O-ring shall not be used to seal integral shaft or hinge pin. Check valve shall be provided with bolted covers for easy access to the discs and shall be outside adjustable weight & Lever and shall be Clow F-5382 or approved by Town of McCordsville.
- Provide sufficient lift chain, float mounting cable, and pump power & control cable to enable non-spliced field adjustment. 304L stainless steel lift chain w/ 4:1 safety factor shall have a minimum workload limit of 1100 pounds. Pump power & control cables shall be suitable for submersible pump applications and this shall be indicated by a code/legend permanently embossed on the cable. Provide sleeve and pin on pump control cable and locate on bracket near hatch.
- Plug valve shall be hand lever operated and shall be Dezurik Fig. 118, Clow F-5412, or Town of McCordsville approved equal.
- Pressure gauge shall be Terrice Model 450 LFB or Town of McCordsville approved equal. Drill & tap run of pipe to install pressure gauge.
- Piping not within 2 feet of wet well and valve pit shall be DI Class 53, PVC ASTM D2241 SDR 21, PVC AWWA C900 or C905, or Town of McCordsville approved equal.
- Piping in and within 2 feet of wet well and valve pit shall be class 53 flanged ductile iron pipe.
- Piping, valves, and fittings in wet well and valve pit shall be factory primed Tnemec series 140 - 1211 to a dry film thickness of 5.0 to 11.0 mils and shall be field painted with Tnemec series 69 to a dry film thickness of 5.0 to 6.0 mils.

- Lift station and valve pit manholes shall be pre-cast concrete in accordance with ASTM C-478, with rubber gaskets equal to ASTM-443 with double row of 1/2" Hamilton Kent-Seal Extrudable Preformed Gasket material or Town of McCordsville approved equal. Exterior joints to have butyl rubber applied over the joint to a minimum of 1'-0" above and below the joint. Interior joints are to be sealed with non-shrink grout or precoat plug material.
- Valve pit shall be constructed on undisturbed soil or compacted granular material compacted with ½ inch nominal size to 95% standard proctor density.
- Horizontal projections from precast integral base and riser may be required to enable the weight of the vertical soil ring above the projection to resist buoyancy forces. See design engineer's certification sheet.
- Camlock flanged coupler and dust cap shall be used within valve vault. Camlock coupling and eccentric plug valve on by-pass line shall be 6" diameter with transition to force main size occurring with concentric reducer placed on top of base elbow. Fix operating nut for eccentric plug in vertical position to enable wrench operation from surface. Layout of all valve vault fittings and equipment to be based upon by-pass line being up close to hatch opening as shown.
- Aluminum hatches shall be Bilco, Halliday or Town of McCordsville approved equal. Leaf shall be ¼" aluminum diamond plate live load rated to 300PSF. Access frames and covers shall be 1/4 inch thick one-piece, mill finish, extruded aluminum frame, incorporating a continuous concrete anchor. All surfaces contacting concrete shall have a bituminous coating. Hatch shall be provided with type 316 S.S. hardware throughout, compression spring operators, automatic hold-open arm with release handle, and non-corrosive locking bar used in conjunction with a Town of McCordsville supplied padlock.

- Sewer connection to wet well shall be KOR-N-SEAL, A-LOK, DURA-SEAL, or Town of McCordsville approved equal.
- Force main penetrations of wet well shall be KOR-N-SEAL, A-LOK, DURA-SEAL, or Town of McCordsville approved equal.
- Automatic pump control system shall include all necessary items and appurtenances, which might normally be considered a part of a complete system. System shall be supplied by one manufacturer, shall be factory assembled, wired and tested, and shall be per complete electrical drawings and instructions. Major components and sub-assemblies shall be identified as function with laminated, engraved, bakelite nameplates. System shall be built in a NEMA 4X S.S. enclosure suitable for the specified horsepower and voltage of the pumps. The outer door of the panel shall be a hinged dead front with provisions for padlocking. Inside shall be a separate hinged panel to protect all electrical components, H-O-A switches, run lights, circuit breakers, etc., mounted such that only the faces protrude through said panel with no wiring fixed to said panel. The manufacturer shall warrant the control center for one year after installation covering 100% parts and labor.

Provide the services of a factory-trained, qualified representative to inspect, to adjust, and to place the system in trouble-free operation and to instruct the operating personnel in the proper operation and care of the system.

All major components of control center shall be available from local sources. Pump manufacturer shall accept the control center in writing to ensure unit responsibility and warranty.

Provide a disconnect switch housed in a separate NEMA 4X S.S. enclosure with external operation handle capable of being locked in the "on" position. Provide 480 volt, 200 amp, 4 wire weatherproof receptacle, Crouse Hinds AR204 or equal, to match plug on existing portable generator.

Provide a Omni-site.net Crystall WM housed within the NEMA 4X control panel.


An incoming power terminal block shall be located at the bottom of the control enclosure. A lightning arrestor shall be provided at the terminal block and connected to each line of the incoming side of the power input terminals. A single main fusible/breaker disconnect switch of adequate size to provide power for control, operation, and appurtenant components shall be provided. Provide a circuit breaker and magnetic starter with each leg manual reset overload protected for each pump. Starters shall have auxiliary contacts on 3Ø applications to operate both pumps simultaneously. Provide a circuit breaker and transformer to power the control panel with 1Ø, 115 volt service for all control functions. Provide a green "run" light and H-O-A switch to enable field connections.

Materials and installation of the required equipment grounding shall be in accordance with NEC section 250-83(c). All wiring shall have not less than 600 volt insulation. Wiring and buss shall be in accordance with NEC, state, local, and NEMA standards. All wiring shall be color coded.

Minimum 4" diameter, schedule 40 conduit shall be provided from wet well to control panel enabling pump power & sensor cables and float switch cables to be easily pulled. Seal conduit at control panel to prevent sewer gases from entering. All conduits, fittings, or connections shall enter from the bottom of enclosures.

Sump level rise to lead pump run float causes lead pump to operate. Lead pump operating and sump level falling to pumps off float causes lead pump to shut off. Lead pump operating and sump level rising to lag pump run float causes lag pump to operate. Lag pump operating and sump level falling to pumps off float causes both pumps to shut off. Sump level rise to high level alarm causes high level alarm to operate. An alternating relay shall be provided to cause pumps to alternate whenever pumps off float is de-energized. If one pump fails for any reason, the remaining pump shall operate upon sump level rise to lag pump run float. An hour meter shall be provided for each pump to record the elapsed operating time of each pump.

- Four manuals shall be presented to the owner, which shall include the following minimum information: 1) Operation instructions, 2) Maintenance instructions, 3) Recommended spare parts list, 4) Lubrication schedule, 5) Structural diagrams, 6) As-built wiring diagrams, & 7) Bill of materials.



REVISIONS				RECOMMEND FOR APPROVAL		7/12/05 DATE	TOWN OF McCORDSVILLE	SHEET
REV. NO.	DESCRIPTION	DATE						
1	Various changes in red	4/18/2023						
				APPROVED		7/12/05 DATE	TOWN STANDARDS SANITARY SEWER LIFT STATION STANDARDS & GUIDELINES	10 OF 10
				APPROVED		7/12/05 DATE		